



DELHI UNIVERSITY
LIBRARY

DELHI UNIVERSITY LIBRARY SYSTEM

Cl. No. 142.2 101

Date of release for loan

Ac. No.

Ac. No. 7 10 34 Date of release for loan 15 SEP 1978
This book should be returned on or before the date last stamped below.

An overdue charge of Six nP. will be charged for each day the book is kept overtime.

[illegible]

BUDDHIST ART IN INDIA.

TRANSLATED FROM THE 'HANDBUCH' OF
PROF. ALBERT GRUNWEDEL,
BY AGNES C. GIBSON.

REVISED AND ENLARGED
BY
JAS. BURGESS, C.I.E., LL.D., F.R.S.E., &c.,
Late Director-General of the Archaeological Survey of India.

WITH 154 ILLUSTRATIONS.

1974
BHARTIYA PUBLISHING HOUSE

BHARTIYA PUBLISHING HOUSE
B 9/45, PILKHANA VARANSI

Published by : Sh. V. S. Singh, for Bhartiya Publishing House
Varanasi & Printed at Delux Offset Printers, DELHI.
Processed by S. P. Sachdeva at Delux Process, 308/5,

BUDDHIST ART IN INDIA.

TRANSLATED FROM THE 'HANDBUCH' OF
PROF. ALBERT GRUNWEDEL,
By AGNES C. GIBSON.

REVISED AND ENLARGED
BY
JAS. BURGESS, C.I.E., LL.D., F.R.S.E.,
Late Director-General of the Archaeological Survey of India.

WITH 164 ILLUSTRATIONS.

LONDON
BERNARD QUARITCH
1901

PREFACE.

THE first edition of Professor Albert Grünwedel's handbook on *Buddhistische Kunst in Indien* appeared in 1893, and the hope was expressed in the *Journal* of the Royal Asiatic Society that the work might appear in English, as "it ought to be in the hands of all antiquarians in India." Believing that so important a publication might, by a few additions, form a useful general guide to the Buddhist sculptures in the museums alike of India and Europe, I have prepared the present edition. Miss A. C. Gibson very kindly translated for me the first edition; but by the time it was ready for the press, Prof. Grünwedel had begun his second edition containing extensive additions and alterations. This involved delay and a revision of the whole MS. Considerable additions have also been made to this translation, which have, partly at least, been indicated, and about fifty illustrations are added.

The difficulties in interpreting the Gāndhāra Buddhist sculptures arise chiefly from their fragmentary and unconnected condition. This has been lamentably increased by the ignorance or disregard of scientific methods on the part of the excavators of these remains. Monasteries and stūpas were dug into and demolished without regard to what might be learnt in the process by modern methods; the more complete fragments only were saved, without note of their relative positions or any attempt to recover smaller portions and chips by which they might have been pieced together; and the spoils were sent to various museums, often without mention of the sites from which they emanated. They were often further scattered at the will of excavators among different museums and private collections, and we cannot now place together the whole of the find from a single site, so as to compare the style,—and still less the order of the reliefs;—while, of the more carefully surveyed, such plans and sections as were made are defective, and without

explanatory descriptions. It is sincerely to be desired that, in future, the Government of India will prevent amateur excavations, and make sure that their excavators really know how such work ought to be executed.

To the "General-Verwaltung" of the Royal Museum, Berlin, I am very deeply indebted for the use of the whole of the illustrations in the second edition, and to Professor Grünwedel himself for others from *Globus* (3 Feb. 1900); he has also kindly looked over the proofs: and for these favours I would respectfully tender grateful acknowledgments.

To the Royal Institute of British Architects I am indebted for the use of illustrations 51, 55, 102, 103, and 104; and to Mr. W. Griggs for 35 blocks that had been prepared for papers on the Gāndhāra sculptures in the *Journal of Indian Art and Industry* (Nos. 62, 63, and 69).

With this manual in his hand, it is hoped, the visitor to any collection of Buddhist sculptures will find it no difficult task to understand their character and meaning. Much still remains to be added to our information; but it is only when complete delineations of the sculptures in various museums and private collections, on the Barahat fragments, and in the Kanheri, Elura, and other Baudhdha caves are made available, that we shall be able to interpret more fully the iconography of Buddhism. Towards this object some real progress has recently been made by the Government of India having ordered the photographing in detail of the Sāñchi reliefs and of the small collections of Gāndhāra sculptures in the Bombay and Madras museums.

JAS. BURGESS.

Edinburgh,
1st May, 1901.

CONTENTS.

CHAPTER I.—INTRODUCTION.

pp. 1-27.

Conditions of early Indian art development; influence of religion; art—sporadic rather than in schools, 1f. Chronological arrangement; remaining monuments, 2. Buddhist monuments of the Aśoka period; iconographic literature, 3.

Chronological table, 4-6. History of civilization and art history, 1f. The Āryas in the Panjāb, 6. The Vedic gods; Sakra in the Veda and in the Pāli texts, 7. No image in the earliest period, 7. Technical knowledge of the early Āryas indicated in Vedic literature, 7f. The spoked wheel; stone buildings; defensive works and stūpas; gold work, 7-8. The Āryans in the Ganges valley, 8f. The 5th century B.C.; Indians, Persians, Greeks, 8. The Persian power under the Achæmenians, 9. Buddha's teaching—the first world-religion; Hellenic culture, 9. Relations of the Achæmenians with India; Hindhū and Gandhāra as subject to the Persians, 9-10. Magadha and Kōśala, 10.

Religious influence in Indian art, 11f. Philosophy, metempsychosis, 11. The universal soul; Brahma and Ātma, 12. Deliverance, 13.

The Buddha, 13f. His birth; youth; the four signs, 13. Leaving home, as an ascetic, 13-14. The "enlightenment," 14. His death; the first and second councils, 15.

The Maurya dynasty of Magadha (Prasādi), 15f. Chāndragupta; Aśoka—his buildings and edicts, 15-16. Persian influence in India, 17. Aśoka's buildings, pillars, 17-18. Winged animals; conventionalized plants; native flora; lotus plant, 18-19.

The Classes of Monuments defined: Stambhas, Stūpas, Chaityas, Vihāras, Railings and Gateways, 20-21.

Two groups: the Indian, and Græco-buddhist or Gandhāra class, 21f. Lāṭis, rock-temples, &c., 22f. Barāhat; Gaya, 23. Sāñchi, 24. Amarāvati, 26. Influence of the Gandhāra school; Ajanta, 26-27. Early school of painting, 27.

CHAPTER II.—EARLY INDIAN STYLE

28-74.

Early Indian carving, 28f. Wood-carving transferred to stone; doors and throne-bark, 29. Decorative character of Indian art, 30. Goldsmith's work, 30-31. Jewellery and the human form, 31f. Nudity; physical development, 33. Mythical and foreign races; the Hindū type, 33-34. Dwarfs; drapery; women's garments and pose, 33-37. Gods and demigods; Jātikas, 37. Indra or Śakra, the thunder-god, 38. Brahmā; Māra; Devaputras; Śrī or Sīrī, 39. Lesser gods, Yakṣas; Śārya, 40f. Hybrid forms: the Naga (snake-demon), two types: the Ureus snake, and a man with snake hood over the head, and with a man's body, or with a snake's, 42f. Maṭsyamāras, 45. Yakṣas, guardians, 45-46. Winged figures, Kinnaras, devatās, 47f. Garuḍas, 48f. Garutmānt, 49. Parrot forms; Gryps, griffins, 50f. Tibetan dog and Chinese lion, Ton-ku, Thien-ku, 51f.

Tiryagyoni, 52. Indian animation of fantastic animal forms; throne and pillar decoration, 53. Sabbidāśvajātaka, 53f. Influence of art on Buddhist literature, 56f. Greek influence in certain forms: Makara (dolphin), hippocampus, centaur, pigmies, 57f.

Composition, 58ff. Processions to holy places; formal repetition; formal repetitions in the sacred texts, 58. Genre scenes in reliefs, 59. The Buddhist heavens, 60f.

The Kāśyapa legend in the reliefs on the east gateway at Sāñchi, 61f. The fire and water wonder at Uruvilvā, 62f. Successive scenes on one relief, 65. Accessories crowded in; the same also in the literature, 66. Buddha only indicated by a symbol, 67. Statues, 68. Intelligibility of the compositions, 68f. The association of reliefs on a monument, a guide to the interpretation, 69f.

Architraves of the east gateway at Sāñchi: the embassy to Ceylon of a Maurya king, 70f. Buddha's footprint, 71. Description of the reliefs, 72-74.

CHAPTER III.—THE GANDHĀRA SCULPTURES. 75-157.

Political history, 75. The Græco-Bactrian kingdom; Eukratides, Menandros, 76f. Intercourse between east and west, 78. Buddhist missions, 79. The Yuezhi or Indo-Skythians; Kanishka and council at Jālandhara, 79. Northern school of Buddhism, 80. Gupta dynasty in India, 80f. Manichæism, the Parakele, 81. Gandarioi and Indoi, 82.

Discovery of Gandhāra remains; their discussion, 82f. Chronological data and inferences, 83f. Resemblances with Italian art, 84. The Gandhāra school represents an offshoot of ancient art, but the materials are clearly Indian; in the northern class the forms are continued, 81f.

The types, 85ff. The Buddha type; Gautama as Buddha, 85f. The nimbus, 86. Types of the gods; Brahmā and Śakra, 87. The supposed Devadatta and Māra, 88. Various types of thunderbolt-bearers; bearded and unbearded heads of gods, 89. Śakra is re-named Vajrapāni, and attends on Buddha, 90. Vajrapāni in the Nirvāṇa scenes, 91. Māra rarely appears in Buddhist art, 92. Græco-I influenced the representations by their types, 93. Two figures with thunderbolts in one relief, 94. Śakra as a Yaksha, and Vajrapāni a Bodhisattva; Māra with bow and arrow, 95. Local divinities, guardians, 95f. Māra's army, 96-99. Earth-goddess; ancient Gē-type, 100f. Yakshas support the horse of the Bodhisattva, 102. Undetermined goddesses, 103. The type of the Japanese Ben-ten. Sarasvatī, 105. Nāgas, 106f. Nāgi and Garuḍa; the Ganymede of Leokhæres, 106f. Devadāsī; nāci girl standing under a tree, 111. Representation of Buddha's birth, 112.

The figure at the feet of the dying Buddha: perhaps Kāśyapa, 113f. The Brāhmanas, 113. Kings, women, Yavunānis, 116.

Artistic value of the Gandhāra school, 116. Mechanical reproduction of a series of complete types, 116. Early pattern compositions: the same continue in the northern schools, 117-118.

The composition, 117f. Replicas, e.g. of the birth, the flight from home, preaching scenes, the death (Nirvāṇa); represented in fuller and briefer form, 117-118. Representation of the Nirvāṇa in Gandhāra, Tibet, China, and Japan, 118-123; derived from ancient sarcophagus reliefs, 123. Combination of more than one model in the same panel (the old Indian scheme of successive scenes reappears) with equal-sized figures (of earlier art); with unequal figures (later art), 125-126. The Kāśyapa legend as a combined composition, 127; as a single composition; and in much abbreviated detail, 128; another combined relief; the leaving home, 129.

Stile composition: Buddha or a Bodhisattva in the centre with two attendants, 130. Decorative elements; pediments, 131f. Giganto-machia, 131; crouching Atlantes or Garuḍas, 135; pillar figures; tribute-bearers, 133-136. World-protectors, (Lokapālas) and art portraits, 136-137. Kubera and Virūḍhaka, 138.

Miscellaneous representations: two scenes connected with Buddha's birth, 138-139. Asita Rishi and the infant, 139; the bathing, 140; Buddha and an ascetic, 141. Śakra visiting Buddha, 142. The Dipankara Jātaka, 143. The sermon at Isipatana, 144. Feet-washing, 145. The *padma* presented, 145.

Iconic representative of the Mahāyāna system, 147. Large and small subordinate figures; Pañcika; garland-bearers, 148. Pedestal sculptures, 149f. Wheel symbol and trident, 151.

Architectural elements: Persian pillars; Hellenic capitals, 151f. Figures of Buddha in the capitals, 153. Gliding; model statues, 154.

Influence of the Gandhāra school on Indian art, 156f. Antiques in the Amarāvati sculptures, 157.

CHAPTER IV.—REPRESENTATION OF BUDDHA AND BODHISATTVA.

158-214.

Chakravartii, 158f. The seven jewels, 159. Apotheosis of Buddha; the greater and lesser beauty-marks, 160f. Bases of the Buddha figure and philosophic explanation of the ideal Buddha, 162f. The Buddha image modelled on the Apollo pattern, 163f. A double tendency,—an idealistic and a realistic aim with Indian degeneration of type, 166f. Indo-Baktrian art in China, Korea, Japan, 168f. Buddha with moustache, 169. Treatment of drapery, 169; Greek treatment of it persistent, 170. The sandal-wood statue of King Udayana, 170f. Legendary explanation of the Buddha figure, 171f. Buddha with bare right shoulder or covered, 172f; in Gandhāra, 173-174. Crowded Buddha figures in further India, 175. Various poses of the Buddha images, 176. Positions of the hands: the *mudrās*, 177f.

Previous Buddhas and their succession, 179f. The Tathāgata, 180. Maitreya, 181. The Bodhisattvas represented in royal apparel, 182; they belong only to the Mahāyana school; their probable genesis; relations to Hindū gods, 182f; their numbers and images, 184. How far the *mudrās* in the Gandhāra sculptures help to identify different Bodhisattvas, 185f. Modern representations of Maitreya, 186. Maitreya with a flask in Gandhāra, 187f. Buddha with *dharmachakra-mudrā*, 189. Kāśyapa Buddha, 189. The worship of Maitreya early developed; dominant in the Mahāyana school, 190.

Bodhisattva figures with lotus flowers, 191. Padmapāni; bears also the Amṛita flask; danger of confounding Avalokiteśvara with Maitreya, 192-194. The Dhyaṇi Buddhas, 195. Iranian elements; the Fravashis, 195. Repetition of Buddha and Bodhisattva images, 196f. Object of multiplied figures, 197. Adibuddha; colossal figures, 198.

The Lotus throne, 198. Two later Bodhisattvas: Mañjuśrī and Padmapāni, 199. The Dhyaṇas, 200f. Padmapāni and Kuan-yin, 201f. Litany of Avalokiteśvara, 203. Groups of figures: triads, pentads; immense pantheon, 204f.


Reaction, 205f. Lama portraits in Tibet, China, Japan, 206. Caricature in Japan, 207.

Decay of Art; artists handed down traditionally as Yakshas and Nāgas, 208. The national element manifested in repetitions of the same forms and in systematizing, 209.

Additional illustrations: the coffin of Buddha, and probable identification of Kāśyapa, 209f. A model of a shrine, 210f. Head of Buddha, &c., 211f. Conclusion, 212-214.

BIBLIOGRAPHY. 215.

INDEX. 219.



EARLY WORSHIP OF BUDDH'S FOOTPRINTS
AND THE BODHI TREE.
Pillar capital from Kanheri Caves,

BUDDHIST ART IN INDIA.

CHAPTER I.

INTRODUCTION.

THE artistic efforts of ancient India, specially of the early Buddhist period, are only slightly connected with the general history of art. From the very first two separate schools are met with—one of them, the older—(when the political history of the far East under the Persians had come to an end)—borrows Persian forms, and, indirectly, some Greek ones, and confined as it is to India, subsequently becomes the basis of all that may be called Indian art—Buddhist as well as Brahmanical. The other, which originated in the extreme north-west of India, depends on the antique art which expired when the Roman empire had accomplished its development of the Mediterranean nations: later it formed a basis for the hierarchical art of Central and Eastern Asia. No other reaction to the art of the West has occurred—the types developed on Indian soil are permanently found in the civilized world of India and Eastern Asia.¹ The religious character, so deeply rooted in the national life of the Indian races, has also continued the guiding principle in their art. In a critical examination of the monuments of ancient India, therefore, it is the antiquarian interest, connected with the history of religion and civilization, that is the most prominent.

The art of ancient India has always been a purely religious one, its architecture as well as the sculpture, which has always been intimately connected therewith, was never and nowhere employed for secular purposes. It owed its origin to the growth of a religion which has been called in Europe Buddhism from the honorary title of its founder—"the Buddha"—'the Enlightened one.'

The sculpture of ancient India, originating as it did in religious tendencies and destined to serve religious purposes, could only

¹ Conf. especially *Kuki Ryūichi*, 'The source of Japanese art,' *Hanrei Zasshi*, xii. 1, 1897, 10-13. The figurative part of Brahman art, so far as we are now acquainted with it, is based essentially upon Buddhist elements,—so much so indeed that the Saiva figures originated at the same time as the Northern Buddhist, appear to have fixed types, whilst the iconography of the Vishnu cult embraces chiefly Buddhist elements to which a different interpretation has been given. But still more dependent on Buddhism are the representations of Jaina art. How far this theory may be modified by the new excavations promised by Oldenburg (*Indoengja Samelli*, p. 350, and note 8) is for the future to decide.

follow its own immediate purpose in sacred representations: otherwise it was, and remained, simply decorative and always connected with architecture. In accordance with the Indian character, the sacred representations themselves were not so much the outset of the development as its end. According to the view of life prevailing among the Hindus, purely artistic execution never found scope in the existence of schools, but only in sporadic instances. The sacred figures themselves even came to be employed again decoratively.

Since the history of Indian civilization became better known in Europe, our previous ideas respecting the antiquity of Hindu art have been found to be very exaggerated. In fact, Indian art is the most modern of all Oriental artistic efforts. No important monument goes further back than the third century B.C. The period of its development comprises about a thousand years—from the third century B.C. to the sixth or seventh century A.D. In Asiatic countries, outside India, which subsequently embraced the doctrines of Buddha, ecclesiastical art is developed on the basis of Indian types until the middle ages (13th to 14th century). Till then the sculptures are executed in stone and frequently on a large scale, but gradually the Buddhist sculpture becomes a miniature manufacture in different materials—wood and clay in place of stone, and later, in metal casts—carried on as a trade.

Indian art, as already mentioned, borrowed from two artistic schools, complete in themselves, but of very different characters—the ancient Oriental, introduced through the Achæmenides, and the Græco-Roman; and the elements thus acquired it utilized for national themes. In its relation on one hand to the vague hybrid style of the Achæmenides whose influence, in the more ancient monumental groups of India, led to the introduction of certain Greek elements, the native Indian style, with its animated and powerful conceptions of nature, succeeded in preserving its independence and in developing itself up to a certain point. The introduction of early ideal types and the antique style of composition, on the other hand, resulted in a rigid adherence to consecrated forms, that is, to a canon.

Above all, stress must be laid on the fact that in comparison with the vast extent of the country, the monuments are far from numerous, that great numbers of them have been destroyed through the indolence or by the sheer Vandalism of men of other faiths, so that considerable monumental groups, in good preservation, remain only where the districts subsequently became deserted and the monuments were consequently forgotten and so saved from direct destruction at the hand of man; or where, as happened in Ceylon, the old religion remained and protected the monuments of olden times. It is therefore exceedingly difficult to represent a continuous development; the individual monuments appear as independent groups, the connexion of which can be sketched only in a general way. Add to this the difficulty of dating the separate monuments,

dependent on chance discoveries of inscriptions dated in eras that are not always sufficiently defined, inferences from the form of alphabet used, etc. It is true that in this domain new and important materials may any day be discovered. As concerns further the development of the artistic canon of the modern schools of Buddhism—which, on account of their valuable tradition, afford (as we shall see) a valuable source of information for the analysis of the subjects represented—as yet critical works thereon hardly exist.

In India itself, Buddhism has been extinct for centuries. The remains of the first golden age, under king Asoka, have for the most part perished: single monumental groups—gigantic heaps of rubbish, still testify to the time when Central India was quite covered with Buddhist buildings. But in the traditional forms of the temples still in existence outside India, we find highly important materials for an explanation of the old representations. Buddhist archæology must therefore begin with the investigation of the modern pantheon, especially of the northern schools, *i.e.* of the religious forms of Tibet, China, and Japan, so as to recognise the different artistic types, and trying to identify them with the ancient Indian. Combined with researches into the history of the sects and, above all, of the hierarchy, there must be a separation of the different phases from one another, and the earliest forms must be looked for to a certain extent by eliminating later developments.

The solution of many difficulties will be reached when the history of the different types of Buddhas and Bodhisattvas, gods and demons, &c., is traced. Unfortunately, however, the raw material required for this task has not yet, to any extent, been made accessible. But besides pictures and sculptures there is a class of literature, belonging especially to the northern school, that is of great importance to Buddhist archæology. The modern precepts for the manufacture of representations of Buddhas and Bodhisattvas—containing the dimensions and arrangement of the figure with the ceremonial rites to be performed, even to the animating of the figure by means of a relic, the opening of the eyes, and so on,—these, as well as the voluminous descriptions of the gods, found in the Tibetan Kanjur and especially in the Tan-jur,¹ with data as to

¹ Kanjur—written in Tibetan *dka-kyur*, the “translated word of Buddha”—is the title of the canonical literature of Tibet. In the Royal Library at Berlin is a handsomely executed MS. copy in 104-folios. Its richly decorated covers exhibit representations of the gods executed in gold and gay colours; all are named. It would be a meritorious and, for the history of the sects, an important task to compare these pictures with the contents of the volumes. The comparison of the illustrations of the Tibetan gods (*Pantheon des Tichananytscha Hutoku*, the five hundred gods of Ner-thang, &c.) with the *Buddha Pantheon of Nippon* published by Hoffmann, as well as with the Nepalese miniatures described by A. Foucher, would be another useful task. See Burges, *Gandhara Sculptures*, sep. repr., p. 18, or *Jour. Ind. Art*, vol. VIII, p. 40. The Tanjur, Tib. *dan-kyur*, literally “The translated doctrine,” forms to some extent the commentary to the Kanjur: the edition at Berlin is in 225 volumes (Nag-thang printing) and contains much material for the history of art. The Indian miniatures are of course more valuable than the Tibetan sources—and the Japanese tradition, which has in many cases retained the oldest forms, should not be overlooked.

the proportions of the figures, aureoles, attributes, &c., are authorities on Buddhist iconography. To these, as yet, little attention has been paid, but their importance must not be underestimated. Just as little known are the manuals on sorcery—the *Sādhanamāla*: they are important inasmuch as they prescribe for the exorcist the dress and attributes by which, according to the conceptions of the degenerate northern school, the Bodhisattva to be conjured may be propitiated: but these attributes are always the same as those of the deity himself.

In the following investigation an attempt will be made to retrace this retrograde path and to determine some of the principal types, on the basis of the materials now accessible, and to analyse the component forms. For this reason—although the investigation only concerns ancient Indian art—we shall frequently have to go beyond India, especially with a view to determine the types; for Tibetan and Japanese forms present highly interesting developments of Indian models. As an aid to understanding the summary of the history of the Buddhist religion, the following chronological table¹ may be found useful.

CHRONOLOGICAL TABLE.

B.C. 558-529.	Cyrus or Kurush of the Achæmenian dynasty took Babylon and founded the Persian Empire.
557	Probable date of the birth of Siddhārtha, or Gautama Sākya Muni, the Buddha.
528	Siddhārtha became an ascetic; assumed Buddhahood
500 BEFORE CHRIST.	
521-485	Darius Hystaspes (Daryavush Vishtasp) king of Persia.
514-486.	Bimbisāra or Srenika, king of Magadha.
486-461.	Ajātasmitta or Kāṇika, son of Bimbisāra, king of Magadha.
485-465.	Xerxes (Kshayarsha), king of Persia; Thermopylae, 480.
478	Virādha of Kosali exterminated the Sākya clan.
477	Parinirvāna or death of Sākya Muni; and first Buddhist Council at Rājagṛha.
400 BEFORE CHRIST.	
377	Second Buddhist Council (?), said to have been held at Vaisali in the 10th year of Kāśyapa.
326	Alexander of Macedon invaded India after conquering Persia and Sogdiana.
321-280.	Selenkos Nikator, in the partition of Alexander's empire, obtained Babylon, Syria, and Persia: Porus and Taxiles were allowed to hold the Panjāb.
315-291.	Chandragupta (Sandrikottos) founded the Maurya dynasty in India.
312	Era of the Seleukides, Oct. 1st.
305	Selenkos invaded Baktria and India; Megasthenes his ambassador.
300 BEFORE CHRIST.	
291-263	Bhindsara successor of Chandragupta; Deinakhos ambassador from Selenkos.
263-221.	Asoka, installed 269, third king of the Maurya dynasty.
256	Baktria revolted from Antiochos Theos under Diodotos or Theodotos who founded the Græco-Baktrian kingdom.
230 cir.	Arshakes founded the Parthian kingdom.
242	Third Buddhist Council held at Pāṭliputra; and missionaries sent to Ceylon, Gandhāra, Kashmir, &c.

¹ This table is an extension of that given by Prof. Grünwedel in the *Handb. d. Ind. u. Eur. Kunstgesch.*, pp. 166, 167, J. 1897.

CHRONOLOGICAL TABLE.

7

- 300 **BEFORE CHRIST**, continued
 220 Euthydēnos usurped Baktrian and extended the Greek power in India and Tartary.
 205 Antiochos III, Magnus, formed a treaty with Sophaganesos, an Indian prince.
- 200 **BEFORE CHRIST**.
 180 Eukratides extended his power in the Panjāb and Baktria.
 178 The Suŕga dynasty in India, founded by Pushyamitra.
 178 cir. The Andhrabhritya dynasty founded in the Dekhan.
 145 cir. Menander (or Milinda) of Sāgala in the Panjāb.
 110 cir. Probable date of Sāñchi gateways.
 130 Mithridates of Parthia overthrew the Greco-Baktrian kingdom.
 120 Baktria overrun by Skythians.
 110-88 cir. Dullak Gāmanī ruling in Ceylon.
- 100 **BEFORE CHRIST**.
 65 Syria became a Roman province.
 57 Samvat era of Malwa and Western India, Sept. 18th
 45 cir. The Buddhist doctrines first reduced to writing in Ceylon: the Dharmarūchika schism.
 80 The Kushana tribe of the Yueh-ti under Kozulo Kadphises subjugates Kabul.
- BIRTH OF CHRIST**.
 A.D. 80 cir. Gondophares or Gudaphara ruled west of the Indus or in Gandhāra and the Kābul valley.
 " " Gandhāra school of sculpture began.
 77 Ming-ti, emperor of China, received Buddhist missionaries.
 78 Kanishka the Kushan, king of North-Western India.
- 100 **AFTER CHRIST**.
 100 cir. Buddhist Council at Jālandhara, presided over by Vasumitra.
 107 Indian embassy to Trajan.
 180 cir. Nāsik Buddhist caves excavated.
 198 Indian embassy to Antoninus Pius.
 150-200 cir. Nāgarjuna, founder of the Madhyamika system, flourished.
 170 cir. Amarāvati stūpa rail; earlier caves at Kāsheri excavated.
- 200 **AFTER CHRIST**.
 226 Ardeshir-Bābegān of Parthia founded the Sāsānian dynasty of Persia.
 260 Valerian defeated by Shapur the Sāsānian.
 264 Odenathus of Palmyra repulsed Shapur; period of Palmyrene greatest prosperity.
 270 Manes flourished; Manichean heresy: he died 271.
 273 Defeat of Zenobia and fall of Palmyra.
- 300 **AFTER CHRIST**.
 319 Chandragupta I, of the Gupta dynasty crowned: Gupta epoch.
 360 Repulse of the Romans by Shapur II at Singara and Bezabza.
 371 Shapur II renewed the war against Rome and was defeated: died 379.
 372 Buddhism introduced into Korea.
- 400 **AFTER CHRIST**.
 399-414. Fah-hian, a Chinese Buddhist, travelled in India and Ceylon.
 401-414. Chandragupta II, Gupta king; inscriptions at Sāñchi and Udayagiri.
 420 Buddhaghosa of Ceylon, translator of the *Athakathā* and author of the *Pāuddhi Magga*.
 422 War between Bahārām or Varahrām of Persia and the emperor Theodosius.
 430 Kidāra Shahi established the kingdom of the little Kushans in Gandhāra, but they were expelled by the Ephthalites or White Huns, A.D. 470.
 468 Dutugemba, king of Ceylon, erected an image of Maitreya.
 472 Simha, the Buddhist patriarch, put to death by Mihirakula of Sāgala, who persecuted the Buddhists in Gandhāra.
- 500 **AFTER CHRIST**.
 518 Sung-yun, Chinese pilgrim, resided in Gandhāra.
 " The Buddhist *Tripitaka*, first collected in Chinese by Wu-ti.

500 AFTER CHRIST, continued.

- 520 cir. Vasubandha and Arya Asanga, Buddhist teachers in Gandhāra.
- 552 Buddhism introduced into Japan from Korea.
- 578 Bādāmī Brahmanical caves excavated.
- 591 Khusrū Parvīz restored to the throne of Persia by the emperor Maurice.

600 AFTER CHRIST.

- 606 Harshavardhana of Thānesvar epoch of his era.
- 609 Khusrū overran Syria and took Damascus and Jerusalem, 614
- 625 cir. Pulakesin II, the Chalukya king, received an embassy from Khusrū of Persia
- 629-635 Hsien Tsung, from China, travelled and studied in India.
- 632 Buddhism propagated in Tibet under king Srong-btsan-sgam-po.
- 631 Council held at Kanyakubjī under Harshavardhana
- 632-651 Yazdgerd, the last Sāsānian king, overthrown by the Muslims, 651.
- 639 Buddhism introduced into Siam
- 671-695 Li-tsing from China travelled in India and the Malay archipelago.

We may now attempt a very brief sketch of ancient Indian history. The civilization of the country is ascribed to the Arya race, a branch of the so-called Indo-Germanic family, which immigrated into the peninsula from the north-west and, in part, at once overcame the peoples settled there, and, after two thousand years' labour, compelled them, partly, to adopt their system of civilization. The Indian peninsula forms a world by itself, whose inhabitants, originally totally different, thus amalgamated into one whole; whilst in detail they represent all grades of social life from barbarism of the rudest kind to the most refined hyperculture. Entirely cut off from the outer world, this mighty land seems intended by nature to provide for its inhabitants a peculiar development with a sufficiently independent movement. From north-west to north-east the peninsula is sharply separated from North Asia by a mountainous range of prodigious height in the snow peaks of the Himālayas: only the Kābul passes on the Kābul river afford free communication with the north-west. This is the old high road by which the Aryans penetrated and which the conquerors of antiquity and of the Middle Ages also followed.

On the north-west frontier several large rivers come down from the western regions of the Himālayas towards the south-west, and flow through a broad, hot, and storm-beaten plain. This is the land of the Five Rivers, the Panjāb,—the first land that the Aryans possessed themselves of, when they conquered and penetrated into India (cir. 2000 B.C.?), while the Irānians, a people closely akin to them, directed their course to the nearer East. Other mighty rivers of far greater volume than those of the Panjāb also flow from the Himālayas, but towards the east. They traverse a vast, sandy, low-lying plain which owes to them its tropical vegetation. This plain is Hindustān proper—the cradle of ancient Indian civilization which, following thence the course of the rivers, advanced to their mouths. In the period which followed, the Aryans by degrees became acquainted with the coasts of the peninsula of the Dēkhan (Sanskrit: Dakṣiṇapatha—the path on the right), which lies to the south of Hindustān, and they also made

their way gradually into its interior—a high plateau rising towards the south. Notwithstanding the enclosed position of the Peninsula, extraneous influences have not been wanting; indeed, they operated only the more decidedly and perceptibly, the rarer they were.

To these foreign elements, which penetrated from the north-west, Indian art belongs in a very marked degree. The most important basis for the development of an independent art among any people lies in its religion. The gods of the 'Indian Aryans, when the race was still in the Panjâb, were personified nature forces of an unusually vague form. The old "ritual-poems" of this people, the *Rigveda*, gives us sufficient information as to this. The ever-recurring myth of the theft of the fertilizing Rain by malicious demons, which are then killed by the gods (*devas*), whereon the Rain is again set at liberty, and brings food, riches, and happiness, is, for example, ascribed to almost all the principal deities. The stolen Rain appears as "treasures," as "cows," as "Wet:" Milk or Water. The place whence the demons get these treasures is sometimes a bank of clouds, sometimes a mountain: in the language of these old poems, the words for clouds and mountains are confounded. In short, the world of gods merges into nature, so that the Vedic mythology, in common with other nature religions (*e.g.* the German), has an elementary and quite unplastic character. The Vedic idea indeed goes further: each individual god, unrestricted by the control of another deity, appears when the sacrificer calls upon him; for the sacrificer each is the chief god, in full possession of all the divine attributes. Thus it is difficult to define the peculiarities of the separate divinities; a development into fixed characters does not belong to this early period. But it is important in the history of art that in the thunder-storm all the principal figures fight against the demons. One is specially prominent in the *Veda*; it is Śakra (Pāli, Sakka), the god of thunder, and in the oldest Buddhist *Sūtras* also, he is almost the only deity of clearly pronounced type. Artistic representations of the very hazy figures of Vedic mythology were clearly impossible. The precise reduction to rule of the qualities, spheres of influence, and attributes of the Hindu gods, belongs only to the post-Buddhist period when, by the sanction of numerous popular cults, till then disdained, more defined figures appeared.

In Vedic times sacred representations were not required. As the offering of sacrifice strengthened the god,—made him capable of granting the desires of the suppliant,—it was the principal thing. On the strength of this idea a laboriously developed sacrificial ritual arose, which, when properly performed, could compel the god to the service of men. Of course, we meet with specimens of primitively artistic character: altars in the form of a *Garuda*, &c., without being able to form a clear idea of the architecture and plastic art of that early period. For the rest, from the Vedic poems we learn little of pictorial art. Some passages certainly, in

quite late poems may be regarded as speaking of idols, possibly belonging to domestic worship.

In the primitive period, the spoked-wheel is referred to as the grandest kind of work of the Vedic Aryans. And for primitive man, the construction of a spoked wheel does, indeed, betoken a vast stride forwards. In the *Rigveda* the wheel (with its spokes, of which "none is the last") and its form are favourite similes, and often executed representations. "The much-lauded Indra," (thus it says in the *Rigveda*, vii. 32, 20) "I incline by means of the song, as a cartwright bends the rim of a wheel made of good wood;" or (Śakra) "the lightning in his hand, rules over all men, as the rim of a wheel embraces the spokes" (*Rigv.* i. 32, 35). It would carry us too far to follow out all the similes; the wheel remains in the Indian civilised world of antiquity, and even down to modern times, as the symbol of occult power, the theme for grand poetical similes. The Buddhists took the wheel, as we shall see below, as one of the distinctive emblems of their religion.

As for stone buildings at that early age, we may at least suppose strong walls for defence and rough conical stone constructions over the graves of kings, which latter custom has been inferred from a study of the stūpa architecture to be discussed below. All buildings for secular ends were in wood, as they are in Indo-China and the eastern archipelago to the present day.

It should be mentioned that, in the early period of Indian civilization, rich and really quite artistic gold ornamentation was everywhere known.

Over-population, and perhaps also the crowding-in of other Aryan races, forced a portion of the Aryans to leave the Panjāb and follow the course of the rivers flowing eastwards. The close of the Vedic period shows us confederations of peoples opposing each other and bands of Aryans pouring into the valley of the Ganges, in the tropical climate of which a civilization is developed altogether different from that of the Vedic age in the Panjāb. The races left behind in the Panjāb have no share in this new period of civilization; from this time forward they go their own way, are considered by the inhabitants of Hindustan as kingless and excluded (*Arāśkīra*, the *Adraistoi* of the Greeks), but retain their full fighting powers.

The fifth century before Christ plays a decisive rôle in the history of the early peoples of the so-called Indo-Germanic race. The three nations that first left their impress on the history of mankind as civilizing powers of the noblest kind, were the Indian Aryans, the Irānians who hardly differed from them in dialect, and the Hellenes with their kindred races. We cannot here discuss the fundamentally different practical proofs of the national dispositions of these peoples; but it is important to mention that the essentially religious and philosophically disposed character of the Indian Aryans is met with again in the course of history among the

western peoples allied to them, and they derived from them faculties which the Indian soil could not have brought to maturity. At the end of the sixth century the Persians and Medes had laid the foundations of the first veritable empire of the ancient Orient—the empire of the Achæmenides. Darius, the son of Hystaspes, succeeded in recovering the conquests of the great Cyrus, and organizing them into a powerful state under Medo-Persian supremacy. With this the ancient history of the East closes its first period; the Persians become the heirs of all the previous currents of civilization which, under their rule, merge into one. In the course of the fifth century Greek freedom is developed in the struggles with the kingdom of the Achæmenides, and at the same time Greek culture attains its apogee. Now about the time that Pythagoras taught in Italy and before Socrates and Plato, Gautama Siddhârtha the "Buddha," the sage of the Sâkya race (Sâkyamuni) was preaching deliverance from transmigration. The ethical precepts based on his teachings were the first among the religions of the world to spread beyond the bounds of the nation where they had birth. When the strict preservation of the national element among the peoples of antiquity is considered, this fact is of distinctive importance.

A glance at the map shows India as the heart of the old world; in fact, the ideas that emanated from India, the elements of culture matured there, had been derived from outside, had been recast and transformed over and over again by an indescribably fertile imagination, sometimes indeed worked up even to extravagance, and in all these stages given out again broadcast to the world. In the rise of Indian studies, India was looked on as "the cradle of mankind," the "seat of primæval wisdom:" this was a mistake. Still in one's zeal to reduce everything to proper proportions we must not go so far as either to ignore or to minimise the immense importance of Indian life in the history of human culture.

Afterwards, the civilization of Athens became the foundation of all western culture; the religion of Buddha is the first universal religion, at least, for all countries lying east and north of India,—from the steppes of the Mongols and the mountainous wildernesses of Tibet, through Japan and far into the Indian archipelago.¹ A century and a half after the Buddha's death the Macedonian empire combined the states of Greece into a universal monarchy, which became the heir of the Achæmenides. The Hellenes formed

¹ It may be worth referring to Lucian Schermann's critique of Outenberg's *Buddha*, 3rd ed. 1897, in the *Deutschen Literatur-Zeitung*, Nr. 5, 1899, 84, 177ff. It is noteworthy that, in contrast with the zeal shown in representing Buddha's system as a mere parrot-like imitation of the Brâhmanical, it should not have occurred to anyone that all Brâhman philosophy works *pro domo*—for the Brâhman caste; and further that, amid the constant squabbles on purely religious questions, we forget the meaning of Buddhism in its bearing on the history of civilization. (Conf. *Zeitschr. f. Ethnologie*, 1897, V, 171). If Buddha were only an echo of the Brâhman, whence his success? He seems, however, to have been an uncommon personality:

the western frontier of this powerful kingdom; while on the east it was defined by the countries of north-western India first opened by Alexander the Great.

It is important in the history of ancient Buddhist sculptures to remember the political relations which prevailed between the kingdom of the Achæmenides and N.W. India. Darius (old Persian Daryavaush),¹ son of Hystaspes, was the first king of the dynasty regarding whose territorial acquisitions and explorations in India we have trustworthy information. After this king, in great measure through struggles with cognate peoples, had restored the empire of his famous ancestors and had prepared the way at least for its powerful organization, he attempted, as Herodotus says, "to explore large parts of Asia." One of these undertakings was the search for the mouth of the Indus,² whither, an expedition, under Skylax of Karyanda, was sent. In the later inscriptions³ of this monarch, the Hīndus (Hidhu) and the Gandhāras (Gadāra) are mentioned among the subject peoples. They are the tributary dwellers by the Indus (Sansk. Sindhu; Old Pers. Hindhu), and the Aryan inhabitants of Kābūl and that district, known in India as Gandhāra, in Herodotus the Gandarioi.⁴ Under Xerxes, the son and successor of Darius, the Hindhu and Gandhāra peoples belonging to the Arakhosian satrapy, still owed allegiance to the Persian king; Indian troops went to Greece with the great army, wintered with Persians and Medes under Mardonios in Thessaly, and sustained with them the defeat of Plataea.⁵ Later they seem to have regained some of their independence; still we know far too little about events in the east of the kingdom of the Achæmenides to be able to pronounce any judgment.

To return to India: in the fifth century B.C. we find the Indian Aryans, who had made their way from the Panjāb into the plain of the Ganges, divided into a number of kingdoms under Brāhman civilization. The most powerful of these states is the kingdom of Magadha; a rival state is that of Kosala, with its capital Srāvastī (Pali: Sāvatthī) on the Rāptī, in what is now the Nepāl Tarāī. Fierce feuds raged between these States and the neighbouring principalities tributary to them; the struggles against the original inhabitants had ceased long before. The system of caste is fully established. Side by side with the richly developed court life of the numerous great and small principalities—large fortified places are described—a luxurious city-life appears; trade flourishes, in the towns a vigorous industrial activity prevails. Along with

¹ Rawlinson's *Herodotus*, vol. III, p. 511, and *Jour. R. As. Soc.*, vol. XI, p. 185.

² Herodotus, Bk. iv. c. 41.

³ Behistun Inscrip. in Rawlinson's *Herodotus*, vol. II., p. 593, and *J. R. As. Soc.*, vol. X., p. 280; Nakhsh-e-Rustam inscr., *J. R. As. Soc.*, vol. X., p. 294; see also Lassen, *Indische Alterthümer*, Bd. I., Ss. 508f.

⁴ Herodotus, Bk. iii. c. 91; vii. c. 66.

⁵ Herodotus, Bk. vii. c. 65; viii. 113; ix. 31.

this is a frugal peasant-class much left to itself—the real basis of Indian national life at all periods of Indian civilization. Religion is entirely in the hands of the Brāhmans; a laboriously constructed sacrificial ritual has sprung from the ancient Indian Nature-worship. The Brāhmans alone are in possession of this ritual, and through the sacred power of their sacrifices they can put a curb on the warrior nobles who are always at strife. The forms of worship of the other castes, especially of the common people, were quite left to themselves. In this way a popular worship, which becomes gradually more refined in proportion as the caste is higher, is everywhere found side by side with the official religion of the “gods in human form,” *i.e.* the Brāhmans. In the great sacrificial festivals of the princes the people participated at most as spectators; the domestic rites, the *Pūjā*, were a repetition on a smaller scale of the official ceremonies. Every village had its sacred fig-tree which was supposed to be the abode of a god, to whom gifts (food, flowers, etc.) were brought (*balikammam kar*). The whole structure of Indian life is permeated by a deep religious character, which, without being called forth by exterior pressure, is the result of their condition. Whilst in the luxury of the cities a tendency towards pessimism makes itself felt, the people do not feel so much the need of an organised Nature-religion. The want of national feeling, the enervating influence of the climate, the contrasts between rich and poor, the exclusiveness of the State-worship, may have been the basis of this religious impulse. The caste system, which had been built up to keep the Aryan blood pure and to prevent intermarriages, was inimical to all true national feeling; for the Indian, indeed, the caste system embraced the whole world. One who had no caste was of no account, and thus was no worthy adversary. The contrasts between poor and rich had a different effect in India from that produced elsewhere. In a land where Nature provides everything, and a handful of rice suffices to sustain life, the tendency is to shake off the worries of civilization and to return to Nature itself. But the degree of civilization to which the nation had attained even in the Panjāb had penetrated so deeply, at least among the upper castes, that a relapse into barbarism was in consequence impossible. This return to the simple life which the tropical wilderness afforded was prescribed for the Brāhmans. We see them in their retreats occupied in solving the enigma of life and, if the answers they found rightly seem pessimistic to the European, it cannot be denied that the intense moral earnestness of the whole movement, which proceeded from the wisest heads in the nation, effected a magnificent development of the theorems themselves. The interrogations astounded by their boldness, the answers by their inexorable logic.

The doctrine of the transmigration of souls—really only a further development of the caste system—held out the possibility of winning a better reincarnation. But the chief aim was how to

escape being reincarnated at all. Stated as briefly as possible, the concatenation of ideas was much as follows: The Nature-gods of ancient times could be forced by means of rightly performed sacrifice to grant what was asked. In this way the attempt to conceive of the origin of the world as independent of the gods (*i.e.* without a real creation) may be explained. The World-Soul, that is, the Brahma, is recognised as the fundamental substance from which all individual souls (*âtman*) emanate in order ultimately to return to it, after freeing themselves from any corporeal vestment. Now the union into which the individual soul, emanating from the Brahma, enters in its embodiment (the one being eternal like the other), brings it into bondage; for, through the embodiment, it becomes conscious of its own personal individuality and begins to act: but every action tends to good or evil, reward or punishment, joy or sorrow. According to what these actions are, the soul, after its separation from the body, passes through heaven and hell, and when reward and punishment are there exhausted, it returns once more to a bodily existence, and, according to the sum of its previous actions, is born again as Brâhman, god, human being of high or low caste, animal, plant, or mineral, to re-enter the cycle (*samsara*) of transmigration. Now in the choice of the means of escaping from this cycle to freedom and re-union with the All-Soul the schools differ. But the fundamental idea remains in all the ancient Indian forms of religion, and down to modern times. Not only, however, do the Brâhmans give themselves up to these speculations in their schools; at kings' courts these matters are discussed; rich citizens take part in the movement, and, side by side with professional monks of the first rank, schools of monks and ascetics are developed, composed of members of the other castes. The Brâhmans themselves, quite in the middle of the movement, were far from being, on principle, opponents of new schools of philosophy. The opposition of these new sects to the official doctrines gradually became very marked and showed itself clearly in the fact that the heterodox disdained to quote examples and proofs for their theorems from the Vedic literature. In India, diametrically opposed religions have always treated each other with a tolerance which would be quite inconceivable in other lands.

It need scarcely be mentioned that the condition of things thus indicated was not calculated to promote the growth of a powerful national art. The efforts of ancient Indian civilization were confined to the domain of the intellectual; their fundamental character was speculative, although their expression might point to aims of a religious and mystical, or philosophical and scientific character. Though a religio-mystical element may serve as a scanty foil for fully perfected or decadent artistic efforts, the philosophical-scientific tendency, especially with the practical side which it had in ancient India, is an altogether barren soil for art.

Deliverance from reincarnation was sought for in different ways; different sects arose which did not, however, take up an attitude of conscious opposition to the Brāhman religion. The pressure from without, the heavy taxation, the bloody wars between the different states may have combined to attract proselytes to the religious sects. But the fact that the founder of Buddhism was himself a prince, refutes the idea that exterior pressure played the leading rôle. For even if the legends exaggerate, it cannot be doubted that Buddha came of a powerful and opulent family.¹

At the foot of the Himālayas to the north of Gorakhpur, on the river Rohinī (i.e. Kohān) a tributary of the Rāptī, was the town and domain of Kapilavastu (Pāli, Kapilavatthu)² which belonged to the Sākya family or clan. In the sixth century B.C. this principality belonged to Suddhodana, and was at constant feud with its next neighbours the Koliya (Pāli, Koliya) clan, dwelling on the east of the Rohinī. To the chief of Kapilavastu, who had wedded two sisters—Māyā and Prajāpatī,—there was born a son who received the name of Gautama Siddhārtha (Pāli, Gotama Siddhattha).³ The legends further relate how the child was recognised by the old Brāhman ascetic Asita as the coming Deliverer, and how the young prince surpassed all his companions of his own age in bodily strength and mental capacity. To terminate peacefully the old feuds with the Koliya, the young prince was betrothed to the Koliya princess Yasodharā, and maintained a brilliant court.

Once, as he drives out, a god appears to him four times—as an infirm old man, as a sick man, as a corpse in a state of decomposition, and as an ascetic (freed from human wants). This sight and the explanations which Gautama receives from his coachman, Chhandaka, raise in him the first thoughts of determination to renounce the world. After a son, Rāhula, has been born to him he carries out his resolve. He parts from his sleeping wife, and flees from the well-guarded palace.

A canonical text (*Avidūreniddna*) describes⁴ the flight from the palace thus: "Gautama lays himself down upon a magnificent couch. Immediately his women-servants, beautiful as goddesses, skilled in the dance, in song and in music, and decked with rich

¹ The earliest traditions represent Suddhodana as only one of the great and wealthy landowners of the Sākya race,—not as a king. Oldenberg's *Life*, Hoey's transl., pp. 99, 416; Rhys Davids, *Hubert Lect.*, p. 126; Copleston, *Buddhism*, p. 20. Apart from this, little that is certain is known about Buddha's family circumstances; even the name of his wife Yasodharā, "Rāhula's mother," is reconstructed; conf. Rhys Davids, *Buddhism*, p. 50.

² Buddha's birthplace has now been found; see Oldenberg, *Life of Buddha*, Hoey's transl., pp. 92, 105, 415; *Jour. R. As. Soc.*, 1898, p. 580; and the critique mentioned above note 1, p. 9; G. Buhler, *Anzeig. K. Acad. Wiss. Wien*, 1897, ss. 219ff; *Epig. Ind.*, vol. V, p. 1; and conf. *Or. Bibliog.*, Bd. XI, 1, 1898, S. 61. Nrs. 1257-8; 2, ss. 218f., Nrs. 4129, 4149-52, &c.

³ Siddhārtha of the Gautama gotra or priestly family. By caste he is described as a pure Kshatriya.

⁴ Rhys Davids' *Buddhist Birth Stories*, pp. 80-82.

ornaments, ranged themselves in order and began to dance, sing, and play on their instruments to please him. But Gautama, whose mind was already turned away from the delights of the world, paid no heed to the dance and fell into a slumber. Then the women said: 'What shall we play, when he for whose pleasure we perform is gone to sleep?' Then they laid aside their instruments where they had taken them up, and lay down. Only the lamps, fed with fragrant oil, continued to burn. Then Gautama awoke, and leaning on his arm on the couch, he saw the women lying sleeping after they had flung aside their instruments. Spittle ran out of the mouths of some, others were grinding their teeth, others snoring, others again muttering in their sleep, or lying uncovered and with open mouths. This repulsive sight rendered him still more indifferent to the charms of sense. 'Oh, horrible! disgusting!' he cried, and thought seriously about adopting a life of solitude. Thereupon, with the words, 'This is the day of separation from the world,' he rose from his couch and went to the door, calling his charioteer. Before fleeing with Chhanna, he thought, 'I will just look at my son,' and rising, he went towards the apartments occupied by Râhula's mother and entered her chamber. Râhula's mother lay sleeping on a couch decked with flowers; her right hand resting on the head of the child. Gautama remained standing on the threshold and looked at them; he thought if he removed his wife's hand he would wake her, and that thus his movements would be impeded; if he became Buddha he would come again and see his son; then he left the palace."

With Chhanna he fled in the night to the river Anomâ or Anavamâ; there he gave to the faithful coachman his weapons, his ornaments and his horse, exchanged clothes with a beggar, and, living on alms, hastened to Râjagriha, the capital of the kingdom of Magadha. In Râjagriha he studies Brâhman philosophy, but dissatisfied with this, he retires to the Uruvilvâ (Pâli, Uruvelâ) forest, where the temple of Buddha-Gayâ now stands. There he submits to the severest privations, till he sees the folly of attempting to obtain enlightenment by enfeebling the body. The legend proceeds to describe the mental struggles through which Gautama passed under the fig-tree at Gayâ as a victory over creatures of a diabolical nature, which Mâra, "the Evil One," the demon of passion, had sent against him. In a following chapter this struggle against Mâra's seductions will be more fully noticed.

From the place where he obtained enlightenment, on the diamond throne (*vajrâsana*), under the "tree of knowledge" (*bodhi-druma*), he hastened back to the world to proclaim the way of salvation—victory over self and love towards all creatures. First of all, he converts some merchants; then Brâhmins and people of all ranks. From among those who were willing to follow him as disciples there arose by and by a body of monks (*bhikkhus*), clad in yellow and shaven, who became the foundation for the later

monasticism. A Christian traveller of the 13th century, the Venetian Marco Polo, says of Buddha,¹ after narrating pretty correctly the story of his life: "If Buddha had been a Christian, he would have been a great saint of our Lord Jesus Christ, so good and pure was the life he led." This is a significant judgment at a time when religious tolerance was certainly not great.

During the forty-five years which Buddha journeyed about in Behâr, we see him vigorously supported by the royal courts; and his followers increasing; still Buddha's doctrines do not yet seem to have been received as a separate religion. In the year 477 B.C. (probably), in the grove of the Malla princes at Kusinârâ, he fell asleep, or as the ritual of his followers puts it, he entered *Nirvâna*.

His funeral was solemnized with great pomp, and the relics were distributed among the princes and cities of the district. Over these eight Stûpas were erected,—at Rājagṛīha, Vaisālī, Kapilavastu, Allakappa, Rāmagrāma, Vethadīpa, Pāvā, and Kusinârâ, besides the shrines erected by Drona and the Mauryas.² But though the princes of Magadha and Kosala (Audh) may have taken a personal interest in the Buddha, they did not adopt his doctrines as their private religion in supercession of the Brāhman state-religion. It was only in later times that a closer organization appeared among the numerous followers of Buddha. After the death of the Master, a council was held in the Sataparna (Pali, Sattapanni) cave of the Vaibhâra hill at Rājagṛīha, which was prepared for the meeting by king Ajātasatru of Magadha. The task devolving upon this council was to fix authoritatively the words of the Master gone into Nirvâna. About a century later there is said to have been a second council, held at Vaisālī to suppress the heresies that had appeared in the community; but the fact of such a council is doubtful.

In the hundred and thirty years between the second and third councils, there had been great political changes. Alexander the Great had invaded the Panjâb; the Magadha state (the Prachya, "Easterns," Greek, Prasioi) had attained a dominating position; the old dynasty had been overturned by an upstart, and Chandragupta (Gr. Sandrakottos or Sandrakypotos) had taken possession of the throne of Magadha.

Neither Chandragupta nor his successor Bindusâra adopted the Buddhist doctrines, the force and authority of which had already created for them an independent position. Asoka (B.C. 264-222)—in his inscriptions called Piyadasi,—the third king of the new dynasty known as the Maurya (Pali, Mora), was the first patron of the religion, which he publicly acknowledged. He was the founder of numerous monasteries (*vihâras*) and other ecclesiastical

¹ Yule's *Marco Polo*, vol. II, p. 300.

² Kern, *Manual of Buddhism*, p. 49; Rockhill, *Life of the Buddha*, pp. 145-147; Rhys Davids, *Buddhist Suttas*, S.B.E., vol. XI, pp. 181-182.

buildings; the sacred texts testify in extravagant terms to the king's zeal for the faith. He is said to have had 84,000 stūpas erected in different parts of his wide realm; and to have gifted his whole kingdom to Buddha's followers several times, receiving it from them again.

But the most striking witnesses to his zeal for Buddha's doctrines are his edicts. These documents, which are unique among the inscriptions of antiquity, relate that Piyadasi, the king "beloved of the gods," interested himself in the faith and its professors, that he endeavoured to establish the sacred tradition, that he had roads, wells, and hospitals made for the use of all living creatures. The only historical inscriptions of Western Asia which are akin to the Indian, both as regards the sense and the form, are those left by the Achæmenides, especially by Darius. The largest, and for our purpose the most valuable, is the inscription of Bagistān (Behistun). The simple language which expresses unreserved sincerity, the truly regal tone of the style, which avoids floridness, simply relates the facts, and does not pass over the names of the leaders who fought the battles,—are significant of the noble character of him who founded anew the Persian empire. The punishment to which he condemns the rebels "because they have lied," may be called humane compared with the barbarities of the Assyrians and other so-called civilized peoples. Now the inscriptions of Asoka may have some connexion with those of the Achæmenides.¹ This appears most strikingly in the form of the language itself. The idioms of the Persians and Indian Aryans were, even until the days of the Achæmenides, nearly allied dialectically: it cannot have been very difficult for these peoples, to some extent, to understand each other directly. The royal inscriptions of the Persians show us language still struggling for expression; everything is still fresh and new. But Asoka's inscriptions, though differing somewhat dialectically from one another, show everywhere the same courtly style (closely allied to the Persian) which is to be remarked especially in the formulating of the introductory sentences, the arrangement of the titles, and so on. It was necessary to mention this fact, for it has a decided connection with other things which intimately concern us.²

No important monument among those preserved in India is anterior to the time of king Asoka. All that have been preserved show undoubted Persian influence in their style. It has been declared, with reason, that stone-building on a large scale was first executed in India in Asoka's time: the criticisms of Indian

¹ Conf. Senart, *Jour. Asiat.*, 8me ser. t. V. (1885) pp. 269ff; or *Inscr. de Piyadasi*, t. II, pp. 219ff.

² The Asoka edicts are found on rocks at Girnār in Gujarāt, Shāhbāzgarhī in Yūsofzai, at Mānāsari, at Kālsī, at Dhauḥ in Orissa, Jaugada in Gāṇjām, and in Malsur, —also on pillars at Dehli, Allahābād, Rādhā, Māthra, and Rāmpūrva. See *Epigraphia Indica*, vol. II, pp. 245ff; *Arch. Sur. S. Ind. s. Amaravati*, vol. I, pp. 114ff, &c.

patriotism can alter nothing as to this fact¹ The Persian style, which the Achæmenides employed in their buildings at Susa and Persepolis, has inherited West Asian forms in its constructive as well as in its decorative features This Persian style, which



1. HALL WITH PERSO-INDIAN COLUMNS, REPRESENTING A FLOOR IN A GREAT PALACE: FROM THE RIGHT JAMB OF THE EAST GATEWAY AT SÂNCĪ.

shows many peculiarities, is unfortunately represented only by a few monuments upon which it is almost impossible to pronounce judgment. But undoubtedly its elements may again be recognised in the buildings of Asoka's day and of the older Indian style, dependent on that of Asoka, as grafted upon the native wooden style.

As chief elements, so far as the Buddhist sculptures are concerned, the following forms may be indicated:—The Persian pillar with bell-shaped capital was adopted directly; it was set up by itself as an inscription-pillar; the famous iron pillar of Dehli is a later example. In sculptures it is seen not only in representations of palace-halls, but also decoratively,—often to divide spaces, and with many interesting variants. The bell-capital frequently serves as a basis for one or more lions or elephants, or for a religious symbol (*e g* the wheel) when the pillar is considered as standing alone. If the pillar is used as a support in a building, the bell-capital serves as base for an abacus on which, turned towards

¹ Fergusson, *Archæology in India*, pp. 9, 18, 16ff.; *Ind. and East. Archit.*, pp. 47-49.

the sides, winged figures of animals (winged horses, gazelles, goats, lions, or sitting elephants) are placed. This last form resembles the Persian "unicorn-pillar." The appearance of the whole pillar in India, however, is rough and clumsy compared with Persian forms.¹

Orientalised animals play an important part in Buddhist art. All these hybrid creatures and winged figures—besides their purely decorative rôle—have been employed in representing the inferior mythical beings of the native mythology. Still it is uncommonly difficult, as will be explained more fully below, to find Indian names for these hybrid forms, in the formation and employment of which great inconstancy and some misconceptions are noticeable. It may be supposed that if the West Asian forms had not been preserved, this inconstancy in the shapes, this careful fashioning of extraordinary creatures of the imagination, to which names cannot be given, must point likewise to foreign influences. It is interesting that, even in Asoka's time, alongside these purely hither Asian forms, some also appeared sporadically which can only be of Greek origin.² The representation of divine beings under purely human forms is a feature of native art that is opposed to these foreign influences on ancient Buddhist art; and a marked contrast to the chimæras (Kinnaras) of West Asia is presented by the native animal world, which is not so frequently met with decoratively, but leaves this rôle to the foreign forms.



2. WINGED LIONS FROM THE SECOND CHOSEBRAM OF THE EAST GATEWAY AT SANCHI

With exceptions we shall meet with in a later chapter, the wings of the Oriental animals are mostly at rest and devoid of signifi-

¹ Conf. Cunningham, *Arch. Sur. Ind. Rep.*, vol. V. pl. xlv, xlvii, pp. 187, 188; and interesting capitals with such creatures in Burgess, *Archæol. Sur. W. Ind.*, vol. IV, pp. 5, 12; and *Cave Temples*, pl. xvi, xxiii, xvi.

² The reader is reminded of the centaurs at Gaya; Rajendralal Mitra's *Buddha-Gaya*, pl. xlv, fig. 12. Centaurs are also found at a later date when the Gandhâra influence appears more distinctly, and it is then impossible to prove whence they arose; *Epig. Ind.*, vol. II, p. 314, pl. ii, fig. 6. The aprons that strike one are doubtless to be regarded as leaves, and have a noteworthy parallel in the relief in the British Museum, *Jour. Ind. Art and Industry*, vol. VIII. (1898), pl. xvii, 1, or esp. ed., pl. xv, 1, and p. 16. The Jaina relief is also a companion piece to ill. 28. East Asian tradition, which represents the Tityagyonis as centaurs, proves that the human-faced oxen on the Jaina relief indicate the centaurs as representations of the animal kingdom in the Sâṃsâra.

cance; the most remarkable are those in the lion group of the applied plaques of the first and second architraves of the east gateway of the large stûpa at Sâñchî, as will be shewn at the end of the second chapter.

Along with representations of mythical plants, which may be traced to the Assyrian tree of life, and to which is attached a series of symbols difficult to explain, appears the native plant-world. A detailed description of the *dharma* symbols,¹ &c., which belong to the first type, would contribute little to the history of art; the second class is of more value. The Indian plant-world, notwithstanding simple and sometimes even rough modelling, is reproduced with astonishing fidelity to nature. A favourite subject is the lotus-flower (*Padma*, *Nelumbium speciosum*), which is employed decoratively and with great taste in the arrangement. Here and there West Asian (Egyptianised) lotus flowers and palms have crept into designs of this category, which are remarkable for the richness of their device (fig. 3). The broad disc of the full-blown flower is employed in all positions as a decoration and, owing to its resemblance to the wheel, is a favourite subject. In contrast with Assyrian art, which cuts the ornament through, like wallpaper, where the wall to be decorated ends, the flower lying under the capital in fig. 3 is turned upwards. In spite of the predominantly picturesque character of the pattern, this preference



3. LOTUS FLOWER DECORATION FROM THE OUTER SIDE OF THE PILLARS OF THE EAST GATEWAY OF THE GREAT STÛPA AT SÂNCĪ.

¹ Originally the wings were only externally attached symbols of speed. (Cf. on this point the notes in the *Festschrift für Prof. Veltj*, Leiden, pp. 222 and 223, note 3. A group of these winged creatures (horned lions, the so-called *ki-lin*, &c.) have been faithfully preserved in the art of eastern Asia. The wings are, however, represented as flames.

² W. Simpson, *The Buddhist Praying-Wheel*, Lond. 1806, p. 15, note 2; Goblet d'Alviella, *Migration des Symboles*, 1891, pp. 294ff; conf. also G. Bühler, *Epig. Ind.*, vol. II, p. 312.

for accommodation to the ornamental design is noteworthy. The Hindu sculptor does not care for purely geometrical designs, and so we frequently find creepers with aquatic birds, &c., which, on a smaller scale, fill in the spaces, and are rich and animated with fine observation of nature. The two outer sides of the east gateway at Sāñchī are a good example of this. While on the left side the design is carried out as geometrically as is permitted in Indian art, the creeper on the right side is full of life. Birds flit about among the flowers; and the plant itself grows from the jaws of a sea-monster. The part which flowers play in later Buddhist art is an important one, yet the finest *motifs* belong to this older period; flowering creepers hung up in holy places may have provided the models. In the main it may be said that these plants, represented in simple lines, with the native animals that animate them—both of which have received purely native modelling—mostly surpass what the celebrated Greek art was able to command: they rest upon a faithful observation of nature.

The ancient Buddhist monuments may be divided into five groups, according to their object:—¹

1. *Stambhas* (Pāli, *Thambhas*; Hindūstāni, *Lāts*), pillars on whose capital a religious symbol, as the Wheel or *dharma*-symbol, is represented, usually on a group of lions or elephants. They were probably always erected in connexion with Vihāras or Chaityas, and served for inscriptions. Some of the finest Buddhist *Lāts* were erected by Asoka and bear his edicts. When the capital was surmounted by a lion, the pillar was called a *Sīmhasambha* (Pāli, *Sihatthambo*). Compare the copy on the small middle pillars (between the architraves) of the east gateway at Sāñchī (fig. 36).

2. *Stūpa* (Pāli, *Thupo*; Anglo-Indian "tope") applies to any mound, as a funeral pile or tumulus; and hence to domical structures over sacred relics of Buddha or other Sthavira or saint, or as memorials on spots consecrated by some remarkable event in Buddha's life. When they preserved relics, the shrine in which these were kept was the *Dhātugarbha* (Pāli, *Dhātugabbho*; Singalese, *Dāgaba*; Japanese, *Tō*); and as most *Stūpas* were erected over relics (*dhātu*), the whole structure came to be called a *Dāgaba*. A *stūpa* consists of a circular or square base supporting a dome (*garbha*), on which stands a square block or neck (*gala*) representing a box to hold a relic, crowned by a capital consisting of a number of flat tiles. Above this is the umbrella or spire (*chūdamani*—Burmese, *hti*)—single or with several roofs usually three, over one another.

3. *Chaityas* (Pāli, *Chetiya*). Like *Stūpa*, the word *Chaitya*² is applied to a monument or cenotaph, and in a secondary sense to a temple or shrine containing a *Chaitya* or *Dhātugarbha*. *Chaityas*

¹ Conf. Ferguson, *Ind. and East. Architecture*, p. 50.

² In Nepal and Tibet (*chaitya*=Tib. *mChod-rien*, pronounced 'Chhor-ien') the word is used in the sense of *stūpa* (*dhātugarbha*=Tib. *mDan-rien*). Conf. Burgess, *Cave Temples*, p. 174.

or Dâgabas are an essential feature of temples or chapels constructed for purposes of worship, there being a passage round the Chaitya for circumambulation (*pradakshinaya*), and from these such temples have received their appellation. The name of Chaitya, however, applies not only to sanctuaries, but to sacred trees, holy spots, or other religious monuments.¹

4. Vihâras were monasteries for the accommodation of monks living together in communities, and were mostly, if not always, connected with Chaityas.

5 Ornamental Rails (*suchaka*) were mostly employed as the enclosures of stûpas, or to surround a terrace on which stood a sacred tree, &c. The stone railings are among the most important monuments in the representation of Indian sculpture, as most of them are ornamented with reliefs on the upright shafts and transoms (*suchi*) or cross-bars. In some places great stone gates (*toranas*) are connected with the railings. These gates—the best preserved are those at Sâñchi—are mostly richly adorned with sculptured scenes. They show the stereotyped wooden style not only in the decoration but also in the form of the building. They seem to have been introduced into farther Asia very early; at any rate the well-known Chinese *pai-lus* and the Japanese *tori-is* are to be connected with these ancient *toranas*. Originally they were, no doubt, somewhat like our triumphal arches.²




4. REPRESENTATION OF A STÛPA: GODS AND MEN BEFORE IT.
From the east gateway of the great stûpa at Sâñchi.

Now the monuments, the sculptures of which show the principal phases of ancient Indian art, are divided into two large groups. The older, and properly Indian group, in which Persian influence

¹ *Conf. Jour. As. Soc. Beng.*, vol. VII, p. 1001.

² Fergusson and Burgess, *Cave Temples*, pp. 171-177; Goblet d'Alviella, *Ce que l'Inde doit à la Grèce*, pp. 44-48.

appears, begins in Asoka's time; to it belong the monuments in India proper; *lāts* at Dehli, Tirhut, Sankisa, Sāñchī, etc.; chaitya-caves and viharas in Bihār, at Nāsik, Ajantā, Elura, Kārle, Kāñhēri, Bhājā, Bēḍsā, Dhamnār, at Udayagiri near Kāṭak, Bāgh, etc.; stūpas of Mānikyāla, Sarnāth, Sāñchī, and Amarāvati: stone railings with gates at Barāhat



5. SKETCH MAP OF INDIA WITH THE NAMES OF THE PRINCIPAL SITES OF THE BUDDHIST PERIOD.

(Bharhut or Bharaut), Mathura, Gayā, Sāñchī, and Amarāvati. The second group, the so-called Græco-Buddhist, or rather, as Fergusson first called it, that of the Gandhāra monasteries,

embraces the numerous remains of the monasteries of Jamāl-garhī, Takht-i-Bāhī, Shāhdēhri, Sanghāo, Natthu in Yūsufzāi, and at Loriyān Tangai and other localities in the Swāt territory. An older branch perhaps precedes it,—the Indo-Hellenic school, Smith styles it,—which is represented chiefly by sculptures from Mathurā.

While in the older Indian group the native element forms the groundwork, and so is developed farther on the soil of India, the Gandhāra school presents strange antique forms. Later it influences Indian art, but, from geographical and other reasons which contributed also to the splitting of Buddhism into two schools, it remains isolated and is thenceforward most permanent in the ecclesiastical art of the northern or Mahāyāna school.

Among the oldest sculptures of India are perhaps those of the caves of Udayagiri in the Puri district of Orissa. The most interesting are in the two-storeyed Rāj-Rānī or Rānī-ka Nūr caves. These remarkable reliefs show an uncommonly animated style, little influenced by foreign elements.¹ They form, so to speak, the primitive basis from which issued the purified and refined forms of later times.


In general, the ruins of the richly ornamented stone-railing and of the gates of the stūpa at Barāhat (Bharhut), which has now all but completely vanished from the spot, show on their reliefs the same style as the sculptures of the Sāñchī gates described below, though they are somewhat harsh in form; this is most apparent where women are represented. The distorted exaggerations of the female figures, and the fondness for the nude are seen on the Sāñchī reliefs; in Barāhat scarcely anything of this is to be remarked. The sculptures of Barāhat are of special value, inasmuch as all the representations are accompanied by inscriptions, and so can easily be explained. Most of the pillars from the south and east gateways and the connecting rail were removed to the India Museum in Calcutta, and only a few fragments left *in situ*. The ruins which, when found, had been terribly destroyed, date from about the first half of the second century B.C.²

The sculpture of the earlier stone-railing at Gayā (Buddha-gayā) are somewhat later than those at Barāhat, and are no doubt to be traced back to Asoka. In ancient times it enclosed a terrace, on which the bodhi-tree—the fig-tree under which Gautama obtained enlightenment—stood, apparently in a sort of chapel. The temple at Gayā is of much later date: it was built by Amaraśeva in the fifth century A.D., restored by the Burmese

¹ Fergusson, *Archæology in India*, p. 12; *Cave Temples*, pp. 77-86, 91.

² Fergusson, *Ind. and East. Architecture*, pp. 85-91, Cunningham, *Bharhut Stūpa* (1870); Le Bon, *Monum. de l'Inde*, p. 52-55. Bharhut lies to the S.S.W. of Allāhābād, about 200 miles E.N.E. from Sāñchī, and 160 W.S.W. from Banāras, near to the railway. The remains of the stūpa here were reported to Gen. Cunningham by a native in 1873, and excavated by him in Feb. 1874.

in 1306-9, and again, it lately underwent a renovation at the hands of the Bengal Government, that must be regretted. Some fine panels from the old Asoka railing seem to have found their way to the Berlin Museum.



6. PLAN AND RESTORED ELEVATION OF THE GREAT STŪPA AT SÂNCĪ.

At Sâncĭ, or Sâncĭ-Kanâkeda, about twenty miles N.E. of the capital of Bhopâl; and S.W. from Bhilsâ, the ancient Vidîsâ, there was a group of ancient stûpas, and other religious

buildings Till about 1820 the largest and second stûpas, with a third, were still entire The place was first seen by Colonel Taylor and then by Captain E. Fell and Dr. Yeld in 1818 Soon after, Mr. H. Maddock got permission from the native government to dig into the stûpas, and by December 1822, Captain Johnson, the Agent's assistant, had opened the largest to its foundations This carelessly conducted search for supposed treasure did immense damage to the structure of three stûpas and hastened the dilapidation of their enclosures, while no discovery compensated in any way for the destruction. They were again further opened up by Major A. Cunningham and Capt. F. C. Maisey in 1851, when several relic caskets were found.¹

The largest stûpa is surrounded by a massive stone railing; access to the space inside the railing is afforded by four lofty gateways of fine grained sandstone facing the four points of the compass. This stûpa is a massive, solid brick and stone building of 121 feet in diameter and about 53½ feet high; the dome rises from a plinth 14 feet high, standing out 5½ feet from its circumference. On the top of the building was a terrace 34 feet in diameter, enclosed by a stone-railing (cf. plan and sketch, fig. 6). The ascent to the ramp which surrounds the building was reached by a double stair on the south side. The whole structure is surrounded by a massive colonnade measuring 144 feet from west to east and 151 feet from north to south In this way the space on the south side of the terrace, where the steps are, is broader. The encircling rail shows numerous inscriptions, but no sculpture on the frieze or coping. On the other hand, the figured work of the four great gateways is particularly rich.

At the instigation of Mr. Fergusson,² a cast of the eastern gateway was made in 1869 and copies of it are in the Museums of Science and Art at S. Kensington, Edinburgh and Dublin, in the Royal Museum at Berlin, at Paris, &c.

The inscriptions on the railings of both the two existing stûpas are short but very numerous. Unfortunately, they contain scarcely any indication by help of which a date might be inferred. But the great majority of them are in the form of alphabet which goes back to the time of Aśoka (B.C. 250) and which had altered for some time before the Christian era.³ It seems most probable then

¹ *Jour. A. S. Ben.*, vol. III, pp. 488-494; vol. IV, p. 712; also vol. VI, pp. 451ff; vol. XVI, pp. 744ff; Cunningham, *Bhilsa Topes*, pp. x, 183, 209f. 275, 283f.; Fergusson, *Tree and Serp. Wor.* p. 88; *Pictureque Illust. of Anc. Archit.* pp. 21, 22; *Ind. and East. Arch.* pp. 60-76, 92-99; and Maisey, *Sanchi and its Remains*.

² The first half of Fergusson's *Tree and Serpent Worship* (1868, 2d ed 1873) was devoted to the illustration of the Sanchi Topes or Stûpas, from the drawings of Colonel Maisey, and a few photographs. A complete photographic representation of all the sculptures is required adequately to illustrate the monument.

³ *Epigraphia Indica*, vol. II, pp. 88, 89. An inscription on the representation of a stûpa on the south gateway, mentions that the block "was the gift of Ananda, the son of Vasishtha, in the reign of Sri Satkarai." Among the Andhra kings there were several bearing this name, one of whom seems to have ruled over the Dakkhin about 150 B.C.

that the gateways were erected in the second century before the Christian era. Stress may also be laid on the fact that the south gate, to judge from the style, is apparently the oldest. For different reasons it is probable that it was Asoka who erected the stūpa. The Singhalese chronicle, the *Mahāvamsa*, relates that Asoka, when he was sent by his father as regent to Ujjayinī (Ujjain), made a stay of some time at Chetiyagiri or Vessanagara (Besnagar near Bhilsā). There he married the daughter of a prince, and had by her two sons, Ujjeniya and Mahinda, and afterwards a daughter, Sanghamittā. The two last took orders, and at the behest of their royal father went to Ceylon at the invitation of King Tissa, to take thither a shoot of the sacred bodhi-tree and to spread Buddhism in the island. Before their departure for Ceylon they were received by the princess their mother, who visited them at Chetiyagiri, in a hall built by herself. Now before the south gate there stood a Lāt (with lion capital), of which a fragment still remains, bearing part of an inscription—apparently of an edict of Asoka,¹—from which it follows that the erection of the great stūpa belongs to Asoka's time, about 250 B.C.: the commencement of the rail followed very soon after; and the erection of the south gateway, about or before 150 B.C. According to their probable age, the gateways stand in the following order—the southern, the northern, the eastern, the western. As the reliefs of the gateways exhibit the most extensive monument of older Buddhist sculpture, and in general represent the Asoka style, the character of this style will be described in more detail in the following chapter. For the reliefs of the east gate see the end of Chapter II.

The great Stūpa of Amarāvati, on the right or south bank of the lower Krishna river, about twenty miles above Bejwādā, was first heard of by Colonel Colin Mackenzie in 1797. It was then being removed by the local chief to be used for building purposes. Mackenzie paid a prolonged visit to it in 1816 and again in the end of 1819, and made many careful drawings from the slabs of the railing and of those that had been round the base of the stūpa. Many sculptures had then been destroyed, but a few were secured by Mackenzie and sent to Madras and Calcutta. Further excavations were made in 1845 by Sir W. Elliott, and the sculptures recovered are now in the British Museum. The Madras Government excavated the whole area in 1881, and a large number of the sculptures then recovered were sent to the Madras Museum.

The Amarāvati stūpa appears to have been deserted in the seventh century, when Hiwen Tsiang visited the district. The short inscriptions found range over a considerable period, and there were evidently enlargements and reconstructions; but the discovery of an epigraph of Puṣyamayi—an Andhra king of the second century A.D., and the reported association of Nāgārjuna's name

¹ *Epig. Ind.*, vol. II, p. 367.

with the creation of the rail, combined with other indications, point to the second century A.D. as the period when most of the sculptures were executed and the work completed. It is due to Fergusson's ingenuity that the railing, adorned with richly composed reliefs, of which the pieces were completely dissevered, has been so far reconstructed that we have a picture of the whole¹.

The Amarāvati railing thus belongs apparently to the second century A.D.; the stūpa itself was older. The style of the sculpture on the railings had its origin in that of the Asoka period, but it has an entirely new kind of formation. The types are all closely preserved; but in the representation of the single figures, as in the composition, other laws prevailed. It will suffice, however, to indicate below some striking points in which the style of this older period—as Fergusson was the first to show—exerted an influence upon the reliefs of Amarāvati. As to the further development of the elements which Amarāvati has in common with Sāñchī, and so on, it will suffice to notice that a certain coquettish elegance, an over-luxuriance of the compositions, is the characteristic feature. (cf. illus. 8, 20, &c.).

The paintings of the cave-temples of Ajantā, N.N.W. of the town of the same name in the Indhyādrī Hills which form the boundary between the Dekhan and Khândesh, do not fall quite within the scope of this book, and the reader is referred therefore to the literary works indicated in the bibliography for what concerns the history of the discovery as well as the artistic character of these specimens of ancient Indian paintings, so important to Indian archæology. Fergusson conjectured that, besides the Gandhāra school of sculpture, an early school of painting existed in Gandhāra; how far what is established in the third chapter as to the survival of Gandhāra types in the ecclesiastical paintings of Tibet, China and Japan, is calculated to support this undoubtedly correct conjecture of Fergusson, will no doubt be seen when our knowledge of the latter has been assured. Now the frescoes of Ajantā and Bāgh are also connected with these ancient ecclesiastical paintings animated by antique elements. It is only necessary to refer occasionally to an Ajanta representation where it seems of value for the history of a type. The uncommon beauty and grace of these pictures,—the sad fate of which I need not dwell on here,—was made evident by the outline drawings which Dr. J. Burgess incorporated in his account of the pictures (Bombay, 1879). The recent splendid publication of the Ajantā pictures by Mr. Griffiths has made them accessible in a worthy form.

¹ The materials acquired have been utilized in the second half of Fergusson's *Tree and Serpent Worship* and in the volume of the *Archæological Survey of S. India on the Amarāvati and Jaggayyapeta Stūpas*.



7. A CHIEF SEATED ON A THRONE, TALKING WITH ASCETICS: FROM SWÂT.

CHAPTER II.

THE EARLY INDIAN STYLE.¹

The form of art which was, and remained, national in India, and which constantly influenced the stone-architecture was wood-carving. The stone gates at Sâñchî, for example, are copied from wooden ones, which perhaps originally stood there; the general construction as well as the detail show this most clearly. The same stylistic features of the gates are met with, on a smaller scale, also in the throne-seats in reliefs of a still earlier period. Thus, among other things, some examples of thrones with backs are preserved on the reliefs of the stone railings of Amarâvatî, which represent the old Aryan native style in a quite distinctive manner. It is astonishing how intimately related these forms are to those of the Middle Ages, especially those of the north (conf. figs. 7, 8). The transoms of the broad low support are worked at the ends so as to project, and the ends themselves are ornamented with fantastic animals' heads (heads of dragons). On the relief from Amarâvatî (shown in fig. 31) the *Tofana* appears to be treated similarly—so far as the architrave is concerned—but the representations are not quite distinct enough. The interstices are adorned with reliefs and little round figures. The West Asian animal forms that are here introduced will be treated more in detail below (conf. figs. 28 and 29).

¹ As the examples of this style are all within the limits of India proper, I prefer this term to "Perso-Indian" employed by Prof. Grünwedel.—J.B.

At the present day wood-carving is still preserved in rustic forms—the characteristic feature of the national life of ancient India, as of the life of modern times, being the peasant class—although these purely archaic forms, reminding one of German compositions of the Middle Ages, have been lost. As in ancient Buddhist sculpture, the carved-wood style reappeared in India at a




8. THRONE SUPPORTING A SMALL STÜPA, WORSHIPPED BY NĀGAS.
On a slab from Amarāvati Fergusson, *Tree and Serp. Wor.*, pl. lxii.

later period in the sacred buildings of the Jains under the Chalukya rulers of the Middle Ages. These buildings were executed in stone (white marble), and the fine lace-like interwoven work that forms the decoration of the buildings on Mount Abu and in other Jaina temples in Western India had then its origin. How these Jaina buildings, in turn,—with the omission of the figure elements—became the models for the trellis and stone filigree work of the Muhammadans in their buildings at Ahmadābād and elsewhere belongs to a different chapter of Indian art. We see then, that early Indian sculpture had an auxiliary in an ancient, indigenous, and deeply rooted branch of art: though, it is true it was only in the hands of an artizan class. When working in stone began it was

an aid in modelling, but an obstacle in the way of development. It is the wood-carving style, above all, which is to blame for the fact that Indian sculpture never became more than a *relievo* serving for the decoration of large buildings,—so much so, indeed, that the buildings executed in stone appear overlaid with carved mouldings. The ornamental relief only seldom, and as if by chance, attains organic completeness; even in ancient Buddhist art a certain irregularity is indulged in—a constant varying of the panels employed decoratively, for the normal architectural development of which there is no hard and fast rule. It is therefore, as we shall see, very difficult to insist upon the points which, according to the design of the sculptor, should be emphasized. (Cf. illus. 36). And, further, there are no separate figures in Buddhist art: for even when figures are executed alone they are never represented without an aureole, never without attendant accessory figures, and never without a wall behind to form a solid background to the figure. This fact bears a certain relation to the Indian conception of the universe—the constant merging of historical persons in a system, the limited freedom of the individual with regard to the world surrounding him, and which is considered essentially from a religious standpoint, even the very idea of the identity of individual souls with the Universal Soul: it is to this that their incapacity is owing to attain a really artistic conception which could have developed the independent figure.

A second branch of Indian art, —more delicate in form, and, by reason of the allusions to models in nature, apparently more productive,—was intimately connected, and that from very early times, with the popular ideas; this was the art of the goldsmith.

¹ So Cunningham, *Bharhut*, pl. xliii. The inscriptions designate the two representations as *Isimiga Jataka* and *Miya samadaka chetaya*,—"the rebirth as Rishi Antelope," and "the antelope enjoying charity." Cf. Kultzsch, 'Bharhut Inschriften' in *Zeit. d. Morg. Ges.*, Bd. XI., pp. 68-70, Nos. 10, 11.



9. RELIEF WITH REPRESENTATION OF THE ISIMIGA JĀTAKA, LIONS AND ANTELOPES BEFORE THE SACRED TREE, &c.¹

Its influence is confirmed in two directions. The sculptures show how the decorative element in goldsmiths' work—often nearly resembling basket-work—everywhere aids in the devising of those chains and other ornaments, with flowers, leaves, rosettes, and finely linked bands, found along with panels which are adorned with figure compositions. The lower decorative lines on fig. 9 present patterns borrowed from ornaments: little bells and chains such as are worn by women for the feet.

For the separation of the different representations in the central belt the tendrils of plants are employed, from which ornaments grow out: the representation of the "Wishing tree" (*Kalpavriksha*), which at a later date becomes common, springs from this ornamental form.

But the goldsmith's art has had a fatal effect on the modelling of the human figure. The heroic form of Indian sculptured figures has been, and at all times remained the same,—they are decked as for gala occasions. This form has been preserved with unalterable tenacity through the whole history of Indian art, and even in neighbouring countries. The old, partly ancient Aryan, forms of festal ornaments passed, along with the Aryan colonists, beyond the limits of India, in manifold varieties in accordance with the peculiar style of the particular country; in Burma and Siam, Tibet and Mongolia, Java and Bali, the modified forms of ancient Indian gala ornaments are still to be found in the gala costume of the kings, or of brides and bridegrooms, or, finally, in the costumes of the theatres which everywhere represent subjects taken from the ancient Indian legends. It is a surprising fact that the non-Aryan districts of India, or the lower castes in the old civilised parts, like the above-named countries outside India, frequently now show more antique forms of articles of jewellery than the ancient civilised kingdoms of India itself, since in the course of time the latter adopted other fashions in costume and ornament. The whole question deserves special and detailed examination in which the monuments of antiquity should play a prominent part. At present I must content myself with suggestions.

The ornaments are uncommonly rich and tastefully arranged, whilst they also in themselves form an artistic motif. The ancient Buddhist plastic art never deteriorated into the rough, monotonous and mechanical sort of style in which the so-called Assyrian art covers its figures with ornaments and garments in rich patterns. But on the other hand the ornament, in the painfully careful execution it received, hindered very considerably the development of the human figure, since it always retained the conventional type for the forms. Here, too, it is to be observed, that tropical Nature has exercised its influence in India; for the very names of articles of jewellery in all Indian tongues clearly prove the most part of them to be imitations of the splendid blossoms and creepers which the flora of this lovely land holds out to man for his adornment on festive occasions. From ancient

literature we clearly learn, for example, that the same flowers served directly for adorning the hair which, at the present day, have given their names to the corresponding metal ornaments. Thus we read in the *Ritusamhara* ('Description of the seasons'), ii. 21: "Now (in the rainy season) the women wear on their heads garlands of *Kadamba*, *Kesara*, and *Ketaki*, and ear ornaments of *Kakubha*-umbels, which, being thrust into the earlap hang down over its edge."¹ These floral adornments varied according to the seasons. With regard to the names mentioned it may here be noted that even at the present day a broad ornamental plate in the shape of a pandanus-blossom is quite commonly worn as a head-ornament. It bears the same name: Hindī, *Ketaki*; Marāṭhī, *Keorā*; Malayālam, *Keiduppā*; &c. Even along with metal ornaments, flowers assert their rights: the Tamil women when in gala costume, along with metal ear-ornaments and ornamental plates on their heads, wear a cluster of single yellow or white flowers strung together by means of threads, and hung from their ears, &c., &c. Among the lower castes similar articles—perhaps imitations—woven of grass and straw, with festoons and chains made of nuts and bright coloured seeds, are still to be seen side by side with metal ornaments.

However pleasing and charming this joy in Nature may appear, the reproduction of these articles of adornment had an unfortunate artistic influence with respect to modelling. The shoulders loaded with broad chains, the arms and legs covered with metal rings, the bodies encircled with richly linked girdles, could never have attained an anatomically correct form. Everywhere the carrying out of a clear outline was interfered with by broad ornamental lines, rich and tasteful in themselves, disturbing the natural position of the muscles of the leg and arm, and, in consequence, the limbs have received at the best, an effeminate seemingly correct finish; but at the worst, they have been subjected to a complete distortion of the skeleton, whilst the muscles stand unduly out.

Connected with this overloading with ornament, certain physical peculiarities which accompany the wearing of heavy ornament are regarded as beauties and are still further exaggerated in the copies. This is especially due to the wearing of large and heavy ornaments. This, again, is in keeping with the fact that the types on the monuments, e.g. illust. 8, 14, 22, bear a greater resemblance to certain ornaments of the Aryan races than those worn by the women of the early civilized territory at the present day. The great metal, wood, or horn discs (Mal., *takka*; Tamil, *takkei*) of the Nāyarchchi of Malābar, the extended ear-lobes of the Marāvatti, &c., are well known.²

¹ These in order are:—*Nauclea kadamba*, *Mimusops elengi*, *Pandanus odoratissimus*, *Pentapleura arjuna*.

² To indicate to the reader what stress is laid on this perception of beauty in the Indian mind, it may be noted that, among the beneficent acts (*Tam. aram*) enumerated by Tamil moralists, besides digging wells, building hospitals, feeding Brahmins,

Out of this emphasizing of ornament came the treatment of the nude. The naked body, as such, was never an object of representation in Buddhist art.

Apart from the fact that nudity is repugnant to Buddha's doctrine, the peculiar ideas of the Hindus as to the purpose of the human body is to be taken into account, the human form is at best a part of Nature itself, the ephemeral garment of the soul, in which the latter lingers against its will. It is important to remember here what ideas were not accepted by the Hindus. Man never appears as the lord of Nature, which was there just to serve him: never is he regarded as the crown of creation. Re-incarnation into the world of human beings is only desirable inasmuch as that alone makes redemption—final escape—possible. With this may be connected the fact that no general interest is taken in the symmetrical training of the body. Physical exercise is not unknown in India, but its ends are professional, not æsthetic. Physical beauty appears as the result of good works in former births: not as that of individual energy and pleasure in life; it is a gift of Nature and transient as the tropical flowers. It is quite true that, in India, people wore, and still wear, as-light clothing as was worn in ancient Greece, and bare limbs are common. Physically, too, the Hindu differs from the ancient Greek. With his delicate and supple-jointed limbs, miserable calves and feeble muscles, the Hindu was in early times, as the ancient Buddhist sculptures show, the very same lightly-built, slippery, eel-like creature that he is to-day. On the whole, it may be said that ancient Buddhist art has represented the Hindu excellently, with an agreeable childlike naturalism which, notwithstanding the graceful moulding, is far from idealising. As strict training was unknown, a refinement soon appears which is seen chiefly in the representations of women, and becomes by and by baroque or rococo in style. With this conception of the human form agrees the circumstance that even at an early date an interest in portraiture, at least in national portraits—if one may be allowed the expression—is evinced. The different peoples that lived side by side in India were distinguished from one another above all physically: contact with peoples of hither Asia, in the time of Asoka, revealed new types, and thus we undoubtedly see an attempt for instance to represent foreign nations in the equestrian groups that adorn the Sâncihî gateways.

On the eastern gateway, for example, besides mythical foreign peoples, two figures are represented riding on horned lions. One of the heads is clearly not of the Aryan type: the woolly negro-like hair and the thick coarse shape of the whole head surprises

"giving-palmyra palm bands (*kâddôl*) to women," is specified, that with these rolled spirally in discs they may enlarge the holes in their ears and so wear large and imposing ornaments (*tôda*, Mal. *tôda*). Conf. Rottler, *Tamil-Eng. Dict. s.v. aram*. In this connexion see also E. Thurston, *Madraz Govt. Mus. Bullet.* vol. II (1898), pll. xxii, xxv, pp. 123ff.

one; this same figure holds a bunch of grapes in his hand. In India wine is unknown. There appears to be no word in the early language for the vine or its cluster¹. Even at the present day,



10. COMPARTMENT FROM THE THIRD ARCHWAY OF THE EAST GATEWAY AT SANCHI.

grapes are mostly brought from Kábul, though they are now cultivated about Daulatábád. Thus the rider represents one who is not Indian, and has perhaps a remote connexion with the representations of Silenus that have been found at Mathura². Although the framework of the figure is in the Peiso-Indian style, at any rate this and the corresponding equestrian figures represent foreign nations, regarded as living far away in the North-west. The whole series of these figures—those mounted on goats, on dromedaries, on lions—present a distinct contrast to the Hindus riding on elephants. The mythical-geographical conceptions on which they are based remind one of those fabulous creatures of which Herodotus tells the Greeks,³ from Persian traditions related by Aristæus of Prokonnesos, and which, on the strength of Indian tales, Megasthenes described at a later date.

The great majority of the other reliefs at Sanchi present the Hindu type—a long head with full round face, large eyes, and thick lips. At Barâhat (Bharhut) the same type appears, but it is somewhat harsher. The greatly extending ear-lobes are never wanting; the way in which the head-dress is emphasized often

¹ Sanskrit *drākṣā* is 'pdx; *mridāṁkā*, *mridat*, is a new form. On the probable borrowing of *Serpus* in Chinese, conf. Hirth, *Erunde Einflusse in d. Chin. Kunst*, S. 15, 28, note 1.

² *Jour. A. S. Beng.* vol. V, pp. 517, 557; *Arch. Sur. Ind. Rep.*, vol. I, pp. 212-14; and Growse, *Mathura*, 2d. ed. p. 456.

³ Herodotus, lib. III, c. 116; lib. IV, c. 18.

causes the heads to appear disproportionately large, so that, in the case of accessory personages especially, the whole figure has something childish and dwarfish about it (conf fig 17, &c.). In this way real dwarfs appear, which are presumably connected with antique pigmy types (conf. fig. 11). This question, which demands much preliminary investigation, cannot here be discussed in detail. Still, it may be said that they represent the basis of the thick-set, dwarfish type of demon that appears later and extends into Lamaist art. It seems not to be without purpose that the dwarf capital appears on the west gateway at Sâñchi, since the architrave represents the attack of the demons on the Bodhi-tree.¹




11. PILLAR CAPITAL WITH DWARF-LIKE DEMONS. From the west gateway at Sâñchi.

In the treatment of drapery, the earlier Buddhist art is very successful,—though unusual articles of clothing, such as the monk's cowl, present difficulties. The dress of the men consists, in the main, of the same articles as are generally worn at the present day,—a loin-cloth worn so as to resemble trousers (Hind. *dhôti*, Tam. *mundu*) forms the garment proper. The upper part of the body is always bare; the modern jacket, for example (Hind. *angiyâ*, Tam. *sokkag*), or other forms of this article of attire, nowhere appear. As covering for the upper part of the body a long shawl-like cloth is used, which is thrown about the shoulders in various ways—the modern *aṅgavastram*, and so on. In descriptions contained in the sacred texts of gala costumes and the like, the *chaluḥkhepa*, i.e. the waving with the dress, that is the upper garment, is always mentioned (fig. 37). This upper garment has ever remained the heroic costume, if one may be allowed the expression, and in the earlier and later representations of Buddhist gods, forms the folds that wave about the figure like an aureole. This arrangement is often completely misunderstood in badly executed pictures, though East Asian art knows how to employ tastefully this Indian dress. (Conf. illus. in Chapters III and IV). Japanese articles of export, nevertheless, when they represent Buddhist deities often manifest the rudest misconceptions.

The women on the sculptures of the older period are seen clothed in the loin-cloth only, but their ornaments and head-dresses are all the more rich. The long loin-cloth, reaching to the ankles, is sometimes treated as transparent, and is then—since the sculptor lacked the means of expressing his idea—indicated by representing the figure without covering, yet so that the edge of a garment is visible over the ankles and between the legs. The upper part of the body is always uncovered; this light kind of dress is still to be

¹ *Tree and Serp. Work.*, pl. xviii, *Prev. Nat. Monks, in India* (Lond. 1896), pl. xxvi, or Cole, *Sâñchi* (1885), pl. ix.



12. RELIEF ON THE INNER SIDE OF THE LEFT PILLAR
OF THE EAST GATEWAY AT SANCHI; A YAKSHA.¹

found in the south of modern India among the Nayar-chchhis of Malabar, whose large ear-ornaments have been already mentioned. On several reliefs the women appear without any garment but a narrow loin-cloth, the ornamented girdle, head, arm and leg ornaments being all the richer. Further details relating to these matters belong to the history of costume. It was important to notice here, that, from the nature of the garments, the hip, and not the breast and upper part of the body, becomes the fixed point starting from which the figure was composed. One has the feeling that the artist wished to provide against the loin-cloth slipping from the figure. This condition, imposed by the character of the vestments, explains much in the modern Hindu; but it also explains the strained attitude of the figures both in

¹ This is possibly Dhrtarastra, the white Yaksha ruler of the East: conf. Bockhill, *Life of Buddha*, p. 48, note; Minayeff, *Recherches sur la Buddha*, (in *Ann. Mus. Guimet*), pp. 188f.; *Arch. Sur. W. Ind.*, vol. IV, p. 99, inscrip. 8; and *Cave Temples*, pl. xxv.—J.B.

the older and later art of India. Modern proverbs are conversant with this.

An artistic feature which naturally originated from the sort of clothing described above,—the rich hip chains and girdle—is the prominence of one hip, the figure being represented with one foot firmly planted while the other, bent or in the act of stepping forward, is almost entirely relieved of the burden. This beauty device is of very ancient standing in Indian art; it is usually, if not exclusively, seen in female figures. Modern miniatures have faithfully preserved it and developed it to a certain coquettish elegance; conf. figs. 8 and 13.

The subjects that were represented were taken from the traditions of the life of the founder of the religion, and referred to local incidents. His life, until he attained Buddhata—*to use their own expression*—seems to have been the chief subject for the earlier period. But besides these, there exist at least as many scenes representing solely the adoration and worship of religious symbols, processions to holy places, and so on. Besides there appear even on the monuments of the Asoka period a few representations which refer to the so-called *Jātakas* or stories of Buddha's previous incarnations. The *Jātakas* form a part of the canonical literature (of the *Sūtra* class); they are an inexhaustible storehouse of fables and legends, but are also of exceptional importance in the history of civilization in ancient India. The plan of the work is briefly as follows:—According to the tradition, Gautama had passed through five hundred and fifty existences in all created forms,—as god, as man, as animal,—till, in his last incarnation, as the son of Suddhodana, he appeared as the deliverer of mankind. Five hundred and fifty verses, or groups of verses, which contain sayings of the Master, form the themes for as many tales told in support of them from Buddha's last earthly life. Some event—an annoying incident with insubordinate monks, for example, or a contest with some adversary, a conversion, et cætera, is related in the attached commentary: Buddha adjusts matters, or delivers a discourse, which contains a parallel from one of his previous lives and concludes with the verse that forms the title as *fabula docet*.

Owing to the simplicity of the religious ideas of the people at the



13. THE GODDESS KAMALA,¹ a form of SRI (Tirumagal). Modern S. Indian bronze.

¹ Or Bhūmidēvi, the goddess of the earth, Vishnu's second wife, who is represented with two arms, holding a lotus flower in one while the other hangs down empty; she wears a crown, and her black hair hangs down to near her feet; she stands on a lotus. Tirumagal, 'the divine or illustrious daughter,' is a name of Lakshmi.—J.B.

time, the figures required by Buddhist art for the representation of the subjects referred to, are few in number, and represent divinities of a low order—demons and beings half divine,—for Buddhism had taken root chiefly among the masses and everywhere employed the speech of the people. According to their teaching all the above-mentioned beings are mortal; even the gods owe their positions to their virtuous actions in previous existences, and appear throughout as believing promoters of the religion of the 'Vanquisher.'

Now in the *Sūtras*, especially in the *Śāktas*, a god and a goddess are particularly prominent. In the Vedic pantheon, the thunder-god Indra or Sakra (the mighty) had attained a predominant position, and had thrust the older class of gods into the background; even in the Pāli *Sūtras* he is familiar, under the name of Sakka, as the chief god. The Buddhists adopted into their mythology certain of the Brahmanical gods, but modified their characters and importance. To Sakka, Mahābrahmā and Māra,—possibly influenced by the Persian conceptions of the Ameshaspends,—they assigned the rank of archangels, and represented them as ruling in great magnificence in their respective Devalokas or heavens, but often descending to interfere in human affairs. Sakra, like Jupiter Fulgurator, is the Brāhmaṇ god of the atmosphere and king of the minor gods; and with the Buddhists he even bears like names—as Vāsava, Vajrapāṇi, Dēvinda, Maḡhavā, Sahassanetta (Sansk. Sahasranetra), &c., but they change Purindara ('destroyer of towns') into the Buddhistic epithet of Purindada ('bestower of towns'). He is inferior in majesty to the other two archangels, but rules over the five lowest of the six Kāmadevalokas and has his abode in the Tāvātīśa. (S. Trayas-trīṃśa) heavens. As in Brāhmaṇ mythology, his consort is Sujātā or Sachi, his palace or car is called Vejayanta, his elephant Erāvata (S. Airāvata), and his charioteer Mātali.¹ In Hindu iconography also he holds the Vajrayudha, which he is represented as giving to those practising austerities to render them invincible. He appears in sculptures in the ornaments and costume of a king: indeed, he is not distinguishable from royal figures.

On the east gateway at Sāñchi (on the front of the right pillar) a large palace of the gods is represented, on the different terraces of which persons in regal costume are represented sitting and waited on by women who dance and play. They are certainly gods: in their left hands they hold a small bottle, in the right an object—not readily recognisable, but which resembles the later thunderbolts (conf. fig. 1), the well-known ritual sceptres (*vajra*: Tibetan, *rdo-rje*) of the priests of the northern school). It must be the thunderbolt, the attribute of divine power—an attribute corresponding well with the storm-myths of the *Rigveda*.

¹ In Persian myth, Indra is the demon opposed to the Ameshaspends Asha-Vahista. Darmstater, *Zandavesta* (Sas. Hist. of the East, vol. IV), vol. II, p. lxxii, or in *Ann. Mus. Guin.*, tom. III, pp. xlv, xlv. — J.B.

Mahābrahmā, Brahmā Sahampati or Pitāmahā, is the greatest of all Devas. Though vastly inferior to Buddha, he rules the second of the Trailokya regions—the Brahmā heāven, called Rūpāvachara, which is beyond the Kāmadevalokas. He has, as a symbol of sovereignty, a silver *chhattra* (Pāli, *chhatta*)¹

Mārarāja, the third of these Devas, is variously named Vasavatimāra, Namuchi, Pāpiyān, Kāmadhāturāja, *Krishna*, Pisuna, &c. He is ruler of the highest of the six Kāmadevaloka heavens—the Paranimmita-vasavatti Devaloka (Sans Paranimmita-vasavatīn) or Vasavatī,—where life lasts 32,000 years. He has a position analogous to that of Ahriman among the Zoroastrians; is the lord of pleasure, sin and death,—the tempter, the evil principle, the representative of inherent sin. He is represented as riding on an elephant, and attended by the Mārakāyikas. He has a hundred arms and assumes monstrous forms. He owes his exalted rank to his having in a previous birth exercised a high degree of charity. His realm (Māradheyya) is that of re-birth as opposed to Nirvāna.²

The pantheon, however, is otherwise vague and accessory: in the legends a confused crowd of Devaputtas—‘sons of the gods’—appear; names are mentioned even, such as Mālābhārī or Mālādharī—‘garland bearer’; but these names are ephemeral for beings living a life of pleasure in their heavens—an idealized representation of Indian royal courts. Notwithstanding the magnificence of the representations set forth, the principal theme of the legends is the inculcation of the vanity of sensuous pleasure and the brevity of human life. It is very evident that this tendency of the texts—which are undoubtedly very old—was by no means calculated to develop plastic figures of individual gods.

One divinity only appears as a fully developed type and is always reproduced with a certain evident pleasure; it is the ideal of the Indian woman, the goddess of beauty, of prosperity, of domestic blessing, of wealth: Pāli, *Srī*; Sanskrit, *Śrī* (Lakshmi). The worship of this popular goddess must have prevailed, in Buddhist times, throughout the whole of India. *Strī* and *Śrī*,



11. THE GODDESS ŚRĪ (ŚRĪ).
From the east gateway at Sāñchī, conf. ill. 39.

¹ Conf. Burnouf, *Int. Bud. Ind.*, 2d ed., pp. 116, 532f, 540f; Rhys Davids, *Buddhist Suttas* (Sac. Bks. of the East, vol. XI), pp. 162f.

² Conf. Burnouf, *Int. Bud. Ind.*, 2d ed. p. 68a.

"woman and goddess of fortune," says a still current proverb,¹—which affords a valuable reminiscence from Indian antiquity, according to the conception of which woman was by birth the equal of man.² Śrī, as Tyche or Fortuna, is frequently represented on gates, stone-railings, &c. Of special interest is the type at Udayagiri, where it is fully developed; it appears in the Barāhat (Bharhut) sculptures



15. THE GODDESS TIRUMAGAL (Śrī).
Wood carving from a side chapel of the temple of
Mīnākṣhi at Madurā, S. India.

and is frequently repeated at Sāñchi.³ Śrī is represented as a woman in the costume and ornaments of a Hindu, seated or standing on a lotus-flower; two of her hands (when she is represented with four) are empty, the other two are raised each holding a water-lily, while two white elephants, holding water-pots in their trunks, water the flowers in her hands. Even to this day this oldest type is firmly established in the Brāhman miniatures. The representation is of unusual interest because it forms the Indian analogy to the Greek Aphrodite Anadyōmene. According to the legend in the *Rāmāyana*, she sprang from the froth of the ocean when it was churned by the gods. This is not the place to enter on the mythological accounts of the goddess: it is enough to indicate that the type of Śrī on the early Buddhist monuments is an ancient and undoubtedly indigenous one.

Among the pillar sculptures from Barāhat,⁴ there appears a series of gods that are of uncommon interest as much mythologically as in relation to art history.

Among these is Śrī called "Śirīmā devata," represented in the dress and ornaments of a Hindu woman with largely developed breasts. She holds in her right hand a flower, now broken. All these figures, in imitation of Western Asian deities,⁵ stand upon

¹ Manu; *striyā Śrīyācha gehoshu*.

² Tiruvalluvar, the Tamil poet of the weaver caste, in his *Kural* (v. 1082), styles the woman in full attire "the goddess Śrī attacking with an army's might":—

"She of the beaming eyes,
To my rash look her glance replies,
As if the matchless goddess' hand

Led forth an armed band." (Dr. Pope's tr.).

For Śrī or Lakṣmī, see *Viṣṇu Purāṇa*, Wilson's tr., Hall's ed., vol. I, pp. 118-120, 144-5.

³ *Cave Temples*, p. 74, and pl. 1; Cunningham, *Bharhut Stūpa*, pl. xxxvi, fig. 1; Fergusson, *Trees and Serp. War.*, pp. 112, 113, 120.

⁴ Cunningham, *Bharhut*, pls. xxi-xlii. Minayeff, *Recher. sur le Bouddhisme* (Ann. Mus. Guimet), pp. 93-102, 138-152, examines the divinities represented as compared with the texts.

⁵ Kubera treading on a Yakṣa is a type preserved even in Lamaism and Japanese Buddhism. Kubera and Virūḍhaka are two of the so-called Lokapālas, again referred to. We have here the origin of the creatures called *vāhāna* (vehicles) on which the Hindu gods stand or ride. Conf. the remarks below on Garuḍa.

their attributes ; thus, Kubera, king of the demons called Yakshas, stands on a pointed-eared, thick-set demon, and the Nāga king on a piece of rock in which are seen heads of snakes, in front a pond with lotuses. Two Yakshini, females, stand on Makaras (fig. 16). In others the attribute or cognizance under the feet is wanting, and they stand instead on elephants or on a stone fence, as it were, on detached parts of a Torana, in order to equalize them with those standing on their attributes as pedestals.¹ Two or three of these women stand under a tree, and raise their hands among the branches as if to pluck the blossoms. The same subject is met with decoratively treated under the *sūchis* of the gateways at Sāñchi.²

Another Hindu divinity also occurs, though rarely, among the early Buddhist sculptures. This is Sūrya, the sun-god (Gr. Helios)—evidently an importation from the north or Central Asia. He is the only member of the pantheon who is represented as clad from the feet upwards to the bosom ; he wears a girdle, *avyaṅga* (Baktrian, *aiwydonka*) about his waist ; and is usually represented in a chariot drawn by four (or seven) horses, and attended by two females. Examples of this divinity occur on a pillar of the old rail at Gayā, in the early cave at Bhājā, and in the Ananta cave at Udayagiri.³

With these we terminate the types of national gods represented as human beings so far as they come under our consideration. For the sculptors of that age it was more difficult to represent the other mythological beings. The lower divinities had to be moulded after fixed types ; for they play a large part in the *Sūtras* already mentioned.



16. PILLAR FIGURE FROM BARĀHAT DESCRIBED IN THE INSCRIPTION AS THE YAKSHINI CHANDĀ. Cunningham's *Bharhut*, pl. xxii.

¹ The reliefs of Bhātemar (Mathurā), Cunningham, *Arch. Sur. Ind.*, vol. III, pl. vi and xi, are certainly not Buddhist (probably Jaina). These very erotically represented groups, which Curtius has so pertinently described (*Arch. Zeit. N.F.*, Bd. VIII, 1876, Ss. 95f.) have no trees in blossom behind them. A noteworthy parallel in mediæval art is supplied by statues standing on "the evil principle," and one that resembles the *vāhanas*, the mediæval personifications of the virtues and vices standing or riding on animals. E. P. Evans, *Animal Symbolism in Ecclesiastical Architecture*, p. 183.

² Fergusson, *Tree and Serp. Worsh.*, pl. xlii.

³ See Rajendralāl Mitra's *Buddha Gaya*, pl. 1 ; Cunningham, *Arch. Sur. Ind. Rep.*, vol. III, pl. xxvii ; and Fergusson, *Archæol. in India*, p. 34. Sūrya also appears on the Lahauri Lota ; *Arch. Sur. W. Ind.*, vol. IV, p. 6.

As explained above, the connexion with liān introduced into India a series of artistic forms which became the standards in sculpture as well as in architecture. From the series of hybrid creations that had come from Western Asia and that were employed decoratively, attempts were made to adapt certain forms to native purposes and to develop them into fixed types, whilst closely related forms continued to be purely decorative. The character of the old Indian reliefs that were also decorative rendered this transition easy. Let us now enumerate the different beings for which early Buddhist art required types, and thus we shall have the opportunity of pointing out how extensive was the hold taken by the hybrid style of Western Asia, and how, on the other hand, the art imagination adapted the borrowed forms for its own needs, nationalized them, and in some cases succeeded admirably in re-animating and developing them,—evidently because indigenous types of a similar character already existed. Much inconstancy in the forms, to which names can hardly be given, is specially remarkable; even those types that we can name do not preserve their similarity, and a series of imaginary shapes crops up, as in early Roman art, in which antique elements—sirens, centaurs, &c., still continued in a way to exist, though no longer intelligible. The similarity between ancient Buddhist art and the monuments of early Christian times, without direct contact being necessarily assumed in every case—becomes greater still when the Græco-Baktrian (Gandhāra) types are introduced.

We shall commence with a type in which the human element still



17. GODS AND MEN (DEVAMANUSSĀ) WORSHIPPING A STŪPA.
On the east gateway at Sāñcī.

plays the principal rôle,—the so-called Nāga. Indian popular belief, whose conceptions were moulded later by the official Brāhman religion, besides demons of every sort, giants, &c., recognises

a much venerated class of snake-gods (Nāgas). We cannot undertake an examination of the origin of this belief, which is unknown to the Vedic age, suffice it to say that besides the world of gods and men there are eight classes of demigods which the Buddhist writings generally enumerate in the order—Devas, Nāgas, Rākshasas, Gandharvas, Asuras, Garuḍas, Kinnaras, and Mahoragas,¹ but the Yakshas often take the third place instead of Rākshasas.

The second class form a separate snake world, the inhabitants of which have the power of assuming human forms. They are fabled to reside under the Trikūṭa rocks supporting Mount Meru, and also in the waters of springs, lakes, rivers, &c, watching over great treasures, causing rain and certain maladies, and becoming dangerous when in anger. They are the subjects of Virūpāksha, the red king of the western quarter and probably the Buddhist form of Śiva, who is well known in Hindu mythology as Virūpāksha as well as Nāganātha and Nāgabhūshana. Chiefs or kings of the Nāgas are named in the legends and their deep reverence for Buddha, which puts men to shame, is specially characteristic of them. The wonderful alms-bowl of Buddha is, according to the legend, a gift from the demigod kings of the four quarters. More than once, Nāga chiefs approached the Master,—thus Muchilinda, the tutelary deity of a lake near Gayā, protected him from the rain; Apalāla, the guardian Nāga of the source of the Swāt or Subhāvastu river in Udyāna, was converted by Śākyamuni shortly before his Nirvāṇa; Elāpatra (Erapato, Sans. Airāvata), another Nāgarāja, consulted Buddha about rebirth in a higher condition, and Chakravāka



18 A NĀGA RĀJA.

From a fresco in Cave I at Ajantā;
Griffiths' *Paintings in the Ajantā Caves*

¹ The Jains also enumerate eight divisions of their Vyantara gods, viz.:—Pisachas, Bhūtas, Yakshas, Rākshasas, Kinnaras, Kimpurushas, Mahoragas (hoas), and Gandharvas. See note 2, p. 47. Each of the Tirthankaras has an attendant Yaksha and Yakshini.

Nāga is figured on a pillar at Barāhat¹ Even in the ritual for admission to orders, the question was introduced whether the candidate was not a Nāga.

Thus it was necessary to represent Nāgas typically in the body of the compositions illustrative of the life of the founder of the religion, and yet in the scenes in which they appear in the legends they could be properly represented only in human form. The problem was admirably solved; the Nāgas were represented as human, and, in the manner of the Egyptian Uræus-snake, a serpent—usually many-hooded in the case of a male, but single-hooded



10. NĀGA AND NĀGINĪ IN WATER.

On a wall-painting in Cave II at Ajanta, from Griffiths' *Paintings*.

for a Nāgi—was placed over the head (or rather springing from behind the neck) as ornament (See figs. 8, 18, 20). We do not maintain that this type is to be regarded as a result of contact with western Asiatic art, but neither must we reject it unconditionally, for the Nāgas were represented in other forms also as hybrid creatures. The Nāga in human form with the snake-hood has been retained in Buddhist art in all its ramifications, and is found

¹ *Real, Romantic Hist. of Buddha*, pp. 276ff; *Si-yu-ki*, vol. I, p. 37; Rockhill, *Life of the Buddha*, pp. 84, 46f., 244f.; Cunningham, *Bharhut Stūpa*, p. 27, &c.

also in the Chino-Japanese, where snake-kings are represented as men in Chinese costume, with a dragon on the back of the neck, whose head appears over that of the human form. Along with this human shape is also found a purely animal one. Sometimes even both appear in combination (conf. ill. 19): snakes the upper part of whose bodies are human, their heads crowned with serpents' hoods, while the lower part of the body from the hips downwards is purely animal. This is, iconographically, the proper form of the Nāga, and they are so represented whenever they appear in their proper element—water, and so we find them pictured in the Ajantā wall paintings (fig. 19). These forms are employed by preference decoratively, or as accessory figures in larger compositions of the purely human Nāgas with snakes as head ornaments. But this type may certainly be regarded as derived from west Asian prototypes. It is allied to the creatures with fish tails that are represented with human bodies: apparently mostly of the female sex—the so-called Matsyanāris—'fish girls.' From this type, modern Brāhman art has evolved the representation of Gaṅgā and Yamunā, the goddesses of the Ganges and Jumna. Together with the creatures with fish tails and human busts, there are also decorative figures with animal bodies, on which a few words will be said.



20. NĀGA, from Ajantā, Cave II.

Yakshas (Pāli, Yakkhas) appear frequently in Buddhist legend and iconography, being usually enumerated as in the third rank of the secondary gods. Their king Kubera, Vaisravaṇa or Alakesvara, is guardian of the north, and his capital is Alakā or Alakamandā. But the other three guardians were also styled Yakshas; and we find various individual Yakshas named, as—Alavaka, Sātāgera, Bemāwata, Pūrṇaka, Virūdaka, Gaṅgita, Suchiloma, Supavasa (Suprāvriṣha), Nandaka, &c. They are always represented in human form. At Barāhat they appear as guardians or *dvandrapālas* at the gateways; at Nāsik also, one at the entrance of the Chaitya-cave is indicated in an inscription as a Yakkha, and the two figures by the door of Cave III bear the same character. At Barāhat, Yakshinis also are figured on the pillars at the entrances,—as Chadā (Chandā) and Sudasava Yakkhini.¹

¹ Sp. Hardy, *Man. Budd.*, pp. 58, 269, 265f., 271, 272n.; *Quest. of Milinda* (in *S. Bhs. East*), vol. I, p. 162; Cunningham, *Bharhut*, pp. 19f.; Burgess, *Cave Temples*, pp. 268, 274, and pl. xx and xxv.

The *Dulva* (xi. fol. 34b) gives us a sort of key to the frequent representation of Yakshas as *dvaḍḍapālas*: Anāthapīṇḍada asks the Buddha how the vihāra must be ornamented with paintings (or sculptures). The Buddha answers—"On the outside door you must have figured a Yaksha holding a club in his hand; in the vestibule, you must have represented a great miracle, the five divisions (of of beings) the circle of transmigration; in the courtyard, the series of births (*jātakas*); on the door of the Buddha's special apartment (*gandhakūṭi*, 'hall of perfumes'),¹ a Yaksha holding a wreath in his hand; in the house of the attendants (or, of honour: *vim-gro*), bhikshus and sthaviras arranging the *dharma*; on the kitchen must be represented a Yaksha holding food in his hand; on the door of the storehouse, a Yaksha with an iron hook in his hand; on the water-house (well-house?), Nāgas with various ornamented vases in their hands; on the wash-house (or, steaming-house: *bsrō-khang*), foul sprites or the different hells (*ndrakas*); on the



21. A GANDHARVA OR KINNARI.

From Ajanta wall-paintings.

medicine-house, the Tathāgata tending the sick; on the privy, all that is dreadful in a cemetery; on the door of the lodging-house (? text effaced), a skeleton, bones, and a skull."²

But if, in the representations of the Nāga, the human element predominates and so affords the principal factor in distinguishing them, the identification of the winged figures is more difficult. Winged animals occur in such numbers that it is impossible to provide them all

with Indian names. A series of representations, however, stand out conspicuously from among those that are purely decorative.

Next to the human figures are the hybrid creatures with human busts, Indian head-dress and ornaments, represented so frequently

¹ Burnouf, *Introd.*, 2d. ed. p. 234; *Lotus*, p. 305; Childers. *Pali Dict.*, s.v.; *Ind. Ant.* vol. IX, pp. 132-3.

² From Rockhill's *Life of Buddha*, p. 48, note 2.

at Sâñchî. The lower part of the body is that of a bird on which the hips of the human form are set; the bushy tail, intended for that of a peacock, is treated decoratively. On the reliefs they appear flying from both sides towards the holy places,—stûpas, foot-prints, sacred trees, &c., and are hanging offerings upon these objects of worship—flowers, strings of beads, &c.—and thus frequently accompany the human worshippers (man and woman) of the under part of the relief: a well defined, oft-employed phrase, which occurs so frequently in the texts, corresponds to this—"gods and men there offered wreaths, &c." In this decorative form these winged creatures are still to be found in modern Brâhman art (Conf. ill 15). They passed also into the Gandhâra school, but with marked differences. The antique Eros type has supplanted the early forms,—so that figures resembling the angels of Christians are found (conf. illus. Le Bon, *Les Civilisations de l'Inde*, p. 251; *Four. Ind. Art and Indust.* vol. VIII, p. 74). The form occurring at Sâñchî (conf. ill 4 and 17) and Barâhat is worthy of notice because its wings are really used, so that they are not simply attributes of speed.¹

The positions assigned to these figures seem to agree best with the characters assigned to the fourth class of demigods—the Gandharvas (Pâli, Gandhabba)—the musicians of Sakra, who join with their master to serve and worship Buddha.² Modern art, however, also represents the seventh class, known as Kinnaras and Kinnaris, by the type above described, as the modern Siamese painting in fig. 23 shows. The two classes, in fact, have got mixed up or confounded.



22. 'KINNARAJĀTAKA.'
Cunningham, *Bharhut*, pl. xxvii, 5.

Notwithstanding the west Asian form of the wings, the type is a purely Indian one, and the time of its origin can hardly be fixed. As to the Siren form of representation of the Kinnaris, there is a Barâhat relief which, if it were more distinct, might afford a sug-

¹ Cunningham, *Bharhut*, pl. xiii, 1, xxxi, 1.

² See Feer, *Avadâna Sataka* (Ann. Mus. Guimet, t. XVIII), pp. 58, 77, 88; *Lahita Vistara*, passim. The Gandharvas or Gandharbas, in Brâhman mythology, belong also to the class of secondary gods, or attendants; this class includes—(1) Kinnaras, having a human body with the head of a horse,—musicians in the retinue of Kuvera; (2) Kimpurushas, with a human face and the body of a bird, are often confounded in later times with the Kinnaras and Gandharvas; (3) Gandharvas are similarly represented with a human bust on the body of a bird; their wives are the Apsaras, their chief Chitrângitha or Supriya, and they are the attendants of Dhritarâshtra (Dhatarattâs), guardian of the East; (4) Pannagas or Nâgas; (5) Siddhas, who fly in the air and can appear anywhere in a moment; (6) Vidyâdharas, the celestial students, skilled in all knowledge; and besides these, the Yakshas, Rakshasas, &c. For some of these monstrosities, see Rajendralâl Mitra, *Buddha Gaya*, pls. xxxiii, xxxiv, xxxvi, xxxviii, xlv, xlv, and xlvii.

gestion (ill. 22) In it are a pair of such creatures so represented as to be seen only to the knees and who appear to be wearing leaves of trees round the body (*parna*: leaf and feather) These secondary deities, then, may have been originally represented in the costume



23 MODERN SIAMESE PAINTING. KINNARI.

of the aborigines of India, which, by borrowing from the antique, resulted in the siren type

The names *deva*, *devatā*, 'divinity,' but in the sense of 'angel,' will suffice generally to designate this whole class of gods, which is apparently unlimited. The type is still retained in Japanese art, as fig. 24 shows

Another type, the development of which may to some extent be observed in the sculpture at Sāñcht, is nearly allied in its form to these demi-gods. These are the sixth class or *Garuḍas*, the

winged steeds of important divinities, which appear among those thus described, in some sort as princes. In India the representation of a *Garuḍa* bird is of extreme antiquity, but a systematic account of this mythical creature is extremely difficult; only what is certain and of value for the explanation of Buddhist sculptures need be mentioned. The Indian popular belief recognizes the *Garuḍa* or *Suparna* (Pāli: *Garuḍa* and *Supanna*) as the king of birds; he is the deadly enemy of the snakes, the *Nāgas* described above, which he kills and injures when he can. A kind of vulture, called *Garuḍa*, and living on snakes, can hardly form the foundation of the ancient allegory; possibly it is of Iranian origin, related to the legends of the *Sināurg*. From the myth, various birds have come

to be called Garuḍas in different districts.¹ How this representation is connected with the Vedic one, which recognizes a solar-being (I) Garutmant, has no bearing upon our purpose. Only this, perhaps—



24. THE GODDESSES KARIÖBINGA AND TEN-NIN.
From a Japanese woodcut.

in the Buddhist *sūtras* (*Jātakas*) the antagonism of the Garuḍa, Nā-gāntaka, or Tārکشya, to the snake plays a prominent part.²

In some places, according to the popular belief, the Garuḍa, Suparna, or Tārکشya, is represented, like the Nāga, as also



possessing the faculty of assuming human form. Buddha, or one of his disciples, is shewn making peace between the two creatures, and we find both at the feet of the Sage imploring better incarnations.


On the relief from the east gateway at Sāñchi, given in fig. 26, the

¹ In S. India the *Falco pondicherryanus* or red Brāhmani kite, which is a sort of dwarfish fishing eagle, but not probably a destroyer of snakes, Garuḍa seems to be chiefly applied in the S. Marāṭha country to *Circus Gallicus*, a widely distributed and conspicuous bird, and certainly a snake-eating eagle. In Kanara the name is also given to the Great Hornbill (*Dicorhynchus bicornis*), of remarkable appearance, and which eats snakes occasionally. See Jerdon, vol. I, p. 77.

² For the Vedic, Epic, and other legends and allusions,—see De Gubernatis, *Zoological Mythology*, vol. II. pp. 180-185. The Buddhist drama, ascribed to king Śrī-Harṣhaḍeva, on the deliverance from Garuḍa, of Sankhaśūda of the Nāga race, has been translated into English by Mr. Palmer Boyd (1872), and into French by M. Abel Bergaigne (1879).

25. DEITIES RIDING
ON GARUDAS. From a
relief at Sāñchi.

animal kingdom is represented adoring the holy fig tree. In the corner, beside a five-headed snake, evidently the king of the Nāgas,



26. THE ANIMAL WORLD REVERENCING A SACRED TREE (Bodhi tree)
A relief from the inner side of the second architrave of the east gate at Sāñcht

stands a large bird with ear-ornaments and big bushy tuft, represented on the whole like a great parrot, and thus a purely Indian type, while his wings again show the artificial forms of west Asiān art. This is assuredly the Garuḍa, with the Nāga, whose mortal enemy he is. This parrot-like creature has scarcely had any successors in Indian art, but it is clearly the ancient national representation. Now, on the same relief, along with the splendidly drawn Indian animal realm—Indian buffaloes, extraordinarily true to nature, and, depicted almost with a touch of humour—are very artificial lions, leonine creatures with dogs' heads, lions with griffin-like heads. On other reliefs these last creations of west Asian fancy appear with wings, as represented above, as vehicles of the gods who, along with the so-called Kinnaras, ride upon them through the air to worship at holy places. It is interesting, to notice that the artificial-like wings of west Asian art again appear here. Evidently it is the Indian feeling for Nature that reanimates these appendages that had been stiffened into a symbol. From these last-named forms the Garuḍa was afterwards developed, as the Gryps, Gryphus or griffin, was in Greece.

But the man who composed the sculpture shown in ill. 26 saw other things. In the middle of the relief we find oxen with human

faces, long pointed beards and finely twisted manes, every lock of which is represented according to rule; these are derivatives of the Assyrian cherubs. They are still more like the ancient Greek river-gods. If this idea is the correct one, they serve

to indicate locality and belong properly to the same category with the buffaloes always wallowing in the water. Another explanation seems more correct; a few words on this will follow in another connection.

The picture affords a new and interesting parallel with the Greek griffin in the dog-headed lions on the left side above the griffin itself. This representation reminds one of the treasure-guarding griffins of Ktesias, which I think have been correctly identified by Ball with the great shaggy Tibetan dogs; they are the prototype of the so-called Korean dog.

The relief in fig. 26 contains at any rate a series of variations upon one theme—the representation of the *Garuda*, for which—in a groping way—foreign types have been introduced, the names of which perhaps sounded like the Indian word. The native parrot type on the one hand, the west Asian



27 JAPANESE TEN-GUS (*Garudas*).
From a woodcut by Hokusai.



28. GARUDA FIGURES, from Ajanta paintings, Cave 17.

griffin on the other, are the bases upon which more modern iconography developed its *Garuda*.

The griffin type was retained in Buddhist art, but it soon received (when?) human arms; indeed the human element was sometimes even more prominent. Modern Brāhmaṇa art makes of it a winged man with a beak, and the Chinese form resembles it. There the *Garuda* (Thien-kou, celestial dog) appears as a winged man, though the head generally, and the feet always, remain animal (ill 29). The Japanese prefer to represent their Ten-gus (*Garuda*) as fabulous animals, and two types are employed—one more animal and the other almost human (conf. fig. 27). The way in which the Japanese

contrive to vary these hybrid creatures, for the purposes of ritual and caricature, manifests a masterly observation of the grotesque-comic, as well as of the weird elements of animal nature. Good



29. THIEH-KOU:
Garuda, modern
Chinese bronze.



30. KHYUNG:
Garuda, Lamaist
gilt bronze.

examples of purely human Garudas with wings and demoniac expression of countenance are to be seen in the British Museum sculptures from Jamālgarhi (conf. *Four. Ind. Art and Indust.*, vol. VIII, pl. xxvi, or sep. ed. p. 18 and pl. xxiv). In modern Nepalese temples, two figures of Garuda form the distinguishing supporters of Amoghasiddha, the fifth Dhyāni Buddha, who, like the Jaina Pārsvanātha, is depicted with a seven-headed snake as

a canopy or nimbus. And in the shrines Garuda is often represented with a serpent in his beak and a Nāgakanyā in each claw.

Such are the types to which names can be given among the subordinate gods in the art of the Asoka period, with their offshoots in modern miniature art. The horse-headed female figure on the Asoka railing at Buddhagaya stands almost alone and is no doubt of purely Indian origin (conf. Rājendralāl Mitra, *Buddhagaya*, pl. xxxiv, 2, and Griffiths, *Ajanta*, vol. II, pl. 142). It agrees with the usual description of the Kinnaras; and we have goat and ram-headed beings in Naigameya, a sort of companion of the war-god Skanda; in Harinegameś, the deer-headed general of Indra; in Daksha, and in the sculpture in the Kailāsa temple at Elura¹.

The combining of the human body with animal elements seems to have been brought gropingly, so to speak, into connexion with the doctrine of reincarnation. It is not impossible that these types, introduced from Western Asia, were explained in Indian fashion—i.e., in each degree of animal existence was hidden a human one which would be attained by good works, and which might then lead to deliverance. It is curious that Chino-Japanese tradition assigns to the centaur-like art-forms the name of Tiryagyoni² as the representatives of quadrupeds within the transmigratory gradation. It is thus not impossible that the centaur represented on the Asoka rail-

¹ *Epig. Ind.*, vol. II, p. 314, and pl. ii.; *Trans. R. As. Soc.*, vol. II, p. 326, and pl. i.; *Mult. Or. Sansk. Texts*, vol. IV, pp. 381, 384; Wilson, *Viṣṇu Purāṇa* (Hall's ed.), vol. I, p. 182n; Wilkins, *Hindu Mythology*, p. 309.

² Centaur-like figures as representations of the Tiryagyoni-gatas (Jap. *Chiku-shō*) are found in the section on 'Buddhist effigies' in the Japanese work *Gwa-zen*, i.e. 'Picture scroll,' of Hayashi Moriatsu, A.D. 1721, containing instructions for drawings and paintings, with many roughly drawn but strongly characteristic examples. The male and female Centaurs are, in Japanese fashion, distinguished by their costume — Dr. F. W. K. Müller.

ing at Gayâ, and hybrid forms thereto related, simply represent such transmigratory phases. The other emblems depicted on the Gayâ railing and the oxen with men's heads in fig 26, already mentioned, perhaps also belong to this category.

It has been stated that the Indian feeling for nature animated afresh even the fantastic forms of the western Asiatic hybrid style. A curious example of the way in which even animal forms when used decoratively were regarded as living animals may be here cited as it well illustrates the Indian character and shows off their childishly naive and invariably humorous disposition. When speaking of the wood-carving style, we have already noticed the chairs and throne-backs in which such interesting early forms have been preserved; but along with these, as illus. 8 shows, west Asian (Persian) winged animals have been introduced among the accessory figures. The rampant lions in the corners of the back of the throne, with or without wings, continue from that time a favourite motif for the ornamentation of pillars and columns of every description. Elephants are worked from the projecting cross-pieces which are ornamented with dragons' heads, and under the rampant lion a new form, the *Makara*—about which we must say a few words. On the specimen from Amarâvatî (fig. 8) little human figures appear on the side pieces also. We must doubtless imagine as similar the throne of king Vikramâditya, of which the legend tells, and whose little carved figures even relate stories.¹ A fragment of a throne, fig. 31, from the ruins of Nâlanda, shows the animals still more artificially: the old Indian dragons' heads, which remind one of German forms, have entirely disappeared; and instead appears the elephant. In the mediæval style of Drâvida (S. India, Mâdura, &c.) these pillar forms have been adapted to native conceptions, *i.e.* hunting scenes of the Kurumbars and the like, and have been further developed in a highly grotesque fashion.



31. FRAGMENT OF A THRONE, from the ruins of Nâlanda. (Conf. Nrs. 8, 82).

The absurd story of the *Sabbadâtha-jâtaka* shows that the popular Indian mind regarded these animal figures as real animals standing one upon the other. Even though the fable only makes sport of such art creations, it is sufficiently clear from it how far the Hindu by himself was from inventing such compositions, and how, on the contrary, his own feeling led him to again reduce these overloaded foreign forms. The story, which is interesting in more ways than one, may be given here from Mr. Rouse's translation in Prof. Cowell's edition.²

¹ Conf. on this B. Joly, *Mongolische Märchensammlung Siddhikâr und Ardâshi Bordâchi Chan*, Innsbruck 1868, xiff.

² Fraasböll, *The Jâtaka together with its Commentary*, vol. II, p. 243; Cowell's English version, vol. II, translated by W. H. D. Rouse, pp. 168ff.

"*As the haughty Jackal, &c.*" This story the Master told while staying in the Veluvana, about Devadatta. Devadatta, having won favour in the eyes of Ajātasattu, yet could not make the repute and support which he received last any time. Ever since they saw the miracle done when Nālāgiri¹ was sent against him, the reputation and allowances of Devadatta began to fall off. So one day, the brethren were all talking about it in the Hall of Truth: 'Venerable brother, Devadatta managed to get reputation and support, yet could not long keep it up.' And the Master came to them with the question: 'What story, O monks, do ye sit and discuss?' and when they had told him, he said 'Not only now has Devadatta thrown away all chance of benefits this happened in olden days in just the same way.' And then he told them an old-world tale:

"Once upon a time, when Brāhmadatta was king of Bārānasi, the Bodhisattva² was his house-priest, and he had mastered the three Vedas and the eighteen branches of knowledge. He knew the spell entitled 'Of subduing the World.' (Now this spell is one which involves religious meditation). One day the Bodhisattva thought that he would recite this spell; so he sat down in a place apart upon a flat stone, and there went through his reciting of it. It is said that this spell could be taught to no one without use of a special rite; for which reason he recited it in the place just described. It so happened that a jackal lying in a hole heard the spell at the time he was reciting it, and got it by heart. We are told that this jackal in a previous existence had been some Brāhmaṇa, who had learned the charm 'Of subduing the World.' The Bodhisattva ended his recitation and rose up, saying—'Surely I have that spell by heart now.' Then the jackal arose out of his hole and cried—'Ho Brāhmaṇa! I have learnt the spell better than you know it yourself!' and off he ran. The Bodhisattva set off in chase, and followed some way, crying—'Yon jackal will do a great mischief—catch him, catch him!' But the jackal got clear off into the forest. The jackal found a she-jackal, and gave her a little nip upon the body. 'What is it, master?' she asked. 'Do you know me,' he asked, 'or do you not?' 'I do' know you.' He repeated the spell, and thus had under his orders several hundreds of jackals, and gathered round him all the elephants and horses, lions and tigers, boars and deer, and all other four-footed creatures; and he became their king under the title of Sabbadātha,³ and a she-jackal he made his consort. On the backs of two elephants stood a lion, and on the lion's back sat Sabbadātha,

¹ A great elephant, which, at Devadatta's instigation, was let loose for the purpose of destroying the Buddha, but which only did him reverence; "non fecit hoc jussu nulloque docente magistro: crede mihi, nostrum sensit et ille deum." Hardy, *Manual of Buddhism*, p. 331; *Milindapañha*, iv, 1 (Sac. Bks. of the East), vol. i, p. 288.

² Buddha in a previous existence.

³ Reading *djāḍḍmi*.

⁴ The name signifies 'All-tusk,' 'All-biting,' Sansk. *Sarvadanta*: a play on the word *Sabbarattha*, Sansk. *Savarakṣa*—'All-ruling.'

the jackal king, along with his consort the she-jackal, and great honour was paid to them. Now the jackal was tempted by his great honour and became puffed up with pride, and he resolved to capture the kingdom of Bārānasī. So with all the four-footed creatures in his train, he came to a place near to Bārānasī. His host covered twelve leagues of ground. From his position there he sent a message to the king. 'Give up your kingdom or fight for it.' The citizens of Bārānasī, smitten with terror, shut close their gates and stayed within. Then the Bodhisattva drew near the king and said to him, 'Fear not, mighty king! leave me the task of fighting with the jackal king Sabbadātha. Except me, no one is able to fight with him at all.' Thus he gave heart to the king and the citizens. 'I will ask him at once,' he went on, 'what he will do in order to take the city.' So he mounted the tower over one of the gates, and cried out—'Sabbadātha, what will you do to get possession of this realm?' 'I will cause the lions to roar, and with the roaring I will frighten the multitude: thus will I take it!' 'Oh! that's it,' thought the Bodhisattva, and down he came from the tower. He made proclamation by beat of drum that all the dwellers in the great city of Bārānasī, over all its twelve leagues, must stop up their ears with flour (dough). The multitude heard the command, they stopped up their own ears with flour, so that they could not hear each other speak—nay, they even did the same to their cats and other animals.

"Then the Bodhisattva went up a second time into the tower, and cried out, 'Sabbadātha!' 'What is it, Brāhmaṇa,' quoth he. 'How will you take this realm?' he asked. 'I will cause the lions to roar, and I will frighten the people and destroy them, thus will I take it!' he said. 'You will not be able to make the lions roar; these noble lions, with their tawny paws and shaggy manes, will never do the bidding of an old jackal like you!' The jackal, stubborn with pride, answered, 'Not only will the other lions obey me, but I'll even make this one, upon whose back I sit, roar alone!' 'Very well,' said the Bodhisattva, 'do it, if you can.' So he tapped with his foot on the lion, which he sat upon, to roar, and the lion resting his mouth upon the elephant's temple, roared thrice, without any manner of doubt. The elephants were terrified and dropped the jackal down at their feet; they trampled upon his head and crushed it to atoms. Then and there Sabbadātha perished. And the elephants, hearing the roar of the lion, were frightened to death, and wounding one another, they all perished there. The rest of the creatures, deer and boars, down to the hares and cats, perished then and there, all except the lions; and these ran off and took to the woods. There was a heap of carcases covering the ground for twelve leagues. The Bodhisattva came down from the tower, and had the gates of the city thrown open. By beat of drum he caused proclamation to be made throughout the city: 'Let all the people take the flour (dough) out of their ears, and they that desire meat, meat let them take!' And the people all ate what meat they could, fresh; and the rest they dried

and preserved. It was at this time, according to tradition, that people first began to dry meat "

"The Master having finished this discourse, identified the Birth by the following verses, full of divine wisdom :—

"Even as the jackal stiff with pride,
Craved for a mighty host on every side,
And all toothed creatures came
Flocking around, until he won great fame :
Even so the man who is supplied
With a great host of men on every side,
As great renown has he
As had the Jackal in his sovereignty.

"In those days Devadatta was the Jackal, Ananda was the king, and I was the chaplain."



32. CHANGCHA-HUTUKTU LALITAVAJRA.

For the ornamentation of the throne compare ill. 8 and 81.
From a miniature on silk, 18th century.

It is clear that a throne like the one shown in figs. 31 or 32 was in the mind of the narrator of the *Jātaka*. The ancient Oriental idea of imagining the subject, the vanquished, as lying under the feet of

his conqueror, is interesting here. But this motif also originated in western Asia, where, in Assyrian reliefs for example, upright figures of gods are clumsily placed on the backs of animals, like one hieroglyph upon the other, without the slightest attempt at appropriateness. The Indian love for nature, which was only too strongly developed, gives a burlesque interpretation to the idea. The throne-seats with ornaments, just described, have been preserved even in the latest Lamaist ecclesiastical style of Tibet and China. Ill. 32 represents the throne of a Lamaic ecclesiastical prince, the original is found in a splendid work painted on silk, dating from about the middle of last century, and containing the genealogy of the so-called Changcha Hutuktu of Pekin. The holy man sits on a throne, the back of which consists of two elephants, with two lions above them, and two goats with riders above these again; higher up still are seen two elephants apparently running downwards, and in the middle a *Garuda* and *Nâgas*. All these are the decorative elements of ancient wooden doors and throne-backs loosely superposed on one another.

The sea-elephant, *Makara*, a creature formed of the forepart of an elephant with the body and tail of a fish, appears even on the reliefs of the Asoka railing at Buddhagayâ, along with winged elephants and hippocampi,¹ &c. It has been retained everywhere in Indian art, though later the fish-tail was made into an ornament. When, later still, it became the ensign of Kâma, the Indian god of love, it was due, as has long been recognised, to Greek influence: the dolphin of Aphrodite supplied the model.



33. MAKARA. From the pattern on the dress of the old Javanese *Manjuri*.

All the Greek elements found within the Asoka period, even counting the Sâñchi monuments, follow throughout, as it were, in the steps of the west Asiatic forms. Altogether there are not many: representations of centaurs, and water-gods (oxen with human faces). Of more importance is the question whether the thunderbolt as an attribute of gods, was introduced by Greek influence, or whether the streaming sheaf of lightning-flashes of the Babylonian-Assyrian gods should be considered as the model; though the former seems to me the most probable, no certain proof is forthcoming. This must depend on the date of its introduction and the extent of the western influence at the time.

I cannot here enter upon the subject of the representation of the dwarfish creatures, which are regarded sometimes as real human dwarfs and sometimes as evidently demi-gods, nor upon so much that is connected therewith. But I would like to point out that the

¹ Rajendralâl Mitra, *Buddha Gaya*, pl. xlv; Cunningham, *Mahâbodhi*, pl. ix, 15; another as a pillar ornament. Burgess, *Cave Temples*, pl. xvi, 6.

type is the same as that of the antique pigmies. (Conf. above, p. 34). It is interesting to observe that the account of the pigmies, like that referred to on p. 49 of the griffins of the west, is given us by Ktesias,¹ who was physician to the Persian king Artaxerxes Mnemon (405-362 B.C.).


This concludes the series of the types found in older Buddhist art. The question now is, how the composition is to be executed. The form of composition, with which every art begins, is the pure narrative. In what follows we shall try to discover how far the art of the Asoka period (including Sāñchi) represented this narrative tendency and how the national character made itself felt thereby.

On the reliefs of the great gateways of Sāñchi is a series of representations of different kinds. Many are purely decorative, others represent perfectly definite historical events. Very few have, as yet, been fully explained, and for those that have been correctly explained, the convincing proof is not yet forthcoming; but they may be divided into two distinct categories. The first category, by the help of numerous figures in a series of formally composed scenes, all resembling one another, depicts—processions to holy places, to sacred trees, to stūpas, etc. On the panel itself there nowhere appears an indication which sufficiently characterizes the incident to enable us to determine it from itself alone. Only inscriptions, like those found at Barāhat, could—so to speak—make of those incidents historical events. The elements that determine the incidents are solely external, as we shall see below. Along with the representations of human beings (of which those seen in illus. 4 and 17 are, as it were, conventional abridgements), we meet with others in which forms of existence other than human come to worship at the holy places. Here, again, a national Indian element makes itself felt—the fondness for the repetition of ritualistic phrases, which thereby become more sacred and efficacious.

The animal world, again, shares also in the worship of the sacred places. Along with animal-representations, that are uncommonly true to life, come in throngs the monsters of mythology, to adore the places where a saint has lived, in order to obtain a better incarnation. The juxtaposition of mythical and real animals has a highly startling effect: it looks as if the uncommonly animated and characteristically represented animal world was intended to impart a greater probability of existence to the fantastic creatures of very varied styles depicted beside them. While the latter, the Tiryaṅgini-type, Garuḍa, etc., stand stiffly in rows (conf. illus. 26), the life of the real animals makes itself felt; alongside a Garuḍa, adorned with earrings and carrying a lotus-flower, an antelope (*cerp. capra*—Indian gazelle or spotted antelope, Skt *Kṛishnasara*). in a curious position, is trimming itself. The religious act—in a truly Indian fashion—becomes a Nature-scene.

¹ *Laoset, Ind. Art. et. Hist.*, Bd. II, Ss. 641, 661; *Ind. Ant.*, vol. X, pp. 220-331.

If, owing to the objects represented, this change appears a very natural one, neither is it lacking in the representations of human beings. Ill. 34 shows the end of a long procession leaving a thickly peopled city. The gate of the city is of the same form as the gates of Sāñchi, though much simpler; the great volute looks almost like the rolled-up tongue of a dragon; the houses of the town are provided with open galleries, from which the inhabitants (men and



34. REPRESENTATION OF A CITY

From the second architrave of the east gateway of the great stūpa at Sāñchi.

women) look down. This looking down from house-terraces is an element that became frequent in Greek art—very late, it is true—for the animation of the background; it belongs essentially to the old Indian art, which owes this form to the representation of towns in west Asian art. It forms a part of the composition—the rejoicing of the inhabitants of the town, who are witnessing the procession, is thus presented, exactly as ancient and modern Indian texts—and the Chinese pilgrims also—describe such feasts. The separation into little groups, each of which has its own interest, also begins here. The Indian character cannot endure the stiffly historic, and breaks up the whole into a series of genre-scenes.

The thickly-peopled terraces are the models of the superimposed storeys of the different heavens in the Buddhist universe.

A genre-scene in ill. 34, which has nothing to do with the main incident, shows a woman who has come through a postern in the city wall to fill her *lôṭā* with water from a pool. In the pool are growing water-lilies in flower; a second woman comes down the

same street to the pool, and this figure is made so large that the gate lintel passes right across her body like a paling. It is difficult to determine whether the elephant rider, or mahaut¹, coming along the street on an elephant, belongs to the end of the procession (conf. ill. 39), or is taking the elephant to the water; but the latter is more probable. I shall return to these narrative-reliefs again.

The second category represents scenes from the life of the founder of Buddhism, or from his previous existences, the Jātakas. In the case of these reliefs also, very few are satisfactorily explained, for the characteristic elements almost disappear beneath the accessories. We are therefore obliged to seek for purely external proofs (the arrangement of the sculptures on the monument itself); and the result is curious.

Few of the scenes represented are so clear and simple as the relief on the inner side of the right pillar of the east gateway, above. It undoubtedly represents the dream of Māyā, the mother of Buddha, in the briefest and simplest form. Above the sleeping woman is seen descending the elephant, in the form of which, according to the legend, Buddha came down to his mother. One is struck by the paucity of detail: the detached treatment of this really notable representation. Its place, too (up in the corner above a rich composition of a different kind), is remarkable. Involuntarily one seeks for something corresponding. The highest panel of the inner side is a continuation of what is seen on the front. The front of the pillar is filled by a large relief consisting of three double stages, *i.e.* storeys. Each of these storeys is divided into three compartments by pillars. In each middle compartment there sits a god with the thunderbolt and a round bottle as attributes. The space behind the god shows a second god, clearly subordinate, and 'daughters of the gods' with sunshades and whisks (Hind. *chaurī*). In these divisions there is always a group of dancing girls playing on instruments before the principal divinity. The background is filled up with fruit trees.

Ill. 1 shows the fourth storey, counting upwards. The two below it are much injured, but still it may be clearly seen that the representation of the second storey corresponded with those that have been preserved, while the lowest of all was filled with weeping and mourning figures seated in a circle. At the very top of the relief there is, on the roof, a group of gods and goddesses. Unfortunately, this group is also much injured. If this highest terrace, the roof of the whole structure, is not counted, one is naturally reminded of the six Devalokas, the six inferior heavens² of the gods. All six form the so-called Kāmāvachara heavens, the


¹ Hind. *Mahaut*, Sansk. *Mahāmātra*, the German has *Kornak*, Fr. *Corneau*. See Yule and Burnell's *Glossary*, s.v.

² As to the heavens of the gods, the Kāmāvachara and Suddhāvāsa (Tib. *Gnus-gnus-mu-lha*)—an obscure expression—are attested at Barāhat by inscriptions. Conf. Hultzsch, *Zeit. d. Dent. Morg. Ges.*, Bd. XL, S. 65, Nr. 47, 48, 49.

abodes of the gods in which desire is still potent. Now it was supposed that when a Bodhisattva, a pre-existent Buddha, attained the lowest heaven, great lamentations broke out among the gods, who feared the end of an earthly period. A thousand years afterwards the cries of the guardians of the world (Lokapāladevatā—the gods of the lowest terrace) proclaim that in a thousand years a Buddha will be born upon the earth: the so-called Buddhahālahalam. The gods of the lowest terrace are represented lamenting; the subject must, therefore, be the birth of a being who is to become a Buddha. The panel is thus the beginning of all the pillar reliefs, and is continued on the inner side of the same pillar. The heavens are to be named as follows, beginning from below: the heaven of the Chaturmahārājika-gods, *i.e.* the four great kings or guardians of the world; the heaven of the Tāvātimsa-gods (Sk. Trayastrimsat), the so-called 'three and thirty' superior angels over whom Sakka presides; the heaven of the Yāmās, where there is no change of day and night: the Tusita-heaven (San. Tushita), where all Bodhisattvas are born before appearing on earth, and where Maitreya now is; the heaven of the Nimmānarati (Sk. Nirmānarati), who create their own pleasures; and of the Paranimmitavasavatti-gods, who indulge in pleasures created for them by others, and over whom Māra presides. These mighty terraces of the gods, mounting one above the other, over which again rise the meditative steps, belong to the grandest ideas which Buddhism has produced. The whole representation—this is not the place to examine it fully—with the ways of deliverance and the cataclysms which destroy whole worlds and put new creations in their place, had to be specially noticed here, for it is capable of affording us the necessary explanation of the representation on the other pillar (front side).

If we return to the reliefs which represent scenes from Buddha's life, we shall find that some of those on the left pillar of the east gateway are highly instructive as regards ancient Indian relief-composition. The first of them, which is found on the middle of the inner side of the pillar (conf. ill. 35) has already been correctly identified, so far at least as determining the incident is concerned, although the naming of the individual figures may not be quite correct. Towards the bottom and to the right on the panel is seen a bearded man with bands of hair (*jatā*) twisted about his head turbanwise; the knees of the crouching figure are held together by a band. This man (from his costume, evidently a Brāhmaṇa doing penance) is seated on the threshold of a hut thatched with leaves. Before him is a pond with aquatic birds and shell-fish; lotus-flowers are in bloom upon the water. Buffaloes and an elephant come to quench their thirst. A bearded ascetic is bathing, another is drawing water, with which to sprinkle his body in the bath, in a vessel shaped like the *lōtā*, which even at the present day answers this purpose. What has already been described is a rough representation (on a remarkably small space, though it is fairly broad)

of a Tīrtha or bathing-place at a river flowing past a Brāhmaṇa hermitage. Higher up, in the middle of the relief, may be seen a temple like house before which a fire burns upon an altar; a second vessel containing fire lies further forward, with tongs and fuel; on the left side, approach unbearded figures carrying fuel; the ordinary occupations of the Brāhmaṇa-disciples are thus represented. A row of Brāhmaṇas stand round the temple in the attitude of adoration; the background is composed of fruit trees, on which monkeys are climbing. Towards the man sitting before the leaf-covered hut, comes another Brāhmaṇa from the right to announce



35. RELIEF OF THE EAST GATEWAY AT SANCHI.
Left pillar, middle of the inner side. The first scene
of the conversion of Uruvilva-Kasyapa.

what is going on in the fire-temple; in the middle of the temple sits a seven hooded snake; flames burst forth from the windows in the roof.

This relief represents a scene from the story of the conversion, at Buddha's hands, of Kāśyapa (Pāli, Kassapa) of Uruvilvā (Pāli, Uruvelā), a Brāhmaṇa ascetic, with his brothers and disciples. The figure sitting before the hut is Kāśyapa; to attempt to name the other Brāhmaṇas would be useless. The

legend is somewhat to the following effect: When Buddha wished to lead all in the right way, he went to Uruvilvā and begged for permission to dwell in the fire-hut. It was granted him; though Kāśyapa warned him of a mighty snake that lived in the temple. Buddha caught it in his alms-bowl and sending forth flames of fire, which burst out at the roof, left the hut unharmed.¹

In the main, the whole incident is well rendered on the relief,

¹ On the Kāśyapa legend, conf. Fergusson, *Tree and Serp. Worsh.*, pp. 143f.; Beal, *Rom. Legend*, pp. 292f.; S. Hardy, *Men. of Ind.*, pp. 198f.; Bigandet, *Legend of Gautama*, vol. I, pp. 138f.; and Cunningham *Arch. Surv. Ind.*, vol. XI, pp. 149f.

though at the first glance there seems to be a great deal that is superfluous. The Brāhmaṇa disciples are not necessary to the representation of the incident; the Brāhmaṇa bathing is quite superfluous, and the one with the *lotā* just as unnecessary, unless one supposes—what seems hardly probable—that he is fetching water to extinguish the fire. In short, the whole prolix and idyllic representation of the pond is a superfluous accessory. But the main point is—Buddha himself is not present at all.



86. RELIEF FROM THE EAST GATEWAY AT SÂNGRÎ.

Left pillar, middle of the front side. The second scene in the Kâśyapa legend

More remarkable still is another and allied relief on the middle panel of the face of the left pillar (ill. 36). If one looks for nothing but the depicting of the situation, and puts aside any thought of a representation of Buddha, the incident can be explained as on the previous relief. The locality is determined by six large fruit trees, to which, though roughly outlined, botanical names can nevertheless be given. On one of these trees are perched two apes,

one occupied in plucking fruit. But the trees are standing in water; the surface of the water is full of animation; aquatic birds are swimming about upon it; one dips its head under; another, with neck bent backwards, is preening its wings; and a pelican is devouring a fish. The waves, on the relief itself, rise very high indeed over the outer lines of the fruit trees; lotus-flowers, with very animated-looking leaves that do not lie flat, appear on the water, and a snail is tossed about on the waves; above, in a corner, is seen an alligator. The water is thus in continual movement; the aquatic birds behave as if they had just gone into it. This must represent the overflowing of a river, or, at any rate, the flooding of a place planted with fruit trees¹. In the middle of this landscape, three men are sailing in a boat. The one sitting in the middle is bearded, and his hair is twisted about his head turban-wise; he is therefore a Brāhmaṇa. A bearded man, like the former, and one without a beard but with long hair,—therefore Brāhmaṇas too,—are rowing in the boat, which is made of planks roughly joined together. This shape of boat is still in use in India, on the Madras coast and elsewhere.

Now among the miracles by which Gauṭama Buddha is said to have converted Uruvilvā-Kāśyapa and his school, it is related that the river Nairañjanā was very much swollen, and that Buddha passed over the flooded place as if there had been no water there. The amazed Kāśyapa followed him in a boat, but did not become his convert yet. The situation is thus broadly depicted here—but Buddha, the principal figure, is wanting.


On the lower part of the same relief, before a high stone plinth, are seen four men; behind them is a stone bench before a tree hung with votive offerings; it is therefore a second composition, which is connected with the former. The men, to judge from their dress, are Brāhmaṇas. The hands of the middle figure, which are raised over its head, as well as the peculiarly high placed heels of the feet (unfortunately, these are partly broken off), prove that the figure is conceived as lying full length on the ground; the touching of the ground with eight limbs (*ashtāṅga*) is hereby intended. The flowers near the figure, seen from above, seem to indicate that it is to be regarded as in a recumbent attitude. Similarly, the slab of the altar in ill. 38 is represented as seen from above, so that the flower offerings on it are shown. The Brāhmaṇas standing beside the recumbent Brāhmaṇa in an attitude of prayer have upright growing plants beside them to indicate that they are standing upon the ground. On the cast in the Museums, behind the figure in the *ashtāṅga*-position and below the projecting stone, no wavy line is to be seen, as on Col. Maisey's drawing (Fergusson's *Tree and Serp. Worship*, pl. xxxi, 2, p. 141). As the water which fills the middle ground is regarded as a surface seen from above, it thus happens that the background of the worshipping Brāhmaṇa is

¹ S. Beal, *Romantic Legend of Śakyā Buddha*, pp. xi, note, and 302.

looked upon as a platform. But this platform, with its far-projecting edge, is, it appears, mentioned in the legend of the conversion of Kāśyapa of Uruvilvā. Buddha, as the story goes, found a hempen garment which he picked up and wanted to wash in the river. Sakka presented him with a flat stone for the purpose.

Now with these explanations, in which justice is done to all the figures represented, and the characteristic common to all of which is—that they only witness to Buddha's existence, but do not actually represent the sage himself, it is possible to connect a third relief belonging to the same cycle of legends.

Below the representation of the miracle of the snake, on the inner side of the pillar, is another relief (conf ill 37), the place of which on the pillar and the Brāhmaṇas represented therein, clearly characterize it as being connected therewith. In a wood, planted with fruit trees, three Brāhmaṇas are busy kindling sacrificial fires; a Brāhmaṇa disciple is bringing wood for fuel; a second carries a pole (H. *bhaṅgī*, S. *vihaṅgikā*) supporting vessels in a network.



37. RELIEF ON THE EAST GATEWAY AT SĀNCHĪ
Left pillar, inner side, under relief No. 35.

Two other bearded Brāhmaṇas are splitting wood with heavy (stone?) hatchets. A round hive-like building decorated with shells and enclosed by a railing forms the background. Whether this building, as I am inclined to think, represents merely a hermit's hut thus railed in as a protection from wild beasts, or something else is uncertain. The whole is a genre picture, and without the reliefs explained above, it would be impossible to determine its nature, so far as the persons and the occasion of the sacrifice are concerned.

The legend of Kāśyapa's conversion relates that, after the miracle of the snake, a sacrifice was offered. When the Brāhmaṇas tried to light a fire the wood, owing to Gautama's power, would not burn. They made their trouble known to Kāśyapa, who entreated Gautama to let the fire kindle. When Gautama gave his consent the wood took fire, and there was nothing to prevent the sacrifice.

Now these three reliefs give one a good insight into the relief-composition of ancient India. It stands on a level with that of the Middle Ages in the Western world. The same legend is continued on one relief; the same figures may therefore be repeated on the same panel. Land and water are always represented as extending horizontally; in consequence of this, the figures are of the same size throughout. The limits of land and water are indicated by sharply defined outlines; flowers and plants are employed to determine whether the figures represented are supposed to be lying or standing. Along with this may be noticed a naïve aptitude for converting the area into a landscape in which the principal groups occupy the centre. External details alone explain the incident depicted. Thus the only certain determining factor to explain the three panels examined above is the circumstance that the persons represented are Brāhmaṇas. Then the first relief may be explained by means of the snake and the flames bursting from the window in the roof; all the rest represents nothing but an ordinary sacrifice, and the second, or even the third panel, would be utterly unintelligible without the first. One way of laying stress on the characteristic features is the decided prominence of the object emphasized in the relief. The reliefs narrate the incident in extenso, adding also details that are not essential. As in the representations of the Middle Ages, the whole story of the sufferings of a believer is given on one relief or one picture, which is divided into a series of consecutive scenes; so is it in the Buddhist art, which in one relief combines a series of continuous events into a Nature-picture. Now the admirable rendering of nature, with the loose representation of accessory details, is apt to lead astray, because it overpowers the main motive.

Something exactly analogous occurs in Indian literature, especially in the so-called *Kāvya*s and the half-epic, half-lyric works related to them. The treatment itself becomes merely an opportunity for introducing descriptions of nature, and comparisons with nature that are broad and sensuous—often delightful though sometimes repulsive, or at least bizarre. In this law—the rudiments of which are perceptible in ancient Indian reliefs, but which reigns supreme in the literature of a later period—chiefly lie the difficulties to the ordinary European mind in understanding their modes of thought; but, at the same time, to it is due the peculiar beauty of this tropical life, bursting forth so luxuriantly on every side. In the art of the Aśoka period—on which that of

Sāñchi was modelled—everything is still naïve, and no trace of refinement exists.

As already mentioned, no picture of Buddha appears on the reliefs of this older period. Only the signs of his activity were represented; the footprints (*padah*) which he left behind him, or the sacred tree beneath which he, or one of his mythical predecessors, obtained enlightenment, or even a Stūpa erected in memory of him, are represented as being universally venerated. To these are added the symbols of his miracles: as snake and fire in the case of Kāsyapa, and so on. The wheel (*dharmachakra*), as already mentioned, was adopted by Buddha's disciples as the symbol of his doctrine, and combined with other symbols—a trident placed above it, etc.—stands for him on the sculptures of the Aśoka period.¹

From the Buddhist literature it clearly appears how irreparable was the loss sustained by the death of the Sage. Schisms soon broke out: there was no proper cult. Everything had to be developed, and it was a slow process. The wonderful growth of the more modern religion must not cause us to forget its simple and small beginnings. As long as the doctrine of the 'Overcomer' was pure, a Buddha cult could not be thought of; the tendency to this first made itself felt when the figure of the Sage was deified. Originally, Buddhism was only a philosophy, no religion; but therein consisted the weakness of the Buddha doctrines, which speedily became unpopular on that account.² When in the course of time the religion fell back into a 'worship of gods, the cult picture appeared. The countless legends which are related of the oldest Buddha pictures describe plainly the embarrassment occasioned when such a representation had to be made. The ability

¹ In these different scenes, Bharhut, with its reliefs determined by the inscriptions, is very characteristic as compared with Sāñchi and even Amarāvati. The *Dharma* or *Chakra* symbol is adored by gods and men, who approach with offerings or with folded hands; purely external accessories determine the scene: thus the wheel and two gazelles are the representation of the discourse at Bānāras, in the deer-park; *Tree and Serp. Wor.*, pl. xxix, 2 (Sāñchi); pl. lxxi, 2 (Amarāvati), etc.—even in modern Lamaist art, cf. the emblem on the roof of a Mongolian temple at Pozdnev, *Zap. geogr. Obšč.*, XVI, 1887, pl. on p. 38; the *Dharma* symbol with five pillars surrounded by Brāhmanas, the representation of the conversion of Kāsyapa (*Tree and Serp. Wor.*, pl. lxx). Another emblematic representation is the celestial ladder, with footprints above and below, for the descent of the Bodhisattva from Tushita; *Bharhut*, pl. xvii (middle), also at Sāñchi, *Tree and Serp. Wor.*, pl. xxviii, 3; conf. S. Beal, *ut sup.*, p. 183. From this comes the idea that the descending elephant beside the sleeping Māyā is a dream. The Bodhisattva descending on the ladder, appears, however, also in Gandhāra sculptures. To this subject also belongs a modern picture from Kamboja in the Berlin Museum.

² If in Buddhism the proud attempt be made to conceive a deliverance in which man himself delivers himself, to create a faith without a god, it is Brahmanical speculation which has prepared the way for this thought. It has thrust back the idea of a god step by step; the forms of the old gods have faded away, and besides the Brahman, which is enthroned in its eternal quietude, highly exalted above the destinies of the human world, there is left remaining, as the sole really active person in the great work of deliverance, man himself, who possesses—inherent in himself—the power to turn aside from this world, this hopeless state of sorrow.—Oldenberg, *Buddha*, &c., p. 53.

to create an ideal type was lacking, so a portrait was chosen which the artists beautified beyond nature, and which they tried to make authentic by tales of miracles that Buddha had wrought. Thus the *Dīyāvadāna* relates that Bimbisāra, king of Magadha, desired to have a representation of Buddha painted on a cloth. The artist tried and failed. Then Buddha let his shadow fall upon it, commanded that the outlines should be filled in with colour, and that the chief articles of the faith should be written upon it. This is an artistic authentication of a modern picture, as clearly no portrait was extant.¹ This point will be found of value in a subsequent chapter, for it proves that there was no desire to create an ideal type. In a modern branch of Buddhist art, in the miniatures of the Lamaist church of Tibet and China, notwithstanding the narrow limits of the canon, the individual appears surprisingly beautiful. It is, indeed, the only really artistic point in the endless series of absurd rites of the degenerate hierarchical representations. But the ideal type of Buddha—which spiritualized the simple monk's figure, and, notwithstanding the want of ornament, stood out from all else,—was created for Buddhist art by foreigners.

The doctrine of Buddha's Nirvāṇa can hardly be taken as affording the reason for the fact that on the reliefs of Barāhat, Gayā, and Sāñchtī the Buddha does not appear. The doctrine of the Nirvāṇa, in its present canonical form, was probably not developed at all at that time. Later, when statues of Buddha were already in existence, the legends paid no attention whatever to the dogmatic conception: according to a legend handed down by the Chinese pilgrim Hiuen Tsang, for example, Buddha, who long before had disappeared into Nirvāṇa, came down from heaven to exhort the statue of Buddha, which king Udayana had made to serve the faithful as the symbol of the doctrine that brings salvation.

In the ancient Buddhist art, so far as the representation of the founder of the religion is concerned, the conditions are the same as in ancient Christian art: symbols, such as the fish, the lamb, etc., were employed at first by the early Christians, as types reminding them of Christ. The type of the Christ was long a fluctuating one, until that of Byzantium became universal. So it was in Buddhist art: the Gāndhāra type, which will be examined in greater detail below, became the prevailing one.


The single panels become comprehensible only by virtue of their connection one with another. For the chief figure does not appear in their composition.

If we return to the reliefs of the left pillar, we are struck above all by the fact that these three reliefs of the Kāśyapa legend, the scene of which was at Gayā, are so much separated from one another. From what was said above (p. 60) about the manner in

¹ Udayana Vatsarāja of Kausambi, and Prasenajit of Kosala are said to have had statues made of Buddha before his death. Deul, *Si-yu-ki*, vol. I, pp. 235-6; Eitel, *Handb. of Chin. Buddhism*, pp. 137-8.

which the heavens are represented, we expected something compensating sufficiently on the left pillar.

As middle panel on the left pillar we have a representation of a great tree so built about by a chapel, that the main branches grow out of one of the windows. Rows of men in the attitude of prayer, stand round about it; gods are flying towards it through the air to crown it with garlands. By means of rows of men at prayer, which fill the upper panel, the composition is made to balance, to some extent, that of the right pillar, even as to form. Now the tree, the worship of which is so important, that it could be placed opposite the palace of the gods on the right pillar as a counterpoise, and in fact in such a way that the Kāśyapa legend had to be divided in two, can be none other than the Bodhi tree of Gayā with the chapel which king Asoka had built round about it. The representation of the fig tree at Buddha Gayā, which is shown on the reliefs of Barāhat, is indeed identical with our Sāñchī representation (fig. 38).¹



38 RELIEF FROM THE SO-CALLED PRASENNAJIT PILLAR FROM BARĀHAT.

(Cunningham, *Bharhut*, pl. xii and xxx). In the middle is the Bodhi-tree of Gautama Buddha. The inscription above reads: "Bhagavato Sakamunio bodhi"—the Bodhi (for Bodhi) tree of the exalted Sākyamuni; the one below: "Kāśā Prasennajit Kosala"—the King Prasennajit, the Kosala.

We see, therefore, that the desire for symmetry in composition also prevailed among Indian architects, though not in the strict form in which we

are accustomed to it from Græco-Roman art.

The reliefs, so far as their explanation is concerned, always refer one to the other. The main difficulty for us consists in separating the decorative elements from those that are important in the composition. Now those external determining points in the com-

¹ Hultzsch, *Zeit. d. Morg. Ges.*, Bd. XL, S 64, No. 46; Cunningham, *Bharhut*, No. 28, p. 134 and pl. xii; Rājendralāl Mitra, *Buddha Gaya*, p. 96.


positions are most apparent and most interesting on the architrave of the east gateway. Above the pillars there rise three transoms, which we shall call architraves; the lowest of them rests upon the capitals, while the next two are laid upon supporting blocks, which are about as high as the architraves themselves. At the places where they rest upon these supports, the beams are covered with carved panels: the whole is of the nature of a timbered scaffolding in which the cross-beams are fitted in beneath ornamented panels. Now we notice that, of the six panels on the front, the two uppermost are carved each with a pair of zebu-riders, and on the other side all the six represent similar mounted groups. Only the two lower ones on the front are sculptured each with three winged lions. If we look more closely at them we see that all the carved surfaces of the architraves—that is, of the three on the back and the uppermost on the front—have purely decorative reliefs, which are continued beyond the panels; only the two lowest on the front present compositions full of figures and of the processional kind described above. Another thing that strikes one is that the representations on the architraves, which project beyond the inlaid panels, do *not* continue the central compositions of the first and second architraves on the front. (Conf. ill. 39)

The relief on the central portion of the first architrave, reckoning from below (front), belongs to the narrative representations, which we discussed on p. 57. In the middle is to be seen a large fig tree with the same kind of building (a *chaitya*) encircling it as on the relief of the left pillar: it is, therefore, once more the Bodhi tree at Gayā. A large and solemn procession is winding round it. To the right, on the relief, a man in royal garb is getting down from his elephant, supported by a dwarf, surrounded and attended by women; chariots with warriors, elephants with mahāuts, archers and musicians, fill up the background. On the left, a great procession approaches with flowers, vessels with perfumed water, flags, etc.; a large band of music, with drums of different kinds, fifes, and conch shells as trumpets, fill up the rest of the relief. It is therefore a procession to the Bodhi-tree at Gayā, perhaps on the occasion of Mahinda's embassy to Ceylon (conf. p. 26). The winged lions in the inlaid panels may possibly be intended to suggest this. Lions are the armorial bearings of Ceylon: 'the lion island,'—*Sīṃhaladvīpa* (Pāli, *Sīṃhaladīpa*). The ends of the architraves, in the corners under the volutes, have a pair of peacocks of unusual size in their reliefs on both sides. On the right end a pair of lovers is represented behind the peacocks. In Pāli the peacock is called *Mora* (Sansk. *Mayūra*); and as peacocks are the symbol of the Maurya¹ dynasty, their representation on the first architrave might indicate that the central incident, which refers to Ceylon, takes place in India.

The middle relief of the second architrave shows a small fig

¹ Conf. Turnour, *The Mahāvamsa*, in Roman characters, p. xxxix.

tree in the centre; this—if the previous relief has been correctly explained—may indicate the newly-planted slip. Again a great procession appears, just leaving a city. The princes have dis-



38. ARCHITRAVES OF THE EAST GATEWAY OF THE GREAT STŪPA AT SÂNCĪ.

mounted; their horses are following the procession. The right side of the relief shows a king kneeling before footmarks¹—presumably Buddha's—surrounded by servants with sacrificial vessels,

¹ Yule, *Travels of Marco Polo*, vol. II, p. 260.

umbrellas, etc.—evidently the worship of the Buddhapāda, the footprints of Buddha, which he is said to have left on the Sumanakûṣa (Adam's Peak) on the occasion of his mythical visit to Ceylon. There a giant footprint has been regarded as sacred from ancient times and for all the religions prevailing in Ceylon.¹ On the reception of Buddhism, it became a proof that Buddha had walked upon the island, and thus was taken as a pattern for similar footprints in Further India, &c. The ends of the architraves, next the volutes, show wild elephants in the jungle as companion pieces to the peacocks of the first architrave; and to correspond with the pair of lovers, a naked man and woman, both with bow and arrows. As, judging from the wild elephants, we are in Ceylon, these may be meant for Veddās.

Thus both reliefs are intimately connected with the story of the building at SâncĪ given on p. 26. It is an extremely interesting fact that, not only at the Christian era, but even in the days of Āsoka, the footmark on Adam's Peak was considered as the print of Buddha's foot. No doubt, for the missionaries of the faith sent from India, it was a decisive proof of the true doctrine, when so striking an instance of Buddha's visit to the island was given to them on the occasion of their bringing over the slip of the Bodhi-tree. The Buddhapāda, which existed later at Gayā, is now worshipped as the footprint of Vishnu.

Reliefs of the east gateway at SâncĪ.

Casts of this gateway were made in 1869 and are set up in the S. Kensington, Edinburgh and Dublin Museums of Science and Art, in the Royal Ethnological Museum at Berlin, at Paris, &c. (See above, p. 25). The following is a brief description of the sculptures upon it. The only representations we yet possess of those on the other gateways are given in Fergusson's *Tree and Serpent Worship* (1873).²

Right pillar, front: Palace of the gods. Inner side: worship of a sacred tree—the fig-tree at Gayā, where Buddha obtained enlightenment; below, the dream of Māyā; the Bodhisattva comes down from the region of the Tusita gods in the form of a white elephant. Below, a large relief presents a great town, in the streets of which meet riders and men on elephants. The windows of the houses are full of people, women with parrots in their hands look down into the streets. A chariot with a young man clearly characterised as a prince is leaving the city: a band of musicians goes before. Archers and an elephant with its *mahāwat* accompany the chariot of the prince. It is perhaps the procession of the youthful

¹ Locally known to the Tamils as *Śivadippāṭham* (Śiva's footprint) and *Dharmarājākkal* (Buddha's rock). The Muhammadans say Adam alighted on it when expelled from Paradise, and call it *al-Bahun*. See E. Tennant, *Ceylon*, vol. II, pp. 132-6; and Skeen, *Adam's Peak*.—J.B.

² Since p. 25 was printed off, Mr. H. Cousens has sent me his re-measurement of the SâncĪ stūpa. The diameter of the dome at the top of the ramp or plinth is 106 feet, and of the encircling rail, outside measurement, 133 feet from E. to W. and only 140½ from N. to S.—J.B.

Gautama on which the four appearances mentioned above (p. 13) were met with. This view is to some extent supported by the fact that on the lowest relief a fig-tree is again represented (the later Bodhi-tree, or the other one at Gayâ, under which Gautama, according to the legend, first meditated?). Before the tree are five men in lay costume, worshipping (Fergusson, *Tree and Serp. Wor.* p. 145 and pll. xiii, xvii and xxxiii). The under half of the inner side represents a large figure of a man, in royal dress, resembling that on the left pillar. These figures appear to correspond to the Yaksha at the entrance of the Nâsik chaitya temple (p. 36).

Left pillar, front: above, two rows of men worshipping. Below, the Bodhi-tree surrounded by the chapel over an altar or table bearing the trisula symbol (conf. p. 69). (Fergusson, *Tree and Serp. Wor.*, pll. xiii, xvi and xxv, 3). Below that, the water miracle of Uruvilvâ (p. 63). The lowest panel is uninterpreted. The representation is divided into two scenes: on the right is a thickly peopled city, through whose streets pass a rider and a *mahâwat* on an elephant. The smaller half, clearly defined as a separate incident, shows two men in rich dress,—one in the attitude of a teacher, the other in a listening, devotional pose with folded hands. Inner side, upper panel: in the foreground is a pond with lotuses; buffaloes, zebus and goats stand on the bank, two buffaloes are up to their necks in the water. Beyond the pond is seen a large stone slab with an awning and two men worshipping. A young man with a sling-pole for carrying vessels (*bahāngī*) stands behind the pond or river surrounded by women; a woman draws water with a *loṭā*, others hold their *loṭās* in their arms. The middle ground is occupied by a large house with adjoining buildings; near it are women engaged in preparing rice: one woman pounds the rice in a mortar, another cleans rice on a winnow, a third makes cakes, a fourth, who is occupied in the same way, is talking with a man (*Tree and Serp. Wor.*, p. 150 and pl. xxxv, 2): probably the meal which Sujâtâ, with the help of the gods, prepared for Gautama, and the stone slab on which he partook of it, before he began the last decisive meditation which was to bring him enlightenment. The panels beneath represent the fire-miracle at Uruvilvâ (conf. above, p. 62, 66). The lower half of the inner face is filled by a man (or Yaksha) in royal dress.

The backs of the pillars, right at the top only, have each a small relief; on the left with a stûpa, on the right with a sacred tree which is worshipped by gods and men.

The outsides of both pillars show rich patterns of lotus-flowers, on the right side is a flower pattern only (conf. p. 19); on the left side, a large garland which is alive with little aquatic birds and springs from the jaws of a large *makara*.

The capitals of the pillars are filled with men richly dressed, bearing flags and seated on elephants. Outside and joined to each capital is a dancing girl, or a *Devī*, on a large scale, under a tree—the one on the right being quite preserved (conf. p. 42).

The first architrave: front, inlaid panels,—winged lions; middle relief: Mahinda at Gayā, see p. 70 (*Tree and Serp. Wor.*, pl. xv, 2). Outside: peacocks.

Second architrave: front, applied panels: winged lions; see ill. pp. 18 and 71. Middle relief: the Bodhi-tree at Anurādhapura (?), adoration of the Buddhapāda; see p. 69. Outside: wild elephants; see p. 72 (*Tree and Serp. Wor.*, pl. xv, 1).

Third architrave: front—applied panels: zebu riders. Middle and ends of the beam: five stūpas and two sacred trees, worshipped by gods and men.

The blocks supporting the architraves bear on the front the following reliefs: between the first and second to the left,—a wheel (*dharmachakra*) adored by gods and men; to the right, the goddess Sīrī on lotus flowers, &c.; see p. 39; between the second and third, to the left, the goddess Sīrī; to the right, a sacred tree with gods and men.

First architrave: back, applied panels: on each a man and a woman with peculiar coiffure, riding on goats. Middle relief and ends of beams,—elephants bring offerings of flowers (lotus-flowers) to a stūpa (*Tree and Serp. Wor.*, pl. xv, 4).

Second architrave: back, applied panels,—on each a man and a woman riding on dromedaries. Middle relief and ends of beams,—the animal kingdom adores a holy tree, the different animals bringing branches, flowers and blossoms; see p. 48 (*Tree and Serp. Wor.*, pl. xv, 3).

Third architrave: back, applied panels,—on each a man and a woman riding on horned and winged lions, clearly foreign types (conf. ill. p. 34). The middle and the ends of the beams show seven holy trees adored by gods and men, evidently the Bodhi-trees of the six predecessors of Buddha and that of the Buddhas—Vipassī, Sikhi, Vessabhū, Kakusandha, Koṇāgamana, Kassapa and Gotama which are also represented at Barāhat, as the inscriptions witness.

The blocks supporting the architraves show, on the back the following reliefs: between the first and second architraves,—groups of lotus flowers; between the second and third architraves,—on each a stūpa with gods and men.

Between the ends of the architraves stand figures, some of which are still preserved: statuary groups of men on elephants and dancing-girls under trees. The small pillars which support the architraves bear in their reliefs lion-pillars (see p. 20), or simply ornaments. How the remaining spaces between the small middle pillars, or the highest architrave between the wheel-symbols, was further ornamented we do not know. On the other Sāncī gateways, small figures of riders and statuettes of different sizes are employed as additional decorations: motifs that remind one of the throne of Vikramāditya (see p. 29).

Above each pillar there was once a symbol of Buddhism: the wheel with the trisula over it (see p. 19 and note 2).



40. THE INFANT BUDDHA TAKING THE SEVEN STEPS (from Swât).

CHAPTER III.

THE GANDHARA SCULPTURES

(SO-CALLED GRÆCO-BUDDHIST SCULPTURES).

By Gandhâra sculptures are designated the numerous images, carved friezes, pillars, &c., excavated from the ancient ruins of Buddhist monasteries and stûpas on the north-west frontier of India. They have been variously styled Græco-Buddhist, Aryan, Indo-Greek, and Indo-Baktrian—terms which are open to the objection of implying a theory respecting their art origin. They are all but entirely connected with Buddhist iconography, and many of them manifest some western or classical influence. And since they are found almost exclusively in the country which early writers named Gandhâra, they may very properly be characterized by the area of their origin. The country of the Gandarioi, Gandaræ and Gandaritîs is mentioned by Herodotos,¹ Hekataios, Ptolemy and Strabo. The Gandarioi furnished their contingent to the army of Darius in the invasion of Greece. Their country occupied the whole lower valley of the Kâbûl river—the ancient Kophen or Kubhâ—from the Kâu or Alingar river near the meridian of 70° W. longitude to the Indus, and from the Safid Koh range and the Kohat Toi river on the south to the borders of Kohistân, Chitral and the Hindu Kush on the north. It thus embraced the whole of the modern Afridi and Momand country, Swât, Bajaur, Bunêr, &c. At one period, at least, it seems even to have included

¹ Herodotos, bk. vii, c. 85, 86; conf. bk. iii, c. 91; iv, 44.

within its limits the great city of Takshasilā in the Rāwal Pindi district, to the east of the Indus,—forming an area 170 miles from east to west, and above 100 miles from north to south.¹ The province between the Swāt and Indus rivers, or the modern district of Yūsafzai and northwards to Kohistān, was known as Udyāna or Ujjāna (Gr. Suastēnē), and sometimes probably formed a separate principality. It was through the northern districts of this country that Alexander led his army into India. On the rise of the Græco-Baktrian kingdom, in the middle of the following century, Gandhāra was included in it.

The political events which followed the short reign of Alexander the Great in India terminated with the founding of two great states—the kingdom of the Prasii with its capital Pātaliputra (Gr. Palimbothra, the modern Pātnā) in the east; and the Græco-Baktrian kingdom, which retained for a time parts of India, the Panjāb, and portions of the North-Western Provinces of to-day. The heirs of the Græco-Baktrian kingdom and of its hybrid civilization, formed of Iranian and Greek elements, were the Yueh-chi or Indo-Skythians (cir. B.C. 126). The struggles which the Indian states carried on with them continued till the sixth century A.D., and thus form the political background for the further development of Buddhism on Indian soil.

With the fifth century begins the darkest period of Indian history, political as well as religious. When, after centuries, the veil is lifted again, and Indian sources are once more fully at our disposal, Buddha's doctrines have largely disappeared from the continent of India, foreign influences are overcome, and, whilst a complete transformation has taken place in Brāhmanism,—which organizes the national worship and moulds it into an important system,—an entirely new development of the languages is in progress.

In detail, the following had probably been the course of affairs. After the death of Alexander the Great, his generals had divided his vast empire among them; his Indian possessions had fallen to Seleukos Nikator, king of Syria. But as the supremacy of Seleukos was immediately subjected to attack, and as he saw that western Asia would call for his utmost exertions,—convinced of the extreme difficulty of retaining the eastern lands of his empire—he ceded the Indian provinces to Chandragupta of Magadha (cir. 305 B.C.) in return for a supply of war-elephants. A daughter of the Macedonian was married to the king of India, and a permanent ambassador, Megasthenes (whose narratives of Indian affairs, though only fragmentary, are of great value),² remained at the

¹ It still retained the old name in the thirteenth century. The capital at different times was Pushkalavati, Purushapura, and Uśakhaśa or Waihand (Ohind).

² The Fragments of the *Indica* of Megasthenes have been collected by E. A. Schwanbeck (Bonn, 1846) and by C. Müller. They have been translated into English by J. W. McCrindle in *Ind. Ant.*, vol. VI, 1877, and also separately (Bombay and London).

Indian court at Pāṭaliputra. About a century later (B.C. 260–230) Aśoka did his best officially to propagate Buddhism within his wide domains, and also sought to procure an entrance for it into neighbouring states. About the year B.C. 246, we learn that a Buddhist mission was sent to Kashmir and Gandhāra by the great Council held under king Aśoka. It was led by an elder or monk named Majjhantika (Madhyāntika) of Dahala, who found a savage Nāga king, Aravāṭa, ruling the country. After strong opposition, the monk is said to have converted the king and gained over the whole population. "From that period," says the *Mahāvansa*, "to the present day, the people of Kashmir and Gandhāra have been fervently devoted to the three branches of the faith, and [the land] has glittered with the yellow robes [of the priests]" And the testimonies of the early Chinese pilgrims, together with the numerous remains of Buddhist monasteries and stūpas still found, amply confirm the statement that such was once the case.

King Aśoka mentions in his inscriptions that he had carried on negotiations in reference to this object with the kings of the Yavanas—Antiochos of Syria, Ptolemy Philadelphos of Egypt, etc. The alliance with the Seleukidæ continued, and about the year 256 B.C. Antiochos Theos concluded a treaty with Aśoka.

But this condition of things was soon altered. Between the two great states there arose a new power which drove the Syrian monarchy from the Indian frontier for ever. The Græco-Baktrian kingdom, which was founded at the expense of the Syrian satraps, waxed powerful, and Eukratides, king of Baktria, took up arms against India (cir. 170 B.C.).¹ His armies seized upon the Panjāb and perhaps made their way as far as Sindh and Gujārāt. The Baktrian kingdom, however, was attacked by the Yueh-chi, a Skythian tribe, who drove the Baktrians, under their king Heliokles, over the Hindū Kush (B.C. 125).² Somewhat later his successor, Menandros, whose dominions could no longer have included Baktria, had his capital at Sākala (Sangala or Sānkala) in the Panjāb, somewhere near the Hydraotes or Rāvi river, and made considerable conquests in north India.³ A generation after Menandros, the Yonakas or so-called Greeks were again subjected to the onslaughts of Yueh-chi tribes, and Hermaios, about B.C. 25, seems to have shared his kingdom with Kadphises, the Yueh-chi chief of the Kōshan tribe.

Among the kings of the Baktrian dynasty—whose contemporaries in India were the Sunga and Kānva dynasties—Menandros is

¹ Justin, *Hist.* lib. xli, 6; Strabo, lib. xv., 1, 3; xi, 9, 2, and 11, 2; Wilson, *Ariana Antiqua*, pp. 234ff.

² Ptolemy, *Geog.* vii, 1, 46; Wilson, *Ariana Ant.* pp. 280ff; Duff, *Chronology of India*, p. 16.

³ Sylvain Lévi, *Quid de Græcia vet. Indorum monum. trad.* p. 17; Beal's *Si-yu-ki*, vol. I, p. 106, note 5; and *Ind. Ant.* vol. XV, p. 246; Speech in *Jour. Asiat.*, 5me Ser. t. II (1888), p. 348; Sylvain Lévi, *ibid.* t. XV (1890), pp. 287-9; McGrindle, *Invas. Ind.* pp. 347-8, 411; *Sac. Bks. of the East*, vol. XXXV, p. 28.—J.B.

by far the most important. He is doubtless identical with the Milinda of the Buddhists; and seems, according to Plutarch, to have gone over entirely to Buddhism.¹ A Pāli work, *The Questions of King Milinda—Milindapañha*² (first rendered accessible to English readers through the Singhalese version, *Milindaprasnāyā*), which belongs perhaps to the first century after Christ, represents the king in conversation with a Buddhist monk who expounds to him Buddha's philosophy in a style almost Platonic; whereupon the king is converted. In any case, this work is an important Indian testimony to the interest of the Greeks in Indian philosophy, on which subject Greek authors are so well informed.

Hermaios, the last of the Yonaka or Græco-Bactrian dynasty, was dispossessed of part of his power by the Yueh-chi about 25 B.C. Other tribes—Ye-tha or Sakas—had also pressed into the same region; Maues had previously established himself there and was succeeded by Azes, Azilises, &c., who were perhaps Skythic or Sakas; and a little later we have names that seem to be Parthian, such as Gondopharas or Gudapharas, Abdagases,³ Orthagnes, &c. Gudapharas must have ruled about A.D. 25-50, and is the king mentioned in Christian tradition as having received the Apostle Thomas. A little later Kanishka the Kúshan became supreme from Kábul to the Ganges.

In those days a vast interchange of ideas was carried on between the east and the Hellenic and Roman worlds by means of the newly opened highways. It is, of course, impossible within the limits of this work more fully to describe this period, so highly important for the east as well as for the west; but a few cardinal points in connexion with the artistic efforts of the Indian world may be mentioned. The Greeks sought and found in India traces of their own gods; the tendency of the Hellenes, noticed as early as Herodotos, to identify the gods of barbarian races with their own, led to the recognition of the ancient conquests of Dionysos in India.⁴ Just as Alexander the Great, impelled by the exigencies of Oriental court etiquette, assumed the title of a god; so, to reverse the process, the gods who, according to the legends, had performed such miraculous feats in India, were soon represented as deified conquerors. The sages of Egypt and India had to furnish pretended proofs that the personages of their national mythology were only deified heroes. The Indian doctrine of the transmigration of souls was adopted, and in the Occident was utilized in a Puritanic

¹ Strabo, *Geog.* xi, 11, 2; Plutarch, *De Rep. Ger.* p. 821; Lassen, *Ind. Alt.* Bd. II, ss. 818f., 840f.; *Hist. Bakt. Kings*, 150-158; *Sac. Bks. of the East*, vol. XXXV, p. xix f.

² Translated by Rhys Davids, *Sac. Bks. of the East*, vols. XXXV, XXXVI.

³ There is no ground whatever for Cunningham's hypothesis (*Jour. As. S. Beng.* vol. XXIII, pp. 7 [1-12]) that Abdagases is the Parthian who led the revolt against Artabanus III.—J. H.

⁴ Herodotos, ii, 60, &c.; Diodoros, iii, 68; Strabo, xv, 1, 68; Pölsen, *Strateg.* i, 1, 1.3. Arrian, *Ind.* c. 6-7.

direction in order to sift the fast increasing crowds of gods and forms of worship which had been the result of the confusion of ideas, or to prove directly the incorrectness of the ancient legends,—the so-called Euhemerisin.

The story of the campaigns in these tropical lands created an interest in adventure and travel, and gave birth to tales of adventure, which, by means of foreign names, romantic descriptions and strange themes, ventured to surpass reality. Greek ideas and narratives find their way into the Buddhist texts, and Indian similes, fables and legends appear in the literature of the West. Whether Greek dramatic art merely influenced the Indian, or founded it, may be left an open question. These attempts continued until the time of the later Roman emperors—about the fifth century.¹

With regard to India and the influence of Buddhism at this period, stress should be laid on the fact that an exactly analogous flood of Indian ideas, which had a much more powerful effect than in the case of the Græco-Roman civilized world, set in at the same time towards the East and especially towards China and the lands east of India, and that this went on for centuries. About 65 A.D. the Han Emperor Ming-ti had Buddhist books brought from India; in the succeeding centuries Buddha's religion made gigantic strides in East and Central Asia. Fah-hian, who visited India about A.D. 400, was acquainted with a set form of prayer to the Bodhisattva Maitrêya: the Buddhists outside India were thus, throughout this whole period, constantly in touch with the development of the doctrines in the mother-country. But the same Chinese pilgrim saw on Indian soil representations of the founder of the new religion for which Western art had afforded an ideal type.

Under the heirs of the Greek power in India, the Yueh-chis, Turushkas, or Indo-Skythians, Greek or Western civilization still prevailed; but coupled with the interest of the ruling houses in Buddha's doctrines, the Indo-Skythians may perhaps have become disciples of Buddha in their own country. The most potent of these kings was Kanishka,² the Kûshana. He ruled over a powerful kingdom including Kâbûl, Gandhâra, Kashmîr, the Panjâb, parts of Râjasthân, and the present N.W. Provinces. About the year 100 A.D., at his instigation, there met, at Jâlandhara in the Panjâb, a council of Buddhist teachers, which set itself the task of collecting and arranging the sacred writings and bringing about an agreement and a reconciliation between the different sects. At this council the sacred texts were no longer written in the ancient Pâli or

¹ On this see Reinaud, *Relations politiques et commer. de l'Empire romain avec l'Asie orientale* (Paris, 1868); and Friauf, *Indian travels of Apollonius of Tyana, and the Indian embassies to Rome* (Lond. 1873).—J.B.

² The Greek form of the name was formerly read *Kanishka*, but see Burgess, *Ind. Ant.*, vol. XIII, p. 58, and M. A. Stein, *ibid.* vol. XVII, pp. 94f. Senart considers the form *Kaneshika* as the correct one; *Jour. As. Soc. Ser.*, tom. VII (1896), p. 11. Huen Tsang calls him Kanishka Râja of Gandhâra; Beal, *Si-yu-ki*, vol. I, p. 66.

Māgadhi tongue, probably spoken by Buddha himself, but in Sanskrit. By this means the split between the now separating northern and southern schools became decided and lasting. The southern school does not recognise the council of Jālandhara in its traditions; its own canons are in the Pāli language; the numerous heterodox works emanating from the sects that had been more or less influenced by Brāhmanism, and which the northern school received for conciliatory reasons, are also unknown to the southern church, which now went its own way, and was in consequence removed from Hindu influences. This southern church thus represents in her sacred canons the older and purer exposition of Buddha's doctrines.

Now-a-days, since the extinction of Buddhism on Indian soil, besides the countries of Farther India—Burma Siam, and Kamboja, only Ceylon is still Buddhist, and it is regarded as the seat of the southern church. The northern school has gained Tibet, Nepāl and China, with the neighbouring countries, but it has also made some way in Farther India, and in Java it has got a footing side by side with Brāhmanism. In Northern India, between the sixth and seventh centuries, Buddhism declined rapidly; in Kashmīr it held out longest. What it lost in the land of its birth it gained in Central Asia; twice it penetrated into Tibet, and there it not only brought all religious life into subjection, but contrived by means of its powerful hierarchy to gain also the political supremacy. In China, Buddhism is found in two sects—Foism, which was introduced from India, and Lamaism, which came from Tibet—side by side with other forms of religion; but it has lost much of its prestige. Japan received the Bauddha religion from Korea. In the Indian Archipelago Buddhism is almost extinct.

Buddhism of the Mahāyāna school continued to flourish in Gandhāra including Udyāna, down to the close of the fifth century. When Fah-hian visited the country about A.D. 404, he found 500 monasteries and the people devoted to the Bauddha Path; but about 515 A.D. Mihirakula, a Hūna, overran Udyāna and Kashmīr, killed Simha the Buddhist patriarch, and massacred the Buddhists. In the seventh century Hiuen Tshang, passing through the country, found the religion decadent; but fully a century later (A.D. 757-764) U-K'ong, who resided for some years in Udyāna, speaks of over 300 monasteries of the Sarvāstivādin or Vaibhāshika school of Mahāyānists in this district, and the then ruling princes zealously patronised the monks.

When, after long struggles, the Yueh-chis had been driven out of India proper, the dynasty of the Gupta emperors became the dominant one. Under their rule (A.D. 319-530) Buddhism began to fall decidedly into decay. It had at an early date become divided into numerous sects or schools, which decidedly contributed to its loss of power; and the mass of the people, who could not follow the hair-splitting dialectics of these various schools,—who

had regular argumentative combats among themselves,¹—fell back into the older and more eclectic cult of Brāhmanism, which they had never altogether forgotten. The strong and continually increasing intrusion of Brāhmaṇa elements into philosophical statement and into ritual gradually but completely transformed the old doctrines of Buddha. Unfortunately, with the fifth century the darkest period of Indian history begins; native sources of information cease almost entirely. What we do know we owe to foreign writers: the Chinese pilgrims already mentioned—Fah-hian (cir. 400 A.D.), Sung-yyun (cir. 518 A.D.), and Hiuen Tshang (629-648 A.D.). While the first of these found the Bauddha religion still pretty generally observed in India, Hiuen Tshang laments its decline.

We have still to note the changes effected about the third century by the Christian religion, which, from western Asia, was spreading in all directions. Through Syrian sources, Christendom had become almost the immediate neighbour of Buddhism.² Alongside of the Christian religion stood the theories of the Zoroastrians; and from these two Manichæism had been evolved, which had already adopted certain Buddhist ideas also: everywhere a lively reaction of the old religious forms had set in against the new doctrines. For our purposes it is specially noteworthy that the Paraclete plays a prominent part in Mani's doctrine, for, as we shall see, in the Gāndhāra sculptures of the Peshāwar district, the Buddhist Messiah, Maitreya, seems to be revered almost more than the founder himself.

Returning to Buddhist art, we find traces of Greek influence in Asoka's buildings, in particular elements which neither the richness of form of the so-called Orientalising tendency, nor Persian influences, suffice to explain. (Conf. above p. 57). The elements in question are essentially decorative, and quite in the Persian style; they consist of particular forms of creatures with fishes' tails (*Mat-syanāris*), hippocampi, *makaras*, centaurs, river-gods with human faces and the bodies of oxen, the thunderbolt, etc. Unfortunately, the miserable ruins of ancient Iranian art are altogether insufficient to represent the whole range of the influence which ancient Irān must have exercised in India. It is particularly regrettable that there is no answer to the question to what extent Greek hands may have been employed in the buildings of the Achæmenides. That Persian ideas were at work for a much longer time in India, and that they had a special influence on the

¹ Notices of such competitions, almost in the monastic style of mediæval times, occur in plenty in *Tirānātha* (Schiefner's transl.). Even still, the Lama religion prescribes similar competitions as school exercises. Conf. Hue et Gabet, *Souvenir d'un voyage dans la Tartarie, etc.* (Paris, 1850), tom. II, pp. 117-8.

² How influential the Christian communities were is evidenced by the fact that the Christians (851 A.D.) buried with great ceremony the shamefully murdered Persian king Yazdigard.—Ibn Athir, iii, 96, quoted by E. Kuhn, 'Barlaam und Joseph,' *Abhand. K. B. Acad. Wiss.* (1899) 1 Cl. Bd. XX, i, S. 97; also Nöldeke in *Zeitsch. d. D. M. Gesch.*, Bd. XLIV, S. 521.

later Buddhism of the north, is shown by what follows. The cuneiform inscriptions of the time of the Achæmenides refer to the Indian peoples under two names, adopted by Herodotos also, as Hindu (Indoi) and Gandâra (Gandarioi).¹ These designations are peculiarly suitable for the two periods of Buddhist art; if the style of Asoka and the Indian style that sprang from it are comprised under the name Indian (Indo-Persian), the name Gandâra (Skt. Gandhâra and Gândhâra) remains to designate the style adopted in the kingdom of that name, whose geographical position we have defined above. The designations Græco-Buddhist, Indo-Baktrian, &c., which have been applied to them, are all, for various reasons, incorrect and misleading.

Yet, of course, there is no lack of transitions and opposing tendencies. Thus, in India proper (at Mathurâ) are to be found traces of what Mr. Vincent Smith styles an Indo-Hellenic school, which represents subjects purely Greek. The best known relief, which belongs to this group, is the so called Silenus, now in the Calcutta Museum; a second represents Hercules with the Nemæan lion.² To this little known school, which ought possibly to be somehow connected with the stay of Megasthenes at Pâtna, belongs the representation of Mâra with bow and arrow, and also some similar older Greek elements which differ entirely from the Gandhâra sculptures, and are still to be found even in Brâhmanical art. Both the sculptures mentioned above are Greek in form, but the figure of the woman in Grecian dress, represented on the Silenus relief, shows Indian influence in its exaggerated outlines. To this group also belongs an Athene found in the Gandhâra territory,³ and described by Vincent Smith. It is now in the museum at Lahor.

The rich antiquarian remains of the Kâbûl valley and Indian frontier were brought to notice between 60 and 70 years ago by Mr. C. Masson, Dr. Hônigberger, General Ventura, and Captains Court and P. T. Cautley. The Manikyâla and other stûpas were opened and large numbers of Græco-Baktrian and Saka coins were collected, together with some sculptures. These excited much interest among scholars at the time; and after the Pânjâb came under British rule in 1849 wider scope was afforded to investigators; the ancient sites, particularly in Yûsufzâi, became accessible, and soon yielded numerous sculptures which have, in various ways, reached our Museums. The late Sir E. Clive Bayley obtained the first collection made at Jamâlgarhî, but,—placing these valuable

¹ Inscriptions of Persepolis and of Nakhsh-e-Rostam, in *Jour. R. As. Soc.*, vol. X (1847), pp. 280 and 294.

² Silenus, Anderson's *Archæol. Cat.*, pt. I, pp. 168-176f. Nemæan lion, *ibid.*, pp. 190-1; *Ar. Ser. Ind.*, vol. XVII, p. 109. Another Silenus was found by Mr. Growse at Mathurâ; *J. A. S. Bang.*, vol. XLIV (1875), pt. 1, pp. 212-15; and references above on p. 84, note 2.

³ *Ind. Monuments*, pt. I, pls 91, 1; *conf.* also the pedestal in Lahor Museum, represented in *Jour. Ind. Art, &c.*, vol. VIII, pl. 20, 7, and *Jour. R. I. Br. Arch.* (1894), p. 138.—J.B.

sculptures in the Crystal Palace for exhibition,—they were destroyed by the fire in November 1866, and this before they had even been photographed.¹ In November, 1885, General Cunningham shipped a large and important collection to England, which was lost in the steamer "Indus" off Ceylon. A very large number were excavated for the Government of India in the Yûsufzai district, and were distributed among the various Museums in India, much to the detriment of their proper study. The largest collections are in the Museums of Lahor and Calcutta.² Numbers have from time to time been acquired by private individuals, and some have found their way to the British Museum, the Berlin Ethnographical Museum, the Louvre, Vienna, the Edinburgh University,³ &c., &c.

In the numerous reliefs thus found, a quite new and very remarkable development is presented. The ruins are found in the neighbourhood of Peshâwar, the ancient Purushapura, at one time "the capital of the Gandhâra kingdom, at Jamâlgarhi, Takht-i-Bâhi, Tahr-i-Bahlol, and places in the Swât (Suvâstu, Gr. Soastos) district. Monuments of a similar style are found farther to the west, such as the colossi of Bâmiyân and so on, and also farther to the east.

It is to the late Mr Jas. Fergusson (1808-1886) that we owe the first scientific discussion of these monuments and of the Indian art represented by them; and whatever advances we have made since, have been largely due to his work as a remarkably skilful and wise pioneer, abreast of the knowledge of his time. Serious attention was first drawn to the subject by his writings, and the materials have since been largely increased.⁴ We are thus in a position now to attempt to advance a step and to arrange the results attained and apply them to the further interpretation of our materials.

The antiquities discussed by Fergusson, Cunningham, Bailey, and others, and made known to the public in part by Cole,⁵ have since been treated more in detail in the excellent paper of Vincent Smith

¹ All the record we have of them is a short descriptive note by Sir E. C. Bayley, with eleven rough lithographed sketches in *Jour. Ar. Soc. Beng.*, vol. XXI (1852), pp. 606-621.—J.B.

² Besides those sent to Lahor and Calcutta Museums, smaller collections were sent to the Victoria and Albert Museum at Bombay, to Madras, and even to Rangoon.—J.B.

³ Sixty-three pieces, largely from Swât, are in the Berlin Ethnographical Museum, and it was chiefly to explain and illustrate them that the following portion of the *Handbuch* was written. The late Dr. Leitner, while at Lahor, formed a splendid collection, which he brought to Woking. In other private hands there are numbers, which, unfortunately, are generally unknown and practically inaccessible to students while unpublished.—J.B.

⁴ *Hist. Ind. and East. Archit.*, pp. 72-83, 169-184.

⁵ Major H. H. Cole published thirty plates of *Græco-Buddhist Sculptures from Fârûsîas*, as a fasciculus of the work on 'Preservation of National Monuments' (1885). This work is out of print, but twelve of the plates were reproduced in the reprint of *Preservation of National Monuments in India* (London, 1896), and other seventeen, (with sixty-four additional) in the *Ancient Monuments, &c., of India*, Part I (London, 1897). In the *Journal of Indian Art and Industry*, vol. VIII, a further series of twenty-five plates and thirty-eight cuts have been published.—J.B.

and in an important article by M. Senart.¹ Both discuss, from different points of view, the period to which the sculptures belong; the former would extend them over the first five centuries of our era, placing the most flourishing period in the third and first half of the fourth century; the latter does not incline to extend the period to so late a date, and regards the second century and earlier half of the third as its principal period. Mr V. Smith lays stress on certain features of the art as being Roman rather than Greek. This distinction, however, must not be carried too far: it is one of age rather than of origin. Roman art had always been influenced by Greek taste and models, through the races of Greek descent in Southern Italy; and finally—

Græcia capta ferum victorem cepit, et artes
Intulit agresti Latio.

Roman art in sculpture and decorative invention was primarily Hellenic, the Greeks developed Roman architecture in their own facile creative way, ever inventing new forms of ornament and lavishing upon it their wealth of decorative taste. We may call the art of the early Christian centuries Roman, as being produced under Roman rule, but it was Greek minds that inspired and Greek hands that executed it. Greek artists, in their wanderings, carried with them the types and style of the age to which they belonged. And during the first three centuries of our era, Greek art was an article of exportation, and artists—art practitioners—also seem to have travelled everywhere in search of employment. Naturally, they would copy or adapt the models of their native art to meet the demands of their foreign clients of whatever religion.²

The few inscriptions found in connexion with the Gāndhāra sculptures or on the same sites are dated from 103 to 384 of an undetermined era. The first, that of Gondophares, is in his 26th year, and he is otherwise placed in the first century A.D. This would refer the epoch to about the middle of the previous century, and the 'Samvat' era dates from 57 B.C. If, then, we adopt this for all the dates, —and there is no reason for supposing the use of more eras than one among these inscriptions, unless indicated, nor for supposing another era than the Samvat one beginning in the same century, —we may thus place the accession of Gondophares in A.D. 21-22, and his 26th year in A.D. 47; the Theodorus inscription would fall in A.D. 57; the Pañjtār inscription in 65; that of Loiyān Tangai in 262; and that of Hashtnagar in A.D. 328.³ All these dates are within the limits otherwise indicated for the age of the sculptures.

¹ Smith in *Jour. A. S. Beng.*, vol. LVIII (1889), pt. 1, pp. 107ff; Senart in *Jour. As.*, 5me Sér., tom. XV, pp. 139-162. An outline of M. Senart's argument was reproduced in *Jour. Ind. Art and Ind.*, vol. VIII, pp. 25-29. Conf. also Bühler, *Ans. d. K. K. Acad. Wiss. zu Wien* (1896), 8s. 44ff. —J.B.

² Conf. Foucher in *Rev. de l'Histoire des Relig.* tom. XXX (1891), pp. 365-68.

³ See Senart in *Jour. As.*, 5me Sér., tom. XIII (1899), pp. 520-527, 555. It may be remarked here that if we assign the inscription of Mogas of 78, to this era, it falls just at the accession of Gondophares; but see *Jour. Asiat.*, 5me Sér. t. XV, p. 128. —J.B.

The period of development is limited then between the birth of Christ and the fifth century A.D. In the seventh century, as stated above, the Chinese pilgrim Hiuen Tshang found the buildings in ruins, with clear traces of long decay. The 'most ancient of all the sculptures are, of course, those which represent purely Greek subjects, such as the Athene mentioned above. A further development revealing an idealistic and a realistic tendency, but at the same time a series that is more Hellenic and one more Indian, is very noticeable in different pieces of sculpture which, unfortunately, cannot possibly be examined in Europe. One seems to recognise a great many of the borrowings made: Greek elements, Roman, and even Christian. The Gāndhāra school has consequently a certain analogy with the old Etruscan. Even here an indigenous naturalism is found side by side with the influence of the architectural styles of west Asia—the Etruscan intermixed with the Greek. But as Italian art gradually passes into Christian, and endeavours to derive from the old types models for the saints of the new religion which has overthrown heathenism; so, in the Gāndhāra school, extraordinarily similar types are developed for the Buddhist saints. A wide range of homogeneous resemblances is apparent here: both religions, Christian and Buddhist, have in their ethical doctrines much that is related; the same external means, outrunners of ancient art, contribute to the development of the types, and, in addition, direct borrowing is evident. By its representation of forms, the school of the Gāndhāra monasteries is only a daughter of ancient art; but, as it represents none but Indian subjects—the saints and legends of a purely Indian religion,—it belongs entirely to Indian life: and this so much the more that it forms the groundwork for the canonical representation of the founder of the religion and several other personages, especially of the northern school; so also the Greek art of composition, as will be shown more in detail below, from this time onward, is apparent in Buddhist art in all lands.



In what follows we shall try to indicate the types occurring in the Greek sculptures, to fix their names as far as possible, and generally to sketch their genesis and further development.

As the central figure of most of these compositions (though also

41 RELIEF WITH SCENES FROM THE LIFE OF GAUTAMA BUDDHA (Takht-i-Bahl). Original in Berlin Museum, 20 inches high.

occurring frequently by itself), the representation of the founder of the Buddhist religion appears as a finished type (fig. 41). He is given again in the form of a young man, in a long robe which covers both shoulders. The face, in the older and more ideal conceptions, shows features resembling those of Apollo, while on the more modern and more stereotyped pieces the features are distinctly Hindu. The representations in Chapter IV. show the extremes fairly well. The hair is arranged in a *krobylos*: sometimes the figure is represented sitting, Indian fashion, with legs drawn up; at others standing with the right hand uplifted, or striding towards the right, and so on. The draping and treatment of the garments is thoroughly Hellenic; on the more ancient slabs it is often very delicate, and here and there it has quite a distinctive character; but on the later representations the different garments, which have become conventional and stereotyped, are arranged in a fashion that is decidedly not Indian. The position of the hand, and the arrangement of the garments, bear a certain relation to the treatment represented, and become typical in their portrayal of particular crises in Buddha's life. As the symbol of his claim to adoration, there appears a large nimbus surrounding the head (Sans. *bhūmandala*, *prabhūmandala*). On the reliefs of the Asoka period, and the sculptures on the gates of Sāñchi, which are related, the nimbus, as a symbol of the gods, is not quite unknown (Buddha does not appear in them at all); on the other hand it appears at Amarāvati, and, with some other elements, belongs to the interesting evidences which point to contact between these sculptures and those of the Gāndhāra school (see ill. from Amarāvati in ch. iv).

The nimbus is borrowed from the Greek school, yet it appeared very late in Greek art—in the time of Alexander.¹ Together with the kindred halo, it belongs originally to the celestial deities; it is interesting to note that, in this sense, it is not wanting in the Gāndhāra sculptures. On the relief from Jamālgarhi the deities of the sun and moon are represented with the nimbus. But that Gautama, not merely as Buddha, but also as a prince, receives the nimbus, proves that at that time his deification was already generally accepted. For such an attribute—which can properly be given only to a god of light,—must necessarily have separated him from the other figures, and put him on an equal footing with the deities there represented with the nimbus. That the Persian fire-worship facilitated the transference of the attribute is an important point, to which we must call attention, as, at a later date, Persian influences show themselves still more strongly. The nimbus is a purely artistic element which, executed in stone, presents a strange appearance, and points in the clearest way to an old school of art. In connection with this, the fact is to be noted that in reliefs

¹ See Stephan, *Nimbus und Strahlenkranz*, in *Mém. de l'Acad. St. Petersburg*, 8me Sér. t. IX; and also Gardner, *Coinage of Greek and Scythian Kings*, pl. xiii, 9; xvi, 4; xvii, 7; xviii, 22, 23; xxi, 8, and xxii, 14; Sauer, *Jour. As. 8me Sér. t. XV*, p. 144.

which go back to the ancient types of plastic composition (e.g. ill. 41, 57, 70) the nimbus is not found, while in artistically executed representations it exists (conf. ill. 50, &c.). But for the solution of this difficulty more data are necessary. In reliefs which represent scenes from the life of Gautama before he had left his home and obtained enlightenment, he is represented in royal garb, in the same manner as gods and kings are represented on the Sāñchī sculptures. It is true that there the figures are Greek also, and the nimbus makes him clearly conspicuous in the later works of art. In the fourth chapter the Buddha-type will be treated in detail.

As concerns the gods,—as was indicated above (p. 36), they retain the regal type, though sometimes with the addition of a nimbus (conf. ill. 50); and if, in the sculptures of the Asoka period, a characterization of the individual divine figure does not exist, expressing the rôle of a deity by his bodily presence, on the other hand we may observe that the Gāndhāra sculptures exhibit, in this respect, a rich individualization. Let us remember, first, then, that in the former, only attributes—the thunderbolt, lotus, and flowers—and in pillar figures the *vāhānas* of the gods are determinative; and now let us look somewhat more closely at the individual types of divinities.


Brahmā (or the Brahmā gods as a class), who, from the description given in the *Avidūreniddāna*, cannot be mistaken on the relief above-mentioned, has a kind of *krobylos*—a *jāta*—on his head, and, so far as can be seen from the somewhat damaged relief, is bearded. He is also represented as a Brāhmaṇa. The figure of Brahmā on this relief, which is probably of later date, reminds one thereby in a remarkable way of Peter. The garments are quite Grecian. The divine attributes, mentioned above—thunderbolt, flowers, &c.—are wanting to him (see also fig. 40).

The most important personality of the older Bauddha Pantheon—Sakka (S. Sakra)—should, however, be expected to bear his attribute of the thunderbolt (conf. fig. 40). In fact, many thunderbolt bearers appear, but varied to a remarkable extent.

On the reliefs, which represent scenes from the life of the great Teacher as he moves about among his fellow-men—teaching, reconciling, healing, and working wonders—the Gāndhāra sculptures almost invariably show, close to Buddha himself, a strange figure, the explanation of which has occasioned much discussion. In more highly decorative compositions this figure appears also, but in a corner of the whole, and not directly beside Buddha. The sketches in ill. 42 show some of the numerous variations in the representation of this being on earlier and later reliefs. One attribute, however, is common to all—a peculiar club-like object which the figure sometimes grasps by the middle with his right hand, and sometimes holds upright on his palm. In the case of the more modern reliefs (e.g. Nos. 2 and 5), one gets the impression

that the sculptor has not known exactly what the object was intended to represent. On the earlier and better composed reliefs, like the one from which No. 1 is copied, this object is more distinct, and it is always grasped by the middle (as in ill. 40).

This figure General Cunningham regarded as Devadatta, and others have agreed with this identification. According to the



42. VARIOUS FORMS OF THE
VAJRA-BEARER.

1 Silenus; 2, 5, Satyr-type;
4 Eros-type.

legends, Devadatta was of Buddha, and repeatedly conjecture has been sup- from the fact that on a this supposed Devadatta

5). But it is to be noted that the figure appears in the representation of scenes from Buddha's life, where Devadatta, according to the legends, could not have been present; as at the discourse at Banâras in the Deer Park, and at the Nirvâna scene,—where the Vajra-bearer invariably appears. And, further, it is a feature common to nearly all the examples that the upper part of the body is depicted naked (sometimes to the middle of the thigh). Even if we must always take Greek forms into account, it is indubitable that, on the basis of a religion which regarded the nude quite as unfavourably as did the Christian religion, this almost

a cousin but an adversary plotted against his life. The posed to derive support sculpture in Lahor Museum¹ is girt with a sword (No.

¹ *Indian Monks*, p. 122. A scene in the Kâtyâya legend.

invariable nudity must have a meaning. Even if Devadatta was really the *Guru* of a sect of naked monks, the partial covering is unintelligible.¹

Next it has been argued that Māra, the evil one, is represented by this figure; and for this view the argument stands thus:—The head of the figure, where preserved, differs widely in character. On the old and beautifully composed relief from which No. 1 is taken, the head is like that of Silenus, with tonsure, sensual fawn, and thin, streaky beard. On another (No. 6) he has bristling hair and a full beard, and is somewhat wild and demoniacal in look and bearing. In representation No. 4, which is taken from a relief representing the one given in fig. 57, the club-bearer is represented with a youthful appearance and with a wreath upon his hair. No. 5 is taken from a rougher replica of the same composition. The features of the head shown in No. 3, from a representation of the discourse at Banāras, which forms part of a pointed arch, express malicious joy. The club-bearer, it is inferred, therefore, is a being who looks with an unfriendly eye upon all Buddha's miracles and upon every practical proof of his ministry, who lies in wait continually, but is careful not to enter into direct opposition to him. In one instance this figure is represented (ill. 57) with a fan (Hind. *chauri*), with which he fans the great Teacher. The lying in wait and the mockery seem expressed on the relief represented in ill. 70 (from Natthu, near Sanghāo), which depicts Gautama Buddha's death. In the centre of the composition, behind the couch of the dying, is seen a bearded figure which raises high his left hand with the club-like attribute. On a rough replica of the same representation (ill. 74) this divinity stands at the head of the Buddha entering Nirvāṇa. On this relief he is naked but for a short loin-cloth, and unbearded, in his left hand he holds his club-like attribute, and with the right he points to Buddha's head. The relative size of the figure varies in different sculptures, while on some it is of the same size as the other figures, there are instances where it is of dwarf-like diminutiveness. It, however, is admitted that on some reliefs at least (ill. 44, &c.), he manifestly stands in a position as if a protecting guardian.²



13. THE THUNDERBOLT-BEARER. From Natthu near Sanghāo.²

¹ Monier Williams, *Buddhism*, pp. 52, 171.

² Cole, *Proc. Nat. Mus., G. - Bud. Sc.*, pl. 17. Burgess, *Mon. Ind.* pl. 113, 7.

³ That the same figure may appear on a combined slab in two different forms within the different relief areas—here bearded and again unbearded—need not surprise us in the case of the Sāṅghāra school which, exercising its art mechanically, always repeats certain compositions.

Now the figure may represent the old thunder-god Sakka, and, indeed, ought to represent him in all the instances where he appears in a protective and sympathetic way. For Sakka is the *Deus ex machina* of the Buddha legends; when anything important is about to happen on earth, his throne in heaven grows warm, and he hastens down to interfere in the interests of right and truth.¹

But, further, apart from the features as they now exist in these sculptures, the appearance of the figure is nowhere represented as distinctly inimical, and we may pause before regarding it as in any case representing Māra—the implacable enemy of the Buddha;—in fact, it would be entirely against all Buddhist ideas that he should ever appear among the followers of the Vanquisher.²

In the different representations of the Nirvāṇa scene, too, the personage in question appears to be clearly identified by the legends as Sakka, Satamānya, or Vajrapāṇi—the bearer of the thunderbolt. In a former birth, they relate, he had been the son of a Chakravartī, or universal ruler, and had taken a vow to defend Buddhism; he was then born king of the Devas of the Trayastrimsat heavens, and as such is the representative of the secular power and protector of the Saṃgha or church. Hence he came to be represented as the constant attendant of Buddha and ever at his call, holding the *vajra* as ready to crush every enemy. He attended at Gautama's birth, and at his flight from home; he assisted Sujātā to prepare his meal on the attainment of Buddhahood; with other Devas he congratulated Buddha on his victory over Māra; at the Muchalinda tree he brought Buddha fruit, a tooth-cleanser, and water to bathe his face; on the conversion of Bimbisāra, in the form of a young Brāhmana, he advanced through the crowd before Buddha, singing his praise. In the *Ambaṭṭha Sutta* we read that, when Gautama was forcing Ambaṭṭha to a confession, 'the spirit who bears the *vajra*³ stood over above Ambaṭṭha in the sky with a mighty mass of iron, all fiery, dazzling and aglow, with the intention, if he did not answer, there and then to split his head in pieces. And the Blessed one perceived the spirit bearing the thunderbolt, and so did Ambaṭṭha the Brāhmana.' Lastly, when he saw Buddha was about to depart, Sakka exclaimed in grief,

¹ I reluctantly differ from Professor Grünwedel as to the weight of his argument outlined above. We must bear in mind that this figure in all these sculptures is carved in most refractory material, on a very small scale, has been weathered by more than a millennium, and was, almost certainly, originally covered by a thin coating of plaster and painted. Such considerations should make us chary of laying too much stress on the features left on these small figures. Then the theory that the thunderbolt is an attribute of Māra and of the Devas generally is one for which I know of no sufficient evidence.—J.B.

² In this and the following paragraphs, I state the view which to me seems most consistent with the legends and the reliefs.—J.B.

³ Buddhaghosa identifies the Vajrapāṇi here with Indra. *Conf. Sac. Bks. of the Buddhists*, vol. II, p. 117.

'The Tathâgata is about to leave us to enter the great Nirvâna; he will no longer teach us, he will no longer protect us. The poisoned shaft hath entered deep, the flame of sorrow riseth up.' Then letting fall the diamond sceptre, in despair he rolled himself in the dust, and rising again full of grief and compassion he exclaimed, 'In the vast ocean of birth and of death who shall be our boat and our oar? In the darkness of a long night, who shall be our lamp and our watch?' Both Fah-hian and Hiuen T'sang refer to this and to the stûpa raised on the spot.¹ Now this Nirvâna scene is one of the most frequently represented, and in most, if not all, the reliefs Sakka appears there—often as a burly, bearded man, naked to the waist—either fallen to the ground, or standing by the dying teacher in an attitude of grief. The hand upon the head, or raised in the air, or pointing to the dying, are attributes expressive of grief or dismay.

The Nirvâna subjects thus explained lead us to conclude that in the others,—whether he appeared as a comely young Brâhmana (fig. 40) or in the burly form reminding us of a copy of a Zeus,—we have the same Sakka in all, distinguished as the thunderbolt-bearer or Vajrapâni; and as Strabo and his authorities regarded Indra as identical with the Jupiter Pluvius² of the Greeks, we can readily imagine how an artist at all familiar with the classical forms, on being called upon to represent the Indian ruler of the atmosphere, would naturally take some well-known type of Zeus as his model, and with the bushy locks he would copy also the nude trunk and even the beard of his originals.³ When a form was demanded representing the Deva 'as a young Brâhmana,' more or less modification and adaptation would be introduced; but the refractory character of the material would interfere with the nicer details of feature and the like. Whether the appearance in the earlier Gândhâra sculptures of a god bearing a thunderbolt always seen near the person of Buddha may, at a later date, have originated the Bodhisattva Vajrapâni of the northern school,⁴ must remain a probable conjecture.

¹ Sp. Hardy, *Man. of Bud.* 198, 298f., 355f.; Beal, *Si-yu-ki*, vol. II, p. 36; Remusat and Klaproth, *Mo-kou-ki*, p. 239; conf. Bigandet, *Legend of Gaudama*, vol. I, pp. 141-2, 154-5, II, p. 78; Rhys Davids, *Bud. Birth Stories*, pp. 67, 89, 109, 116-17. In Legge's translation of Fah-hian the illustration (No. 8) of the Nirvâna scene, from a Chinese work, shows Sakka fallen to the ground beside his sceptre.—J.B.

² Strabo, lib. xv, c. 1, § 89; conf. Lassen, *Ind. Alter.* Bd. II, §. 702-3; Muir, *Or. Sansk. Texts*, vol. V, p. 77.

³ Conf. *Globus* (1893), vol. LXXIII, No. 2, p. 170, fig. 2. There is another replica of No. 44, on which the bearded figure holds the thunderbolt—which is wanting here. Conf. *Jour. Ind. Art.* vol. VIII, pp. 78 and 35, pl. 10, fig. 1.

⁴ Further, as Vajrapâni swears to Buddha's doctrine, so Buddha—his master and defender—must have at his disposal Vajrapâni's weapon, the thunderbolt. Thus the legend of Buddha's thunderbolt arises, and also the use of the small brass vajras (rod-like, Mongol: *Opir*) which to this day are among the most indispensable attributes of a Lama. But that pictorial representations have exercised a very important influence on the creation of Buddhist legends has been mentioned when speaking of the

Māra Pāpiyān, or Vasavartī (p. 39), rarely, if ever, appears in Bauddha sculptures, except in the representations of the temptation scene. There, among the weapons that he and his host threaten to hurl at Sākyamuni, his sceptre javelin or vajra may appear, but not specially as an attribute, for the bow and arrows are rather his distinctive symbol.



44. GANDHĀRA RELIEF. From a photograph.

On the relief (ill. 44)² Buddha is represented with the wheel symbol, supported on the *trisula*, therefore preaching and surrounded by disciples. He sits under the Bodhi tree; and among his surroundings, a bearded figure appears on his right hand and

throne supports of the Lamas, and can hardly be sufficiently emphasised. With reference to the spread of Buddhism and the intercourse between different countries, it is interesting to note that the thunderbolt worshipped in Sa-ra near Lha-sa originated in Persia (conf. Laufer, *Sitzungsber. der Phil. Kl. Bayer.-Acad.* 1898, III, S. 591). I would remark that Māra has been received into the system at least of the red-capped Lamas (Padmasambhava's school) as 'Tse-ma-ra. He is the tutelary deity of Sam-ye, the most ancient monastery of Tibet, where he enjoys a strange ritual: *Jour. Buddh. Text Soc.*, vol. V (1897), II, pp. 3-4. But there a tutelary deity also—Kin-kas, i.e. *vajra*—is worshipped; conf. Jasche, *It. Dist. s.v.* However, these remarks are not decisive for our relief, though they may be of value for the later history of this type.—A. G.

² In Lahor Museum; see *Ind. Monument.*, pl. 96; and conf. Rhys Davids, *Buddhist Birth-Stories*, p. 100.

one without beard to the left. As to their persons we can say nothing, as almost nought but the shoulders are seen. The identity of the bearded head with that of the thunderbolt-bearer on the Nirvāṇa reliefs (No. 70) is evident; but we can hardly assume that the attitude here is inimical to the Teacher, or that the two heads represent a good and an evil divinity. In the line of sculptures above, we see the vajra-bearer on Buddha's left—here, too, with a sword—while another *deva* kneels on the right.

The designation Vajrapāni which we assign to these figures in the reliefs, suggests other conceptions—quite a new phase in the development of Buddhism. We have before us a descriptive term or poetical appellation which has crystallized into a special deity;¹—the term itself was perhaps taken from a *Stotra*, such as the verses of the *Lalita-Vistara*,—a term, indeed, which may even go back to the sculptor's studio. Let us fancy how the artist receives his commission: According as there is more or less space available, the pious donor will pay more or less; a Buddha, a thunderbolt-bearer, a few Nāgas, &c., will be brought together from the ready made figures and grouped as desired. Thus we see that we must everywhere work with a history of the types employed, and that these artist's types, in details as well as in whole compositions, may be used for different individuals and different events. Doubtless, in the development of the Gāndhāra period, changes of interpretation may have taken place, even through the artist himself. Let us remember that the huts of the Middle Ages were often the birthplaces of new doctrines: thus the idea strikes us that the Græculi and their disciples, who executed the first reliefs in Gāndhāra, were not without their influence on the religion. The artist is surely the first exponent of his own work. In the circumstances we have here, such must have been the case, when a mythology had to be first created from fixed types. No one has described this better, with reference to the circumstances in Gaul, than M. A. Foucher:²—"Do you want a Hesus, a Teutates? We can give you a Mars, a Mercury, and you can worship them under other names. We do not know your goddess Sulcis—you people of Aquæ Solis (Bath), but how would it do to make this representation of Athena stand for her image? . . ."

If now we consider more closely the early materials from which the Gāndhāra sculptor chose to represent the Indian legends, there offer themselves as the basis of his types—Zeus represented with the eagle (= *Garuda*); the eagle with the thunderbolt (*vajra*); the eagle with Ganymede³ (*Garuda* with the Nāgakanyā: conf. p. 109).

¹ On the genesis of new gods from epithets, conf. G. de Blonay, *Matériaux pour servir à l'histoire de la déesse Tārd*, Paris, 1895, p. 64.

² 'L'Art Bouddhique dans l'Inde' in *Revue de l'histoire des Religions*, tom. XXX (1894), pp. 366ff. Conf. for Hesus or Eus and Teutates, Lucan, i, 143; Lucan, i, 21.

³ The employment of this type in the Persian style plays an important part at the period of the migrations of peoples. Conf. Hampel, *der Goldfund von Nagy Szent*

If we call the figure Vajrapāni, what is it to be called when it appears twice on the same relief? We must decide (ill 45),—

(1) Whether we should call the one Vajrapāni, the other, Māra or Indra (Sakra). The latter is quite possible, since the texts often indicate both (as well as Śiva and Rudra) as different gods side by side; or,

(2) Whether we should think of the old Indian panoramic scenes which would permit two representations of the same person to appear on the same panel: but, so far as our evidence goes, panoramas are usually divided by pillars. The figures also are here so varied in appearance, dress, and attitude that we might readily suppose they are different.

The representation relates to the snake king Elapātra.² Elapātra



45. RELIEF FROM KOTH MONASTERY, NEAR SANGHIO. (Cole, *Proc. Nat. Mon. pl. 8*).

the Nāga appears before Buddha in human shape, in order to hear his teaching. Buddha requires him to show himself in his true form as a snake. The Nāga answers that he is afraid of the Garuḍas, the hereditary enemies of the Nāgas. Then Buddha commands Vajrapāni to protect him. Vajrapāni does so and the Nāga appears as a gigantic snake. The relief shows a small Vajrapāni in the background, who raises the thunderbolt threateningly, while in the

foreground the Nāga king, accompanied by his wife, stands before Buddha in water, and a second thunderbolt-bearer walks behind the Buddha. The indication of the Nāgas is the usual snakes appearing over the heads of the hero worshippers.

Sakka, converted into a Vajrapāni, loses his old Hindu character as a nature god; and, as is common with the Buddhists, he is multiplied into a class of Devas: thus, when Buddha returned to Kapilavastu, "the eight Vajrapānis surrounded him as an escort," and "divine Sakra, with a multitude of Devas belonging to Kāma-

Miklós, Budapest, 1885, figs. 4, 10, 11, 23. Compare, further on, for example, the bronze medallion in Speier, *Jahrb. des Vereins der Alterthumsfreunde im Rheinlande*, Hft. lviii, Tf. 1. This combination of the Vajrapāni with the Garuḍa still lives in Lamaism: there is a Vajrapāni, accompanied by Garuḍas, the Vajrapāni-śāhārya, — *conf. Globus*, 1899, S. 170b; and one with Garuḍa wings, Khyun-chog-ghan.

² *Conf. Schiefner, Tibet. Lebensbeschreibung des Sakjamuni*, S. 16 (S.A.); the same, 'Mahākātyāyana und König Tshāndrapadya,' in *Mém. de l'Acad. de St. Pétersbourg*, tom. XXI (1875), p. 11.

loka, took their place on the left hand." Vajrapāni thus got separated from Sakra and was converted into a distinct god, or into a Bodhisattva; lastly, Sakra sinks into a Yaksha.¹

The later Indian art retained the thunderbolt bearer: we see him as Sakka, for example, on the Amarāvati relief (in ch. iv.)² where he is present when Rāhula, Buddha's son, demands his inheritance from his father, and is clothed as a monk. Another figure which, though many handed, we must call Vajrapāni, is carved in the Viśvakarma Buddhist chaitya cave at Elura, and is here given as an example in fig. 47.



47. VAJRAPĀNI.
From Viśvakarma's
rock temple (Elurā)

Though different sculptors may have taken their own ways of representing Māra, still there was a fixed type also for this Deva. He appears, at a later date, in full festal attire, youthful in figure, with bow and arrow; and in this type (fig. 49) he appears at Buddha's temptation. He is thus brought into comparison with Kāma or Smara, of the Hindu pantheon, who also bears the names of Māra and Samāntaka. The worship of this latter god



48 THE THUNDERBOLT
BEARER From a relief
in Lahore Museum.

seems to have been much cultivated in mediæval India. His attributes, bow and arrow and Makara, ill. 33 (Dolphin) suggest that there is some connexion with the Greek Eros.⁴

On the relief on ill. 50, the lower subject presents Gautama on his faithful horse Kanthaka, riding out of the gate to spend his life as a begging ascetic. At the gate, from which the guards are fleeing, stands a kingly form with a nimbus, the divinity (perhaps) of the palace gate (*dvare adhiṣṭhātā devatā*), and, if so, a local divinity, quite in the style of later Hellenic art. With regard to the Hellenic influence under which the composition originated, it is of interest, further, to note that the right hand of the divinity stretches out into the frame and so points forcibly to what is following.

¹ In Japan the two temple guardians called Niō, and habitually found at the entrances, are named as Indra and Brahmā; but their type is derived from Vajrapāni (Shōmei-kongo). Vassiliéf, *Le Bouddhisme* (tr. par M. La Combe), pp. 197, and 193; Schiefner, *Tib. Lebensbesch.* S. 14.

² From Ferguson, *Trees and Serp. Wor.* pl. lix, p. 189.

³ Burgess, *Elura Cave Temples in Ar. Sur. W. Ind.* vol. V, pl. xix, 4.

⁴ The Holt or Hôlt, the spring festival in honour of Krishna's sporting with the Gopis, may perhaps be indirectly connected with Kāma,—but this is doubtful.

If we now look at a replica of the same subject in the Lahor Museum,¹ we find there that, in the place occupied by the gate



48. GĀNDEŚĪKA RELIEF IN LAHOR MUSEUM.

divinity, in the first representation, is an archer—perhaps Māra. In the *Aviddhāniddān*, it is related how, at the moment the gate *devatā*.

¹ Burgess, in *Jour. Ind. Art and Ind.* vol. VIII, pl. 10, 1, or sep. ed. pl. 17, 1; Simpson in *Jour. R. Asi. Soc. Arch.* 2d ser. vol. I (1894), p. 106.

opened the door, Māra came with the intention of stopping Gautama; and, standing in the air, he exclaimed "Depart not, my lord! in seven days from now the wheel of empire will appear, and will make you sovereign over the four continents and the two thousand adjacent islands" When Gautama asks who he is, he receives the reply "I am Vasavatti" (Sk. Vasavarti—'acting under the will of another'). Gautama's victory over the tempter is well represented by the immovable attitude of the chief figure here, as also by that of the umbrella-bearer stepping out vigorously over the relief.

It must be admitted, however, that any quite accurate apportionment of names for the accessory figures in this composition can hardly be given, since it has to do with a more or less extended scheme.

Māra's army, which combats Buddha and seeks to drive him from the "diamond seat" under the Bodhi-tree at Gayā, is effectively represented in the Gāndhāra school by means of popularised figures

of demons which have received at Greek hands a powerful characterization (conf. ill. 48). The original of this—one of the oldest and finest reliefs—is now in the Lahor Museum. The three lowest figures are soldiers, equipped partly like Greeks,¹ but with peculiar accessories—one wears an Indian loin-cloth and turban, another a kind of three-cornered helmet or hat which suggests the well-known whitey-grey felt caps of the Tibetans and Khwarezmians: to the heads, represented as quite human, a decidedly demoniacal expression is given by the great staring eyes and the wild hair of head and beard. It has been doubted whether this relief represents Māra's army, but its agreement with the Ajanta picture given in ill. 49), which, with the sculptured representation in Cave XXVI,² at the same place, must be considered. The relief arranges these frightful figures in tiers in a




49. MĀRA'S ATTACK, ON GAUTAMA.
Painting in Cave I at Ajanta, from Rājendralāl
Mitra's *Buddha Gayā*, pl. ii; conf. Griffith,
Ajanta, vol. I, pl. viii.

to the heads, represented as quite human, a decidedly demoniacal expression is given by the great staring eyes and the wild hair of head and beard. It has been doubted whether this relief represents Māra's army, but its agreement with the Ajanta picture given in ill. 49), which, with the sculptured representation in Cave XXVI,² at the same place, must be considered. The relief arranges these frightful figures in tiers in a

¹ It suited the stone-cutter who produced this relief, in representing the coat of mail—unintelligible to him—to put the scales with the rounded ends (openings) upwards. Whoever would use these sculptures, therefore, for the history of costume and armour must be careful.

² Burgess, *Cave Temples*, pl. li and p. 815. There are also two other fragments of temptation scenes in Lahor Museum. *Ind. Mon.*, pl. 183.

very clever way. In the first row are seen ordinary soldiers, behind them, in the second row, are the real demons, whose grotesque faces rise one above the other in a most effective way. On the Ajanta representations, also, soldiers appear in the first row, and the



50. AJANTA SCULPTURE (Lahor Museum),
The Bodhi-sattva Gautama leaving home.

hob-goblins behind them only. This graduated arrangement produces a quite peculiar effect in the relief. One figure, the first of the second row, the ample dimensions of which bind the whole

group into a sort of scaling-party, shows this cumulative arrangement in a grotesque fashion. The almost fleshless mask, which is evidently intended for a death's head, grins broadly, while the hairy hands are thrust into the corners of the mouth, on the body of the demon appears a wild bearded face, and over the bare skull there rises a grinning animal's head that forms the end of a skin cap. Detached elements of this powerful figure are to be found in the art of a later day—figures with faces on their bodies, or with half-macerated skulls, or with animals' heads over the real head of the figure, have been preserved even in the modern art of the Lantias. It would be an interesting but difficult task to find out how far these



51, FRAGMENT OF A GĀNDHĀRA SCULPTURE.

The Earth-goddess bearing upon her shoulders the feet of the horse *Kintōka*. Before are two men (*guard*), one in quilted mail with bow

Gāndhāra forms are shown in the Oni-types, so popular in Japan. The second figure of the second row is very striking. The clubs and peculiar fold of the sleeve are purely Greek; indeed, were it not for the fangs and the demoniacal features, one would be reminded of a Hercules. The three heads of the leader of the group are

almost surpassed by a bearded figure in the third row: only a Greek could have succeeded in combining these skulls, which evidently belong to three faces (though only two are recognisable). This form is unique, and the Hindu artists of later times were incapable of repeating the motif except by placing side by side three disconnected faces. The little flame on the tip of the tongue of the demon, who is represented with two swords, is also interesting.

On the reliefs given in ill. 50, 51 there appears a female figure which calls for special mention. Under Gautama's horse the upper part of a woman's body (much destroyed) is seen rising out of the earth. In Greek art the female figure rising thus from the ground is known as Gê or Gaia, the goddess of the earth. On the Buddhist relief, also, it is evidently the goddess of the earth that is intended. This is clear from a description of the situation in the *Avidāreniddna* of the Jātaka book. There it says, after the description of the repulse of Māra, literally this: "When Gautama desired once more to look back upon the city, the wish had hardly arisen in his mind when the great earth (Pāli, Mahāpathavi; Skt. Mahāprāthivi) turned round like a potter's wheel, as if to say: 'thou needest not to turn round in order to look,' and so let him see the town once more."¹ On the relief the feet (now broken off) of the



52. CENTRAL PART OF AN IVORY RELIEF, in the Casa Berberni, Rome. For comparison with No. 50.²

horse *Kanṭhaka* evidently stood on the forearm of the Mahāpathavi (ill. 50). Another incident of the Buddhist legend, in which also the goddess of the earth is represented as speaking, is of interest in connection with the question how far art has influenced the sacred texts. When assailed by Māra, Gautama, who is sitting under the Bodhi-tree, calls the Earth to witness that he has acquired the right of sitting in this place (on the "diamond-throne"—Vajrāsana) by reason of his liberal alms-giving in a previous existence. The description of the incident in the *Avidāreniddna* says merely that Gautama laid his hand upon the Earth, whereupon the Earth (Mahāpathavi) testified to his beneficence by a loud rumbling³. Now the description which the much

¹ Rhys Davids, *Buddhist Birth Stories*, p. 84. Conf. Foucaux, *Lalitā-Vistara*, pp. 198f; A. C. Warren, *Buddhism in Transil.*, pp. 61f.

² *Materialien zur Archäologie Ruesslands, herausg. von der k. archäol. Komm.*, No. 8, St. Petersburg, 1892, Taf. 14 (Russ.). Conf. below, note on coin of Demetrios.

³ Rhys Davids, *Buddhist Birth Stories*, p. 101. Conf. also the Gandhāra relief in Arnold's *Lights of Asia*, Mund. ed. p. 19, where the earth-goddess is represented under the Bodhi tree; and a pedestal in Lahore Museum, *Jour. Ind. Art and Ind.*, vol. VIII, pl. 18, 1, or sup. ed. pl. 16; Foucaux, *Lalitā-Vistara*, pp. 271-2.

later *Lalita Vistara* gives of this scene, seems to correspond exactly with the illustrations which show the earth-goddess introduced in the Gāndhāra sculptures. "The great earth-goddess, named Sthāvarā," it says there, "not far from Buddha, showed half of her body with all her ornaments."

This antique design is best represented by a copy on an ivory relief preserved in Rome¹ (ill. 52). In this instance it has to do with an Emperor-type developed from coin-types (conf. ill. 56 and coin of Demetrios)

Now the representations which show the event in profile are



53 GAULINA'S MAHĀBHINIŠIKRAMINĀ, OR REDEMPTION,
A relief from Loriyan Tugri, in Goleutta Museum

remarkable in this that below the hind legs also a figure rising out of the earth supports the horse. Thus, according as it is viewed from the front or from the side, we have two phases, one of which is due entirely to artistic considerations. It appeared to the artist irregular to place the horse in the side representations merely with the forefeet on a supporting figure (*Prithivī*), and so he places

¹ The composition is thus directly connected with the late Roman so-called 'giant riders,' e.g. on the pillar of Marten, Dürty-Hertzberg, *Gesch. d. rom. Kaiserreiches*, Bd IV, S 58; F. Heilmann, *die römischen Steindenkmäler des Prov. Mur. zu Triest*, 1895, S. 21, Nos. 81, 32, 33.

the hind-legs also on a figure,—later art has even a supporting figure for each foot of the horse. The real explanation, however, of this artistic phase is something different: we must, in the majority of the figures, think of the deities who raise the horse



54. THE BODHISATTVA LEAVING HIS FATHER'S PALACE.

[From the Trai-p'am prepared for King P'aya-tak, about a hundred years ago.
(Original in Berlin Museum).]

Kanthaka. Indeed, in a relief found at LoriyānTangai, the beings that uphold the horse have moustaches (fig. 53).¹ This sculpture,

¹ The legend (*Asiddhāniddha*) represents Gautama as considering whether he cannot leap over the gate while Channa hangs on to the tail of the horse, and it would have happened so if the gate-keeper had not opened the gate. We must recognise in the bearded figures the Yakshas which lift high the horse's hoofs so that their tread may not awaken the sleeping citizens (*Beal, Sac. Rts. of the East*, vol. XIX, p. 57; *Romania, Egypt*, p. 139; *Rhys Davids, Birth Stories*, p. 83). But on a sculpture at Lühör, represented in *Jour. Ind. Art and Ind.* vol. I (II (1896) pl. 22, 1 (or sep. ed. pl. 20, 1, conf. also pl. 11, 2), it is clearly two female figures who support Kanthaka's hoofs. We have thus a transition from the one to the other, i.e. we see how the Yakshas took their genesis in the Gāṇḍhī. In the legend of Padmasambhava, which however is the whole story of the flight from the Buddha legend, the Dakhinis and their support have been explained thus, take their origin in this way: conf. *Ein*

which measures 19 inches each way, is in the Indian Museum at Calcutta and is exceedingly well preserved. The representation of the Mahābhiniṣkramaṇa or renunciation here given, shows the white horse Kanthaka, as at Amarāvati,¹ on the flank, and we can note the trappings. Here his feet are borne up by two Yakshas, as mentioned in the Chinese *Buddhacharita*.² Sakra, with the *vajra* on his palm, follows close behind in the air, and, as usual, is nude to the waist: Chhandaka holds the umbrella over his master's head; three other Devas,—one bearing a short sword,—appear in the air in front; and two figures, one of them holding a bow (possibly Māra), stand in front, apparently addressing Siddhārtha.

Later Buddhist art has retained the uplifting of the horse. Fig. 54 gives an outline sketch of a beautifully finished, though mechanically composed representation from the Siamese *Trai-Pum* book, painted for king Paya-tak about 1780 A.D. Indra leads the horse, four Yakshas bear his feet, Channa holds firmly by the tail, Brahmā (of Hindu type) follows with an umbrella, the Vedas and drinking vessel. Before the group stands Māra represented as the prince of

nons. eference may here be made to two goddesses, to the first of which we cannot yet attach any name in Buddha iconography. Along with a small stūpa, carefully excavated by Major H. A. Deane, at Sikri in 1888, were found two sculptures of considerable interest, now in Lahor Museum: a very emaciated form of Buddha, and the female figure ill 55. These were first published by M. Senart.³ the western influence in the female figure is quite pronounced. It is 3 feet 0½ inch in height, but the feet are broken off. Whether she be a symbolic representation or a divine personage, is difficult to determine; she may even be allied to the earth-goddess in some Mahāyānist form; or she may possibly represent Hārītī, who will next be noticed. She is accompanied by three children, one of which sits astride on her right hip in Indian fashion, and which she is about to suckle.⁴ The head-dress and crown surmounting it have also a classical appearance. In other respects, the bracelets on the arms and the anklets are after the Indian fashion: and the pad that appears under the robe near the middle of the body corresponds, no

¹ Burgess, *Amarāvati*, p. 81, fig. 22; the representation of this scene must have been frequent at Amarāvati; besides the one just referred to, see also pl. xvi, 4, xxxvii, 5, xl, 1, xi, 6, and *Tree and Serp. Hor.* pl. xlix, 1, or lix, 1.

² *Sac. Bks. of the East*, vol. XLX, p. 37; conf. vol. XLIX, pt. 1, p. 61.

³ *Jour. Asiat.* Sine sér. t. 15, pl. ii and iii; reproduced in *Ind. Monks*, pl. 145, and in *Jour. Ind. Art and Ind. vol. VIII*, pl. 3. The illustration No. 55 is the sketch of Mr. J. L. Kipling, in *Jour. R. I. B. Arch.* (1891), p. 136, by kind permission of the Institute.

⁴ A statue at Lahor, accompanied by small attendant figures (*Ind. Monks*, pl. 86) will be noticed later on. Among the sculptures in the Lahor Museum is another, which may be compared with this (*Jour. Ind. A. and I. u.s.* pl. 5, 1). It is a statue of a woman, completely draped, and holding on her left arm a child. Unfortunately, the head and right arm are wanting, and the whole fragment is much worn and abraded. But the disposition is quite Western in disposition, and the general appearance at once recalls to one's mind a mutilated statue of the Virgin suckling her child (Sewar, *J. A. u.s.* pp. 141-2).

doubt, to the girdles which formed a feature of female attire, in a great many cases, at Mathurā, at Sāñchī, at Amarāvati, and elsewhere. On the forehead hangs a

jewel, in the form of a star, the cord holding it is clearly indicated coming from the hair. It may be noted that in the cutting of the eyes, the pupils are marked with the care observable in other works from the same source.



Fig. 55. FEMALE FIGURE WITH CHILDREN.
— From Sikri, Yusufal.

The other goddess referred to is a sculpture in the British Museum, about 28 inches in height, also representing a female divinity.¹ She has one child in her lap, one between her feet, and three at each side, of whom two on the left are wrestling,—recalling the expression in the *Ratnakūṭa-sūtra*, that each of Hārītī's children "was possessed of the strength of a great wrestler." The Sikri figure just described, it may be suggested, is possibly another form of this Yakshinī,—or, at least, of some allied being. For we can hardly fail in identifying the British Museum figure as Hārītī—"the mother of demons." The Yakshas (p. 45) are described as devouring human beings, and they possibly represent the aboriginal local divinities; and, if so, are a survival of demonolatriy. This Hārītī is described as having made a vow in a former birth to devour the children of Rājagriha, and was accordingly born as a Yakshinī, and became the

husband of the demon king Prajñāka. She became the mother of 500 children,² all very strong. To nourish these she daily took a child of Rājagriha. The people having appealed to Buddha about this, he took her youngest child Pingala—"the loved one"—

¹ *Journal of the Asiatic Society*, vol. VIII, pl. 4, 2; or sep. ed. pl. 2, 2, and p. 9. There is a rubbing of this relief in the Edinburgh University Library.

² Some versions of the legend say "ten thousand;" the Japanese say "a thousand;" but the number in the legend is not to be looked for. From *Lahitā Vist.* u.s. p. 171. We might infer that the demon king—chief of the Yaksha army—was called Prajñāka.

and placed him in his bowl. The mother sought for him seven days and, failing to find him, applied to Buddha for information. He addressed her—"Do you so tenderly love your child? yet you have 500 of them. How much more would persons with only one or two love theirs?" On this she was converted and became an Upāsikā, or lay disciple; and to feed her children Buddha said to her, "The Bhikshus, who live in their monasteries, shall every day offer you food out of their portion for nourishment." Hence, I-tsing tells us, the image of Hārītī was found either in a porch or in a corner of the dining hall of Indian monasteries, holding a babe in her arms, and round her knees three or four children. An abundant offering of food was daily made before it. This "demon mother of children" is described as one of the subjects of the Chatūrmahārāja devās. In Japan, she is known as Kishimojin, the protectress of the earth, and is represented carrying her youngest child Bingara in her arms, or sometimes with six daughters.¹

Another Indian goddess must also be mentioned, though she does not appear in the body of a relief itself, but is only employed decoratively. this goddess is represented (in a defaced sculpture in Lahor Museum) sitting sideways on a lion and holding on her knees a musical instrument in the form of a lute (fig. 56). This can only be intended for Sarasvatī, the goddess of music, while it remains enigmatical why the goddess, who plays no part at all in the older Buddhist texts, appears here beside the Hindū gods known by the Buddhists. This figure is possibly meant for a local deity. Perhaps, as goddess of Vedic poesy, she received the attribute of the lute. Sīrī (Skt. Śrī), the local goddess of the Asoka period, is not found in the Gandhāra sculptures, and later she disappears from the Buddhist pantheon. But Sarasvatī is very prominent not only in Chino-Japanese Buddhism—as the goddess Ben-t'en she belongs to the gods of fortune,—but in the Buddhism of Tibet, the so-called Lamaism, she has taken a prominent place among the goddesses of that degenerate form of the old doctrine. She is the only one of the female Energies of the Bodhisattvas whose characteristics are pronounced and well-defined; she is the Energy (Śakti) of the Bodhisattva Mañjuśrī or Mañjuśrī,² with whom we shall deal in a




56. SCULPTURED FRAGMENT FROM GANDHĀRA. A goddess playing the Vīṇā, sitting on a lion a type of the goddess Sarasvatī.

¹ I-tsing's *Record of the Buddhist Religion*, p. 187; Beal, *Si-yu-ki*, vol. I, p. 110; Bigandet, *Leg. of Gaudama*, vol. I, p. 245; *Archæologia*, vol. lvin, p. 241; *Mahāvagga*, I, 6, 30; *Tinaya Pit*, *Samyuktavastu*, ch. 31; and *Samyuktavastu-sūtra*, vii, 106; *Guide au Musée Guimet*, 1897, p. 203; *Catal. du M. G.* 1883, p. 218.

² Grunwedel, *Mythol. u. Buddhismus in Tibet*, &c., &c., 152, 155; Schlegelstein, *Buddhism in Tibet*, p. 68, n.; conf. Oldfield, *Sketches from Nepal*, vol. II, pp. 177, 188, 267. Śrī is one of the names of Sarasvatī; it is also applied in Nepal to Mañjuśrī himself. Waddell says no female energy is allotted to Mañjuśrī; *Bud. of Tibet*, pp. 355-6.—J.B.

subsequent chapter. The figure of Sarasvatī thus forms an additional proof of the connexion of the iconography of the northern school with the Gāndhāra sculptures.


In the Gāndhāra school the Nāga has preserved the same type which the older Indian art has created for him. The relief shown



57. GĀNDHĀRA RELIEF, LAHORE MUSEUM. Buddha attended by Vajrapāṇi, talking with a Nāga. From a photo.

in ill. 57,—other replicas of which are known,—represents the Nāga-king behind an altar, before which stand Buddha and Vajrapāṇi. The snake-hood over the head is hardly visible in the illustration, but on the replicas it is clearly seen. The relief represents the scene in which a Nāga wishes to be admitted into the order. Evidently the lower part of the Nāga's body, which is to be imagined behind the altar, should terminate in that of a serpent. This is a

thoroughly antique refinement which seeks to mitigate the repulsive appearance of the figure, and makes the human form possible for



58. RELIEF FROM LORIAN TANGA, IN CALCUTTA MUSEUM. Buddha attended by Vajrapāṇi, gods and men, teaching the Nāgas.

the Nāga as far as the figure is visible. From the time when a Nāga managed to introduce himself, in human form, into the


monastery till, in sleep or at Buddha's command, his true form was recognised, the question—whether the novice was a Nāga—was



59. BUDDHA, VAJRAPĀNI AND NAGAS (Takht-i-Bahī).

embraced in the formulæ for admission to the order (*Kammavācchā*), and to this day the ritual is thus completed. Ill. 58, from Loriyan Tangai, is almost a replica of the same, only the Nāgas appear in it to be rising out of water; and fig. 59, from Takht-i-Bahī,

is a third example, in which a good representation of Vajrapāṇi appears¹ In many sculptures, in the rock-temples, figures of Nāgas, both with the full human form and also showing only the trunk, are represented upholding the Padmāsana or Lotus-throne of the Buddha With the lotus stalk growing out of water, it is not inappropriate as a decorative device This is exemplified in fig 60 from the Kanheri Caves.² The Nāga seems at a later date to have



60. BUDDHA'S LOTUS THRONE SUPPORTED BY NĀGAS (Kanheri Caves).

been looked on as a protecting power (Burgess, *Cave Temples*, pl. xxxix).

But the purely human form with the snake over the head appears also on the sculptures of the Gāndhāra monasteries. The most remarkable representation of this kind, which evidently was popular as a decoration, has been quite misunderstood by its interpreters. A group—in which an imitation of the Ganymede of Leochares

¹ *Journ. R. A. Soc.*, 1896, p. 422.

² The numerous sculptured panels in the Kanheri Caves, if carefully delineated, would form an important chapter in Buddha iconography.

(B.C. 350)¹ has been, with reason, recognised,—appears in the Gāndhāra sculptures in several replicas (conf ill 61)² A rather coarsely executed female figure, from the back of whose neck, on the best preserved relief, rises a long snake, is borne into the air by a great eagle. The features of this female figure, whose uncovered right breast escapes from the otherwise ample garments, are distorted with pain. The eagle's beak tears at the serpent. The bird itself has a cap with a kind of fillet and ear-rings¹ Cunningham tried to explain the group as the ascension to heaven of Māyā, Buddha's mother, who according to the legend, died seven days after the birth of her son. Apart from the fact that the legends do not speak of an eagle thus carrying off any one to heaven, or even of any sort of ascension, but only of re-birth, —it seems clear from the representation itself that it is intended for a Nāgī, i.e. a female snake-demon who is borne off into the air by a Garuda,—for the great bird decked with these ear-ornaments can be none other than the Garuda or Suparna with the golden wings. Legends of such acts are frequent in Buddhist literature, so that representations of them cause no surprise. The Baudhdha drama of *Nāgā-nanda*, already mentioned, will at once occur to the mind in connexion with the representation, but in the *Jātaka*s there are two or three that speak of the Garuda king carrying off a beautiful queen from her husband,³ and it seems here as if he had taken



61 RELIEF FROM SANGHĀO.

Cole, *Pr. Nat. Mon.* pl. 8.

¹ Visconti, *Mus. Pio-Clement.* vol. iii, p. 19; Muller, *Denkmäler d. alten Kunst*, vol. i, pl. 86; Zanetti, *Statue*, vol. ii, pl. 7; Stuart's *Athen.*, vol. iii, pls 2 and 9; Lübke's *Hist. of Sculp.* vol. i, p. 187.

² Cole's *Pres. Nat. Mon. Ind.—Græco-Bud. Sculp.* pl. 3; and *Anc. Mon. Ind.* pl. 118. This important sculpture disappeared at Lihor. Two less perfect examples are represented by Cole *ibid.* pl. 4 and 17, or *Anc. Mon.* pl. 114 and 115. Conf V. Smith, *Jour. A. S. Beng.* vol. LVIII, pp. 183-85.

³ The *Jātaka*, ed. Conwell, vol. III, No. 327—*Kakati Jātaka*, No. 360—*Sussongā Jātaka*, and No. 366—*Kumbhā Jātaka*.

hold of a Nāgi by the neck of the serpent, and is carrying her off, his talons holding her by the waist. The Garuḍa represents the type that still exists in the northern school (Tibet), and here too it is very frequently represented as tearing a snake-maiden in pieces by thrusting both its talons into her breast. As a decorative motif this group, arranged somewhat differently, is very frequent on gates, in apses, windows, and on throne-backs (conf ill. 32, &c). It is quite easily conceivable that the replica of the Leochares group, which was at the disposal of the unknown stone-cutter of Gandhāra, must have produced a very great impression. That very attitude of the Garuḍa (which is represented quite as an animal) to its helpless human victim—to which, in order to heighten the pathos, a female form was given,—was quite in the spirit of Buddhism. If this interpretation requires confirmation, it is found in a fragment in the British Museum, about 6 inches broad by 7½ inches in height (ill. 62). The work is somewhat coarse and the head of the great bird has been broken off; but here he has been represented as carrying off both a male and female Nāga—one in each claw, while a second female lies below, a male stands on the proper right, apparently in an attitude of defence, and traces of a fifth figure are seen on his left.

By the name of Buddha's mother it was thought that a series of female figures found in Natthu, near Sanghāo in the Yūsū(zai) district, ought to be described. These figures, which are mostly very gracefully and pleasingly executed, stand, with one leg crossed



62. GARUḌA CARRYING OFF NĀGA YOUTHS.
(British Museum)

over the other so that one hip protrudes, under trees whose branches they grasp with one hand. One arm is always posed somewhat coquettishly on the protruding hip. Besides the drapery round the legs, three of the four examples recovered wear a sort of jacket, one of which is open down the front; three have scarfs over the shoulders; and three wear bead-girdles round the loins, with a clasp suspending a leaf-shaped ornament. The hair is waved over the brow and plaited into a wreath above, terminating in knobs; and all wear earrings, necklaces, torques and bangles round the wrists and ankles. The costume proves at once that Māyā cannot be represented thus; all these women wear Persian trousers and long jackets with sleeves; in their hair are fresh lotus-flowers;

like the dancing girls on the ornaments of the architrave of the gateway at Sāñcht, they may represent Nāch-girls employed for side decorations on reliefs of larger groups, or on portions of façades.¹ Conf. ill. 63, and above pp. 40, 41. But the pantheon was too numerous to require, even for a decoration, to resort to the merely human or secular individual. The Yakshins are Dryads as well as spirits of the air; (the Yoginis or sorceresses of Hindu myth may possibly be only a modification of the same, of whom six appear in the iconography of Tibetan Buddhism—always dancing naked); and we may regard these figures as probably analogous to such *devatas* as Chulakoka Devata and Chundā Yakshini, found at Barāhat. Similar figures are found on mediæval temples, and even on modern ones.²

Mâyâ, the mother of Buddha, and her sister Prajāpatî are depicted on the reliefs in Greek dress—upper and under garments; but with Indian ear-ornaments (Hind. *Karan-phāl*), and large anklets (*ghunghru*) on the feet. The female figures are remarkably coarse; Indian exaggerations appear much more distinctly and with a more unpleasant effect in the contours of their figures than in those of the men. A favourite subject is the scene already mentioned, of Buddha's birth in the Lumbini garden. As Mâyâ is stretching out her hand to grasp the blossom of a sāla-tree, the child springs from her right side, is received by Brahmā, and



63. DANCING FIGURE.
From Natthu Monastery.
Cols. *Pr. N. Monts.* pl. 15.

being set down, advances seven steps with the boast, "I am the best in the world." On this relief (ill. 64), from Loriyan Tangai, now in the Calcutta Museum, we may note the appearance of the child twice to indicate both the birth and the assertion of greatness. The legends mention *chamaras* and a *chhatra* appearing in the air; and

¹ Conf. Cole, pl. 10 and 15, 2; or *Pres. Nat. Monts.* (1896), pl. 93, and *Anc. Mon.* pl. 116, 2; and Fergusson, *Trees and Serp. Wor.* pl. iii, 1, ix, and xiii.

² Among Buddhists a woman representing a goddess to be worshipped is also styled a Yogini. For the Yakshas, see above p. 45; Burnouf, *Introd.* (2nd ed.), pp. 480, 596-7; *Notes on Ajanta Paintings, &c.* p. 103 and figs. 32-36; *Arah. Sur. W. India*, vol. III, pl. xx, 4; xxi, 5-7; and xxvi, 4-6.

in this relief a *chāmara* is represented above the head of Brahmā Śakra and other gods were also present. This sculpture is about 18 inches high. On the relief shown in ill 64 an ancient Nike type has supplied the prototype for the figure of Māya. Another representation also from Swāt (fig 65) includes two of the women in attendance on Mayadevī together with the same three Devas as before.



64. SCENE IN THE LUMBINI GARDEN.
From Lorian Tangai. In Calcutta Museum.


This mode of representation of Gautama's mother continues in later art. The Tibetan figure sketched in No 66, so far as the Māya is concerned, rests distinctly on the Gāndhāra form; but in later Indian reliefs, as at Amarāvati, Fergusson, *Tree and Serp.* *Wor.* pl. lxx and xxi the Māya looks exactly like the Nāch girls

mentioned above. It naturally occurs to one that here we have to do with an instance of Buddhist myth formation, which has been developed in connexion with a special artistic type. The application of an existing model to a distinct legend gives rise to a want of clearness, which unfortunately we too often meet with. In Gandhâra the model is artistically differentiated by modification of the costume and by the manifest adaptation of an ancient Nikê for the representation of Gautama's mother. As regards the origin, we have here one of the instances where archæology aids in explaining the texts by pointing to the source of Indian myth formation.¹

A peculiar figure, the signification of which it is difficult to fix, appears on the reliefs which represent Buddha's death (conf. ill. 70 and the fragment No. 77), at the foot of the victor as he enters Nirvâna. A fully-clothed, earnest-looking, un-bearded man, whose head is so enveloped in a close-fitting cap or cowl that only the face is visible, holds in his left hand, on the different replicas of the



65 THE LUMBINI SCENE.
Fragment, from a photograph.



66 MÂYÂ IN THE LUMBINI GARDEN

The infant Siddhârtha springs from her right side and the gods receive him. From an old picture (companion to Nirvâna picture ill. 75)

¹ On this compare the pertinent remarks of L. de la Vallée Poussin, *Bouddhisme, Etudes et Matériaux* (Lond 1898), pp 168f. The Devadâst dancing under the tree has, moreover, continued in Brâhmana art. Thus one is found represented on the Brâhmana Picture of the World in the Tanjor Library, of which a copy is in the Berlin Museum.

scene,¹ a staff with what might be intended for a sort of noose or



67. FIGURE OF A BRAHMANA.

Gandhara: from a photo.

loop at the upper end of it. Might this represent the mendicant friar's jingling staff—the *hi-ki-la*, (Tib. *hKhar-gsil*) carried by the *bhikshus* of the northern schools;² or was that introduced so early as to appear in these sculptures? Though the dress may possibly give the figure the appearance of a messenger, we can hardly take it for the messenger of Yama, the god of death; nothing in the legends would suggest this; and in Buddha's Nirvāṇa there is clearly no question of a death,—though such a figure, typifying the event, would agree with the character of the latest Hellenic art. Nor can it be Chunda the smith, who supplied Buddha with his last feast (*kari* and pork),—for neither does he figure in the legends on this occasion, and his tongs could hardly be misrepresented by such a staff as appears in his hands. May we not then conjecture that it was intended for the monk Kāśyapa who, though not actually present at the *parinirvāṇa* scene, arrived afterwards and, asking that he might see the marks that had prognosticated Buddha's destiny, was honoured by the prodigy of the feet appearing of themselves? Kāśyapa and Ananda

are the two personages pious Buddhists would expect to be repre-

¹ *Asp. Mente. Ind.* pl. 181, 2; 118, 4; 122; or Cole, *Graeco-Buddh. Sculpt.* pl. 16, 2; 17, 4; and 22; *J. Ind. Art. and Ind.* vol. VIII, pl. xiii, 6; or sep. ed. pl. xi, 6; also figures 70, 72, 73, 74, and 75.

² The Singhalese monks follow the early orthodox fashion—making no appeal for alms. *Compendium, Buddhism*, pp. 468f.

sented in the scene. Kāśyapa learnt of the decease by seeing some one (Subaddha?) carrying one of the Mandārava flowers that had fallen at Kusināra. Might he not, further, be indicated by such a flower on the head of his staff? In some, perhaps later, replicas this figure has disappeared, as it were, among the mourners, without being assigned any other special rôle.

I have now enumerated those gods and demi-gods of the Gāndhāra sculptures known to me. As regards the mortals, the Brāhmanas take the first place (conf. ill. 67, 68). Generally speaking, the type must be the same as that of the Asoka period, making allowance, of course, for its further development. They are represented as bearded men simply dressed; the hair is not dressed turban-wise in plaits about the head, as at Sañchī, but fastened together like a *krobilos*, in a wavy tuft on the top of the head. Most frequently they are represented as old men leaning on a staff or led by their disciples, and several of the older of these Brāhmana representations (a blind old man occurs frequently) are of uncommon artistic merit. See also below, fig. 93.



68 RELIEF FRAGMENT FROM SWĀT.

An old Brāhmana sitting on a pillow of straw under a leaf hut, a scholar behind. Original in Berlin Mus.

Among the other figures—men and women of different conditions—apart from the fact that different races are represented, there occur two kinds of types from a stylistic point of view: beside purely Hellenic forms, the Indian element is very prominent. Generally speaking, the principal figures, Buddha, kings, gods, and so on, have on the whole rather the ideal Greek types, while the other figures are less and less conspicuous according to their importance. But, among uncouth and coarse figures of inferior composition, there would also seem to appear a purely Greek type, which haply may have suggested itself as appropriate. The repre-

sentations of royal figures (conf. ill 88, and in ch iv) are of great interest from an antiquarian point of view, especially as regards ornament and dress. Long breast-chains, the clasp of which lies on the breast and ends in two animals' heads, festooned cords with square appendages, which now-a-days would be called *Ta'wîs* (*tâbîj*)—amulets—are especially striking. In the more important types the old Indian costume is always found. Along with these barbarian types, men of small stature are prominent—with features that are certainly not Indian and heavy moustaches, clad in trousers and long coats with sleeves, and again horsemen and camel-drivers in costumes that are not Indian, and others of the same kind.

It has already been mentioned that the dress of the women, where the principal figures are intended, is mostly Greek, although the ornaments—earrings and anklets—are Indian. An interesting feature is presented by the armed women, the female body-guards of the kings, who were well known to the ancient historians and are spoken of in Indian literature as *Yavanânîs*—Ionian women, i.e. women from lands under Greek rule (conf. ill. 81). Among the subordinate figures, as we have already mentioned, there appear women in Persian dress: wide trousers, sleeved tunics reaching to the knee, and loose upper garments resembling shawls.

The chief significance of these single figures lies in their bearing on the history of religion and civilisation; as regards their artistic value the following judgment should perhaps be pronounced upon them. The employment of the types, above described in detail, of which the reliefs are composed, is only a more or less clever adaptation in a new domain, of the finished phraseology of an art already in decadence, whose moral earnestness, as seen in particular modifications, lends them a charm which rests indeed only on this change of rôle. These types, created, perhaps at the word of command, by the dynastical interests or by the personal initiative of one of the Hellenic kings who favoured Buddha's religion, have a certain development which, as we pass from replica to replica, ends with a degeneration in which individual ideal forms, preserved as by miracle, appear beside creations which are childish and coarse. But that their genesis was accomplished with great ability and intelligent deliberation will be seen by the treatment of the relief as regards its composition. The permanence of single types, as well as of whole compositions in the sacerdotal sculptures of the northern school, proves how greatly native interest has been excited thereby.

In truth, the tradition of the northern school proves very reliable. Later on, in speaking of types of Buddha, we shall have occasion to point out that the miniatures of Tibet (paintings and bronze casts) are capable of affording very substantial and unexpected aid in correctly explaining not only the single figures but also the compositions as such. Unfortunately, space does not allow me to enter into all the consequences of this fact: all that I may

hope to attempt is to represent convincingly the facts and thereby to explain correctly the sculptures to be noticed

As a preliminary to entering upon this subject, it is further necessary to compare the Chinese and Japanese pantheons, as well as their favourite compositions, with those of the Lamas, in which case a history of the types, going back to the sculptures of the Gāndhāra school,

must be attempted. It is a troublesome task, but only in this way is a scientific archæology of Buddhism made possible. Many interesting results may be obtained from a special study of the Gāndhāra sculptures by themselves combined with tentative efforts to trace those types which are already known to us from the history of Hellenic and other art; but this investigation will always have to cope with the greatest difficulties, and be exposed to strange mistakes. A remarkable proof of



69 BUDDHA WITH DISCIPLES.

Relief from Takht-i-Bāhi original in Berlin Museum.

this was the supposed seizure of Māyā by the eagle! To leave the ecclesiastical tradition of the northern school out of account is absurd.

That certain forms became quite changed in their development, were absorbed again into ecclesiastical art, and obliged to give place to new formations, is explained by the evolution of new sects; and if we take into consideration the constant equalizing efforts of Buddhism, we cannot wonder that individual elements again become models for new arrangements; and fresh interpretations are always possible. But I must defer the detailed discussion of this and many other questions.

If we now pass to the compositions,—one of the most interesting and frequently repeated is the death of Buddha (the *Mahāparinirvāṇa*, ill 70-74, 77). We shall treat this representation in some detail, and it may be well to remember that the legends ought to be our guides: in attempting to interpret the scenes, we

ought in the first place to look for the personages referred to in the literature. We may not import others that are not mentioned, in order to explain what we may not quite understand.

In the middle of these reliefs the dying teacher lies on a raised couch (Hind. *chārpai*); the deities and monks stand round him.



70. RELIEF FROM THE LOWER MONASTERY AT NATTHU NEAR SANGHĀO.
BUDDHA'S NIRVĀṆA. From Cole, *Fr. Nat. Mon.* pl. 92.

In ill. 70 the vajra-bearer stands beyond, lifting his arms in despair. One of the monks (Ananda) has fallen to the ground in his distress, while another, at the head of the couch, raises him by the hand. The figure at the feet,¹ who has already been mentioned (p. 113), has his robe (*chaddar*) drawn over his head, somewhat as women wear

¹ In the Ajanta sculpture (Baruas, *Ajantāvali*, p. 90) this personage seems to be represented by the large figure behind the feet of Buddha, and there he has no rod. In the Bombay V. and A. Museum is a much damaged replica, 13 inches by 11, of ill. 71, and another in better preservation (21 inches by 15) without the fallen monk, and with Vajrapāṇi holding the figure at the feet. Both are from Marjān tope near Miyan Khān. There is also another copy, about 20 inches by 17, from Chinglai Siān, much like the two figured in ill. 70 and 72.—J. B.

the *sāri*; he carries a thick rod or staff,—sometimes it is represented as a number of thin rods bound together (*fascēs*),—the upper end being thicker or broader than the shaft. Whoever he



71. MAHĀPARINIRVĀNA SCENE FROM IONIAN TANGAI in India Museum, Calcutta.

may represent, he is deeply interested in the decease: can it be Kāśyapa? The background of the compositions is almost always filled in by the traditional two sāla trees of the little wood of Kuśi-

nāra, and among their foliage we usually find represented the Devis who resided in, or watched over them, and who, on the occasion of the decease, are said to have thrown down beautiful flowers on the Buddha and sung in his praise. Devatās, Nāgas, and other supernatural beings also showered Mandārava flowers (*Erythrina fulgens*) till they were knee-deep. This is probably the meaning of the flying figures in the upper part of the relief ill. 71.



72. MAHĀPARINIRVĀNA SCENE FROM LORIYĀN TANGAI.

The monk sitting in front beside the tripod water-cooler (ill. 71) appears in most of the reliefs, generally, but not always, facing the couch. He appears also in the Ajantā relief. In the sculpture from Loryān, Tangai, in the Calcutta Museum, measuring 2 ft. 4 in. long by 1 ft. 4 in. high, we have one of the most artistic representations as well as the most elaborate in detail (ill. 71). In this, and in another from the same locality (ill. 72), we observe that the fallen figure is Vajrapāṇi. The replica (ill. 73) from Kāfarkot in Swāt, and now in the British Museum, is on a slab 16 inches long by 10 high, and there Vajrapāṇi is represented standing at the head of the

couch, holding up his right hand in dismay and grief at the demise of the Master whom he had constantly followed to protect. The relief from Natthu (ill. 74) is almost a copy of this.

The representations of this subject differ in minor details, but the general features seem to persist down to modern times: these permanent features must have been regarded as essential. In most



73. BUDDHA'S NIRVĀṆA. RELIEF FROM KĀPĀNKOT, SWĀT VALLEY
In the British Museum.

of the copies of this scene we find these,—(1) the small figure of an ascetic seated in front of the couch on which the dying Sākyamuni lies; (2) Vajrapāṇi—the bearer of the *vajra*; (3) a naked figure close by; (4) the Sāka trees, between which the couch was placed, usually with the Tree Spirits (females) rising among the foliage and adoring the Teacher; (5) the robed figure with (or without) a rod or baton, at the foot of the couch; and (6) the gods and other

attendants. Careful study may yet determine satisfactorily who are intended by each of the individuals thus represented; but the legends must be our guide. We read of Subhadra, the Brāhmaṇa heretic (possibly a follower of the naked Tīrthakas) being converted by the dying Buddha and immediately entering Nirvāṇa; of Ananda, Aniruddha and Upāvana attending the dying Master; of Vajrapāṇi's great grief; of the visit of the Malla chiefs of Kusināra; and of Kāśyapa's arrival and worship of the sage's feet.¹ Possibly these may be identified in one or other of the reliefs.



74. BUDDHA'S NIRVĀNA. Relief from the upper monastery at Naṭṭhu (Yāsuṣāi). From Cole, *Pr. Nat. Monis.*, pl. 16.

Among the striking features presented by the Gāndhāra sculptures is the fact that, beside figures of quite perfect formation, cases of awkwardness occur that otherwise appear only in works of primitive art. The sketch (ill. 74) of the Nirvāṇa scene shows the usual arrangement with the deities round the couch, &c. Here the well-formed figure at the Buddha's feet and the stiffly depicted monk alone represent contrasts such as are met with only in the decay of art. The mechanically executed figure, too, of the reclining Buddha, from the expression of the face, is simply a standing figure laid down. If we turn the picture round, we have simply the upright statue before us.

This composition, two other replicas of which are found in Cole's collection², gives evidence of having been long in vogue, for modern

¹ Rockhill, *Life of Buddha*, p. 128. The *Acaddha Sataka* (x, 10) mentions that on the occasion of the Nirvāṇa, Sakra, Brahmā, and Anuruddha each chaunted a separate verse. In the above description I have not quite followed Professor Rockhill's text.

² Cole, *op. cit.* pl. 16, 2; *Pr. Nat. Monis.* pl. 121; conf. Cole, pl. 17, 4, and 22.

Tibetan and Chino-Japanese representations (conf. ill. 75 and 76) still show clear signs of having been based on the old Gāndhāra reliefs.

Clearly the entourage of Buddha's death-bed has grown with the embellishment of the Buddha legends. Along with Buddha's chief disciples are assembled as mourners not only representatives of all classes of the gods, but of all the demons: Nāgas, Garuḍas, all sorts of monsters, and representatives of all living creatures. Particular figures, still clearly defined in Gāndhāra, as we have already mentioned, have disappeared from the number of the mourners. It is




75. NIRVĀNA (MYA-NGAN-DAG) OF GAUTAMA (SHA-KYA-THUB-PA). FROM AN OLD TIBETAN PAINTING. ORIGINAL IN BERLIN MUSEUM.

one of the ingenious suppositions of Vincent Smith that the subject-matter of this most expressive composition of old Buddhist art has been derived from Greek and Roman sarcophagus reliefs.

The composition of the reliefs of the Gāndhāra monasteries is throughout based upon ancient models. The relief itself is set deeper than was the case in the older Indian art: for the sculptors of the Aśoka period, and of the schools that sprang therefrom, executed hardly any but flat reliefs. The individual figures of the Gāndhāra reliefs are types of statuary arranged beside one another, starting from the middle, and grouped always according to the importance of the individual figure (conf. ill. 45, 69, &c.)

The same figure can even be used in the representation of different scenes: thus the figure of Buddha in the different scenes of his life is based upon a reproduction of a few statuary motifs; this adaptability is remarked in the case of accessory figures, e.g. (ill. 46 and 48) gods, disciples, spectators, devotees, soldiers and servants. We at once think of model figures brought together in the mechanical execution, more or less numerous according to the means which the donor wished, or was in a position to spend on a relief. Side-figures

would sometimes change their rôles: a figure that in one relief throws down flowers, in another may throw stones—even at Buddha.



78. *PARINIRVANA OF GAUTAMA BUDDHA.* A Japanese painting from a Chinese copy. The couch of the dying is surrounded by his disciples, gods, and representatives of all classes of living beings. Above the table tree is the weeping mother of Buddha, descending from heaven. Conf. Hofmann, *Buddha-Parinirvana von Nipon.* Original in Berlin Museum.

This form of composition, due to ancient influences is retained in Buddhist art and is powerful and permanent in the northern canon, on the reliefs of Borobudur; in Java, the compositions are also put together according to this plan. From these reliefs, which have

been constructed purely on antique models, and which, separated from one another by small columns and pillars, have served as gallery decorations, a series of scenes is afforded by slabs known to me, which are either model compositions (this is more rarely the case), or which have been copied from still older ones. It thus happens that the composition in its principal features varies only slightly in the replicas; but that besides slabs where the figures are numerous—a 'scriptio plena' as one might say—there is often found a 'defectiva,' which retains the main design but curtails the rest, thus frequently omitting just what is most important. Of the following scenes more or less complete replicas are to be found—I shall mention only a few—the birth of Gautama in the Lumbinî garden, in full composition—Mâyâ, Prajâpati, Brahmâ, Sakka behind Prajâpati, girls with palm-branches and pitchers (conf. ill. 64, 86, and Cole, pl. 11, 2, 10 [only two girls]; Vincent Smith, pl. 9). Gautama leaving his palace, in full composition: Gautama on horseback on the shoulders of the earth, before him the palm-bearer, beside him Mâra, guards in flight, and god of the gate (conf. ill. 50, 51 and 54). The simplest form of this representation shows only the Bodhisattva riding out from a gate.¹ In this composition the artistic element is striking (conf. p. 27). Further, a series of scenes from the miracles of Gautama while he sojourned upon the earth. The construction of these last-named reliefs is usually thus:—In the centre stands Gautama coming from the left, near him Vajrapâni alone or with disciples and people also near; Gautama



77. FRAGMENT OF A RELIEF WITH REPRESENTATION OF BUDDHA'S NÎRVÂNÂ. Swât district. Original in Berlin Museum.

with palm-branches and pitchers (conf. ill. 64, 86, and Cole, pl. 11, 2, 10 [only two girls]; Vincent Smith, pl. 9). Gautama leaving his palace, in full composition: Gautama on horseback on the shoulders of the earth, before him the palm-bearer, beside him Mâra, guards in flight, and god of the gate (conf. ill. 50, 51 and 54). The simplest form of this representation shows only the Bodhisattva riding out from a gate.¹ In this composition the artistic element is striking (conf. p. 27). Further, a series of scenes from the miracles of Gautama while he sojourned upon the earth. The construction of these last-named reliefs is usually thus:—In the centre stands Gautama coming from the left, near him Vajrapâni alone or with disciples and people also near; Gautama

¹ Conf. Arnold, *Light of Asia*, ill. p. 86; Burgess, *Amaravati*, p. 81.

posite, then Gautama with his entourage, converts or devotees (cf. ill 57, 69).¹

Gautama usually takes a position reminding us of the ancient sacrificing commanders, the alms-bowl (*pātra*) taking the place of a patera (conf. ill 79 and *Veröffentlichungen aus d. Kgl. Mus. Völkerkunde, Berlin*, V, 130)

These compositions, generally very similar, must no longer be regarded, I think, as representations of a fixed legend, but as a mark of respect for Buddha on the occasion of a conversion, a sacrifice, &c, which had been performed by him. From architectural considerations, uniformity of the relief may have been the standard for these forms.

According to this, we would have before us the very reverse of an Asoka style. In these compositions (conf. pp 65ff) the situation is always broadly and readily worked out, but generally without a central group, as Buddha is wanting in them. But in the Gāndhāra representations we have Buddha and his entourage as a model, which, by certain local indications, attributes, and such like, is apparently described as connected with a certain legend. Unfortunately, this model has proved absolutely indestructible in later Buddhist art.



URUVILVĀ KĀŚYAPA AND THE FIRE WONDER.
Grünwedel, *Buddh. Stud.* 8, 8, Abb. 10

As an example, let us select some reliefs representing a legend that has already been brought under notice, from which the differences will be made more distinct.

Besides these reliefs, composed so as to constitute a series, each of which gives by itself a complete and self-interpreting representation, we very frequently find a blending of two or

compositions on one slab.

We treated in detail the representation of the conversion by Uruvilvā Kāśyapa as it is pictured on the reliefs of the Great Sañcī (above p. 61). The theme is also a favourite

part of the legend (the fire-miracle, conf. above p. 62) is

and compositions, therefore, take the place of the schematic representations of the period, characterized in note 1, p. 67.

also represented in detail on the relief from Gandhāra sketched in ill. 78. The disciples endeavour to quench the fire with their lō/ās filled with water, while Kāśyapa arrives leaning on his staff. Buddha stands behind him with the snake in his alms-bowl.

But this relief belongs to the detailed narrative panels, forming the upper portion of a larger slab, the under half of which is almost completely destroyed¹. The sketch of the thunderbolt-bearer on



78. GANDHĀRA RELIEF IN LAHORE MUSEUM.
 Conf. Beal, *Romantic Legend*, p. 296f.; Fergusson, *Tr. and Serp. Wor.* pl. lxx.

ill. 46 is taken from the lower part, which is very interesting in connexion with the Kāśyapa legend.

The story relates further that Kāśyapa still did not bow. Then Buddha caused the whole precincts to be flooded, and walked away over the water in presence of the Brāhmanas. Both phases of the

¹ See *Ind. Monts.* pl. 121, fig. 1. Conf. Beal, *Romantic Legend*, p. 295.

legend seem now to be employed in order to celebrate Buddha as master "over fire and water." To this belong two reliefs which are among those running continuously: ill. 79, 80. On ill. 79, Buddha is seen standing, turned slightly to the right, surrounded by laics—men and women; the bearer of the thunderbolt—in this instance, a bearded figure—follows him; water springs up before him in which stand lotus flowers. It might be doubted whether this represented the water wonder of Uruvilvā, but Buddha holds in his right hand his alms-bowl,—as the ancient sacrificing commander does the patera,—but,—owing to its derivation from a foreign type,—it is represented very small, and in it lies the snake. This proves the connexion of this relief with the Kāśyapa legend.

In relief No 80, Buddha appears between eight worshippers, facing us, with his right hand raised; water springs up under him, on which he stands. His nimbus is surrounded by flames. I believe we have here the most abbreviated form of the representation of the Uruvilvā miracle. Buddha is revered as master of the elements of fire and water.¹ It is interesting to compare this with the representation of this legend at Amarāvati. Fergusson, *Tree and Serp.* *Wor.* pl. lxx. This is still from the standpoint of the old school: there Buddha is awaiting, but is expressed by the Dharma symbol.




80. RELIEF FROM NATTHU, NEAR SANGHAO. Cole, *Proc. An. Mus.* pl. 17.

A further example of the combined panel is found in ill. 50, and the closely related one in No 81; both belong indeed to the older period when the figures were all represented of the same size. A reduced and much curtailed replica of the whole composition appears above the chief figure on the relief from Muhammad Nāri, shown in ill. 82. All three represent the leaving home of Gautama. On the first-named relief, the upper composition is much destroyed, though Gautama is seen rising from his couch; beside it stand two female figures almost completely defaced, and an armed Yavanānt. The lower composition has been more fully described above. On the small replica (ill. 82) the rising from the couch is represented in the lower composition: sleeping women sit in the corners. The upper representation, which unfortunately is injured also, shows Gautama, and under him the Mahāpāṭhavi on whose shoulders Gautama himself stood; before him, as it appears, his faithful Channa, and behind him the head of his horse Kāṇṭhaka.

Better preserved and quite distinct in all details is the relief from Jamālgarh, now in the Lahor Museum, represented in ill. 81. It gives two stages of the story, and is also specially interesting from

¹ Zettach, *d. Denk. Mon.* *Epills.* 1898, S. 460, note 1.

its architectural forms in which we find such a mixture of styles,—the alcoves panelled on the roofs in the later Græco-Roman style, the pillars with Persepolitan capitals and Indian bases, the Buddhist rail pattern of frieze, and the ornate Hellenic or Roman torus. The



81. GAUTAMA BUDDHA ABOUT TO LEAVE HOME.
Relief from Jamālgarh in Yāufāī. (Lahor Museum).

upper portion of the sculpture shows Gautama reclining on a couch, attended by women, one of whom sits on the front of the couch with her feet on a stool (*pādapīṭha*), and one behind seems to fan him, and girls are performing on musical instruments—a flat harp (such as is still used in Burma), drums, a flute, and cymbals (*idlas*); while two dancing girls (*kañchukinī*)—one on each side—beyond the pillars, shew their performances. The lower half of the slab

presents Gautama seated on the front of his wife's couch, contemplating the sleeping musicians. He then felt more disgusted, we are told, with the vanities of life, and determined to accomplish the renunciation (*abhinishkramana*). Behind the couch are two spirits,



82. RELIEF WITH BUDDHA ENTHRONED.

Found at Muhammad Nâri in Yâsufzâi. Cole, *Pr. N. Monts.* pl. 1.

one in the form of an old man, possibly Dharmachârin, who made all the sleepers contort themselves, or Lalitavyâha, who prevented all sounds from being heard. To the right and left, in niches or windows, are Yavanânîs, or Ionian female guards—two of whom are armed with spears. Above, from a balcony, the gods look down: Sûrya (the sun) to the right and Chandra (the moon) to the left of a bull, that is the sign Taurus (*Tâouri* or *Vaisâkha*). It was on Tuesday, at the full moon of Vaisâkha in the Nakshatra or asterism of Visâkha, that the legends say Gautama was born, and

this representation would agree with that date. But the conception and renunciation are both placed at full moons of *Ashāḍha* (June-July) in the Nakshatra Uttara-*Ashāḍha*, when the sun would be in Karka or Cancer, and in conjunction with Pushya (Tishya) "the king of stars."¹ The representation then seems intended to show the sun in connexion with the constellation of the Bull, perhaps between two personified "houses" of the moon in the month *Ashāḍha*: evidently the night of that month on which the moon was full was thereby intended. Perhaps this is an indication of the date when, in the artist's opinion, Gautama's flight took place; but it does not agree with the tradition, but with the date of the birth. But this is by the way. What is important here is the similarity of the whole composition to early Christian ivory tablets.

By the combination of different scenes in one relief, the old principle of composition is thus again reverted to, according to which the complete representation of the different phases of an event was related, as it were, by the repetition of the same figures. Yet, owing to regularly arranged decorative elements, the different groups remain separated. The influence of ancient art was also strong enough to preserve the prominence of the principal scene or of the chief figure, to which the others had to be subordinated. Many reliefs contain a representation of Buddha as principal figure enthroned in the centre, and on the left, on a smaller scale, stand servants or worshippers; and smaller compositions, often only rows of figures, are found under and above the central group. Among the reliefs from the monasteries of Gandhāra are semi-circular pediments containing a principal scene below, and two concentric arches over it, filled with smaller figures (Ill. 58, 84). One of the most richly carved of these pieces in the Calcutta Museum is a pediment slab from Loryān Tangai (fig 83), measuring 3 feet wide by about 25 inches high,—a portion having been broken from the top. On the capitals of pillars that appear at each side sit Devas adoring the Buddha who occupies the centre. In a band just inside the outer moulding of the arch are figures, perhaps also of Devas, one above another; within this is a torus covered with leaf or scale ornament, and inside this again two arches divide the area into a lower semi-circular and two upper lunulate spaces. The narrow ends of the lunular areas are occupied by dragons or Nāgas having snake bodies, fish tails, wings, forefeet, and human busts. Above them are human or divine figures worshipping Buddha enthroned at the apex of each arch. In the scene below, Buddha sits under

¹ The *Lalitā Vistara* in one place (pp. 54-55) fixes the conception at the full moon of *Vaiśākha*, in the nakshatra *Vaiśākha*, and "when in conjunction with Pushya"; but Pushya (6 Cancri) being scarcely 70° east of Taurus, the full moon must have been fully seven hours behind it; and if the conception were not in *Ashāḍha*, the birth could not have been in *Vaiśākha*, as is always stated. Conf. S. Hardy, *Man. Buddh.* pp. 144, 149, 163, *Lal. Vist.* pp. 26, 74, 185, 191, 193; Kern, *Man. Buddh.* pp. 13n., 17. —J.B.

a canopy and preaches his Law to a group of females on his right and males on his left, while figures (Devas?) look down from balconies above on each side. Buddha in the Tushita heavens,



88. RELIEF FROM LORYÁN TANGAI. In the Indian Museum, Calcutta.

whither he is said to have gone to teach and convert his mother, may be suggested by this scene: but the identification is altogether uncertain.

* Terraces are also occasionally carved to separate the different parts of a relief, and then the whole scene reminds one of a festa procession marching through a crowded street in which the cult picture is shown as stationary or is being carried along. The Chinese pilgrims describe such festivals in which the faithful upon the roof

terraces showered down wreaths of flowers upon the great idols.¹

The construction of the sacellum in the temple, with the image of Buddha in the middle and the ornamental reliefs round about, provided another model for these compositions. The stelés, in the centre of which Buddha stands or sits, are then much reduced; beside him are disciples and monks: above rises a pointed arch, in which a conversion-scene—as replica of some much employed composition—is represented (ill. 84).² Pillars—before which stand followers of Buddha, or groups reduced from larger compositions—make a complete whole of the slab.

It is very interesting to find that this kind of stelé composition is still stereotyped in the style of the reliefs, and especially of the pictures of Tibetan ecclesiastical art and of the Buddhist school of Japan. This is most strikingly shown by a comparison of ill. 82 with the modern Tibetan picture from Nga-ri-Khor-sum (ill. 85): the connection is very striking. At any rate, the transitions mentioned prove once more in regard to this that in the main the Gāndhāra sculptures dominate the art of northern Buddhism, so that we may justly hope that an acquaintance with the iconography



84. STELÉ FROM JAMALGIRI
From a sculpture in S. Kensington Museum.
From Fergusson and Burgess, *Cave Temples*.
p. 128.

¹ The splendour of these ancient feasts, as well as many characteristic features still to be found in Tibet, Mongolia, and especially in Siam and Japan even in modern times, shows that Buddhist pessimism cannot have been so very terrible; we might just as well speak of Buddhist optimism. Conf. A. Pfungst, *Ein deutscher Buddhist*, S. 43.

² The illustration affords a characteristic example of this class of reliefs. These stelés have been taken to be conventional representations of the fronts of cells or small shrines. This may be so; but they seem to have been employed decoratively as pediments of a sort. The lower scene in fig. 84 presents Buddha addressing a kneeling figure with two attendants. On Buddha's right is Sakra with the *vajra* and behind him a figure in reverential attitude, while above are four Devas throwing down flowers. The middle is occupied by Buddha teaching, seated under a square canopy—an unusual form,—with two attendants,—perhaps Devas,—and worshipped by three figures on each side and Devas above. The third storey also represents Buddha and attendants; and above all is the *Pātra* or alms-bowl worshipped by the Nāgas.—J.B.

of this modern school may provide valuable material for the explanation of the old Gāndhāra reliefs.



85. THE BOGDHISATVA JAMBA (Byams-pa) MATREYA.

Modern Tibetan picture from Nga-ri-Khor-sum

Original in Berlin Museum.

The decorative elements which serve as framework or border to the reliefs contain a series of figured and purely ornamental forms of very varied origin. Along with such as have been borrowed from the older Buddhist art, appear quite a number of antique motifs. It is impossible to examine these individually; therefore only the most noteworthy will be mentioned. The giganto-machia relief published by Vincent Smith is only a reproduction of a Greek motif, but it is also a unique example.¹ A giant, seen from behind, similar to the one in the Zeus group from Pergamon, threatens with his club a naked man, who with his right hand tears at the left snake-foot of the giant. These snake-feet are

¹ *J. As. Soc. Beng.* vol. I, III, pt. 5, p. 1817, and pl. ix, 4; Anderson, *Ar. Cat. Ind. Mus.* pt. i, p. 240; and *Ind. Mus.* pt. 102, 6.

so coarsely executed that they look almost like fish-tails. Smith was the first to give the correct explanation, and he is of opinion that the fame of the great work at Pergamon may easily have led to some small replicas, of which an example came to Gandhāra. The crouching Atlases (otherwise Garudas, see above, p. 52) are likewise purely antique. (The Royal Museum at Berlin possesses a fine example of these) They serve as supports to the beams; on the relief from Muhammad Nāri shown in ill. 82; they appear,—even furnished with wings,—beneath the slender pillars which are partly of an older order. It is a favourite feature, as has been already mentioned, to set before the broad pillars and columns which border the reliefs, a figure of Buddha alone, or flanked by upright forms of worshippers,—as a curtailment of a larger relief,—or a single worshipping figure, and so on. Of quite special interest is the figure



86. BUDDHA'S BIRTH IN THE LUMBINI GROVE
Māyā and Prajāpati before Brahmā and Sakra
From a Gandhāra relief in Lahor Museum.

employed as a pillar ornament in ill. 86:—the Ram-bearer, the Kriophoros. It is, perhaps, more than a strange coincidence that this Hermes representation (which, in ancient Christian art, was adopted as a symbol of the Good Shepherd) appears on a Buddhist monument and in evident reference to the founder of Buddhism. Smith's attention has been chiefly drawn to the contact that has taken place with Christian art. If one compares with the Ram-bearer the statue of the Good Shepherd in the Christian Museum of the Lateran (conf. Spencer Northcote, *Roma Subterranea*, p. 299)

one cannot fail to remark a certain resemblance. The clothing is the same, and among the Gāndhāra sculptures known to me it nowhere else appears.

What the figure carries, however, cannot be quite made out. We may perhaps derive a hint from a sculpture in the Lahor Museum of a man pouring out what may be meant to represent money at the feet of a seated figure, as described by Dr. J. Burgess (*Four. Ind. Art and In.* vol. VIII, pl. 14, 3, and p. 37; or sep. ed. pl. 12, 3, and p. 15).

It is the so-called "tribute bearer" of the late antique art, so often appearing on ivory diptychs, which we must so generally draw upon as important parallels for the explication of our Gāndhāra sculptures.¹ At Ajantā also the "tribute bearer" is employed decoratively (ill. 87).



87. REPRESENTATION OF "TRIBUTE-BEARERS,"
from Ajantā.

The representation of the tribute-bearers brings us to the so-called world-protectors. In Bauddha mythology, the mountain Meru, in the centre of the universe, is guarded by four "heroic like" kings of the demons. These are:—Kubera, Kuvera, or Vaisravana, also called Dhanada, Dhanapati, Yaksha-rāja, &c., the Hindū Plutus or god of wealth; he is regent of the north, and his attributes are—a pike with a flag, and a rat or mungoose that vomits jewels; his colour yellow;—Virūdhaka, the ruler of the south and chief of the Kumbhāndas, his attributes being a helmet of the skin of an elephant's head and a long sword, his colour is green;—Virūpāksha, the red king of the west and ruler of the Nāgas, whose attributes are a jewel and snake; and Dhṛitarāshṭra, the white guardian of the east and ruler of the Gandharvas, whose attribute is a mandoline.²

In the Lahor Museum is a sculpture, referred to above, which perhaps represents Kubera (*Four. Ind. Art, &c.* vol. VIII, pl. 14, 3, and p. 37). It presents a king sitting on a throne, wearing a richly ornamented turban; beside him is a smaller figure—a Yaksha. Further, at his feet is the tribute-bearer, who is emptying out a bag

¹ Conf. Duryu-Hertberg, *Gesch. d. römischen Kaiserreiche*, Bd V, S. 409. So far as the correlation between Christian and Indian art is concerned, I can only indicate some of the modes in which the Indian may have influenced the Christian: first of all, the "folded hands" already noticed by Curtius (*Archdol. Zeit. N.F.* Bd. VIII, Ss 90ff.) and the Indian *aśvini*, must be mentioned; the lions of St Barlaam, Buddha's *simhāsana*; St. John's cup with the snake, the alms-bowl with the Nāga in Buddha's hand,—are matters I can only mention in passing.

² In China these Caturmahārājas, or four great kings, are placed as guardians at the temple gates. In Japan they are respectively:—Bishamon, holding a club in his right hand and a chakra-shaped gasket in his left, with his feet on two demons; Zōchō-tennō, seated on a dragon, and holding a scroll and brush; Kōmoku, holding a *vajra* with three points, and sitting on a demon; and Jō-keku, also seated on a demon.—J.B.

of gold. This sack with the gold rolling out, is replaced, in modern pictures, by the rat, or rather ichneumon or mungoose (Sansk. *nakula*; Hind. *ne-valā*; Tib. *neu-le*).

The reason for this we know not.¹ Kubera is by far the most prominent of the Lokapālas: in Japan he is placed among the seven deities of fortune. Even in the Asoka period he is represented; and at Barāhat he is named in the epigraph to a statue on a gate-pillar, as a guard-ian Yaksha. (Cunningham, *Bharhut*, pl. xxii).

Another sculpture, represented by Burgess, has also been identified as a Lokapāla (*ib.* Pl. 13, fig. 1, and pp. 31, 37). It is in the British Museum and is about 18 inches in height, but somewhat damaged. The principal figure wears a richly jewelled turban after the Rājput style, and holds a pike in his left hand; the right hand is gone. His right foot rests on the regal footstool, and a small figure stands by each knee. On the base one attendant,



88. THE SO-CALLED INDO-SETTHIAN KING.
From a cast in the S. Kensington Museum and in the
Mus. f. Völkerkunde, Berlin.

¹ If the Gallic divinity represented by Duruy-Hertzberg, *Gesch. des römischen Kaiserreiches*, Bd. I, S. 148, is to be depended upon, we have the same motif before us. The god sits between Hermes and Apollo, with legs crossed in Indian fashion; from a sack he shakes out what appear to be beech nuts before a couple of stags; on the gable above him is a rat! Conf. the explanation of A. Foucher, *Rev. de l'Hist. d. Rel.* tome XXX, p. 306f; and see *Globe*, 18 Mar. 1899, Ss. 169ff.

in the middle, sits on an animal; another, on the left, presents some offering; to the right, one addresses the figure in the middle; and a female kneels behind in a precatory attitude.



89 REPRESENTATION OF P'AGS-SKYES-PO, Virūdhaka.¹

With this we may compare a figure at Lahor (ill 88), which is usually described as an Indo-Skythian king. Two things here are of special interest:—1. The little attendant figures which surround the chief one. This is a peculiarity of the declining antique, which represents the portraits of emperors as larger than the surrounding soldiers, servants, and tribute-bearers; 2 The portrait-like character of the heads of the figures described. Could actual kings have been represented as Lokapālas?

If it is probable that we have here a figure of Kubera,

then it is manifestly useless to seek to identify the others.



90. COIN OF DEMETRIOS, son of Euthydemos.²

Only Virūdhaka, king of the south, is remarkable because of his attribute, wearing, as above pointed out, the skin of an elephant's head over his scalp (ill. 89). In this, moreover, he has a very remarkable Hellenic counterpart in Demetrios, son of Euthydemos I, who is represented on his coins³ with just such a head-covering;—a distinction possibly referring back to the heroic deeds attributed to Alexander the Great (ill. 90).

Miscellaneous Sculptures.

Before passing from these reliefs a few other sculptures from Gandhāra may be here noticed. The two illustrations 7 and 40 are of sculptures from Swāt and evidently have belonged to the same monu-

¹ From an original Peking Lamaist miniature on silk in the Berlin Museum für Völkerkunde. Conf. *Originalausstellungen aus dem Egt. Mus. f. Völkerk.* Bd. V, S. 110.

² Coins play an important part in the development of the north Buddhist types. Notice, for example, the derivation of the Siva type from the ancient Poseidon (conf. Gebelin d'Alviella, *Ce que l'Inde doit à la Grèce*, p. 80; and F. Gardner, *Catalogue Ind. Coins, Greek, &c.*; *Kunst*, pl. v, 1); the same type meets us in the bronze from Khotan in *Forschungen in Zentralasien*, p. 864, pl. xi, 8. The victorious emperor represented in ill. 32 is likewise a coin-type; the Paravati type in ill. 56 also appears on Gupta coins (V. A. Smith). Conf. *Gedächtnis-Münz*, 1890, S. 169 ff.

³ Conf. *Gedächtnis-Münz*, *Col. of Ind. Coins*, 1890, pl. ii, 9-12.

ment and to the same frieze or dado. The Corinthian pillars sunk into the dividing spaces at the ends of the panels are identical. The individualization of the faces is particularly marked. In fig. 7 the central figure is a royal personage seated upon a throne with a very antique style of back. Overhead is a large canopy hung with tassels; below is a footstool; and at each end of the throne stand *chauri* bearers,—the face of one of them being destroyed. In front, at each side are two persons, seated on what seem to be cushioned stools carved with considerable care. Each holds a round bottle or vessel with his left hand; and the one on the king's left, who is the older, raises his hand in addressing him. This scene naturally suggests the story of the Brāhmana explaining to Suddhodana the dream of Māyā previous to the birth of Gautama, or perhaps the omens after his birth.¹

Ill. 40 represents separately the second part of the scene in ill. 64, or the seven steps (*vaptapaddni*) taken by the new-born Bodhisattva. Here the gods only are represented as present. Satakratu or Sakka, the legend says, had dispersed the attendants by a storm of wind and rain; and here he stands on the infant Gautama's left, clad much as a Brāhmana, with a high turban and holding the *vajra*² in his right hand. Brahmā, bearded, with his hair in a *jatā* and with the *kamundalu* or ascetic's water vessel, stands on his right. Other Devas appear behind, and a canopy is held over the infant, who alone has the nimbus. In the relief, fig. 64, the infant Buddha is represented pointing with the right hand up to heaven and with the left to the earth, in sign of taking possession of the world. This is the legendary attitude still preserved in China and Japan.³



91. ASITA AND BUDDHA.
Ajantā wall-painting in
Cave XVI.

Connected with the scenes from the infancy of Gautama we might expect the incident of the visit of the ascetic or *Rishi* Asita to Suddhodana; and among the wall-paintings at Ajantā was one on the right side of Cave XVI which was long pointed out as representing the old hermit⁴ holding the child in his hands (ill. 91). Unfortunately, this and neighbour-

¹ Rhys Davids, *Buddh. Birth Stories*, p. 68; Bigandet, *Leg. of Gautama*, vol. I, pp. 29f.; Beal, *To-sho-king-tsan-king*, in *Sac. Bks. East*, vol. XIX, p. 8.

² In these Gāndhāra sculptures the *vajra* is not forked at the ends, as is usual in Nepal, Tibet, &c. The *vajra* with single-pointed ends is still in use in Japan, and known as the *da-kō*, as distinguished from the *san-kō*—with three prongs, and the *go-kō*—having five points.

³ See a bronze figure of Tanjō Shaka (the infant Śākya) in the Musée Guimet.—*Petit Guide ill.* (1897) pp. 196, 198. In Tibet called *lha'debs*, 'the god who came down.'

⁴ Burgess, *Notes on Bauddha Rock Temples at Ajantā*, p. 60; *Rock Temples*, p. 308. Conf. J. Muir in *Ind. Ant.* vol. VII, pp. 282f.; Beal, *Rev. Leg. of Buddha*, pp. 66f.; Griffiths, *Paintings of Ajantā*, vol. I, pl. 45; and Mrs. Speir's *Life in Anc. India*, pp. 248-257. With this picture compare the sculpture of Sileus and the infant Bacchus, in the Louvre Museum: Seemann, *Die Götter und Helden*, p. 187.

ing scenes were ruined by natives about the time Mr. Griffiths was copying these paintings.

Still another of the infancy stories is given on the lower part of the panel figured in ill. 92. This may be compared with a small



92. BATHING THE INFANT GAUTAMA, &c.
From a photograph of a relief from Swāt.

relief, about 8 inches by 4, in the British Museum, probably from Sikri,¹ which represents the child taken to the Vimalavyūha garden to be decked with the royal jewellery, of which event we have so detailed an account in the ninth chapter of the *Lalitavistara*: "All the gems on his person were lost as the glow-worm's spark in the light of day."² Two attendants here pour water on his head to bathe him: this service is ascribed to the gods immediately after his birth. Two nurses hold him or put on the ornaments; and two Devas behind them pay reverence with joined hands. Above this is another compartment re-

presenting two bare-headed figures, the front one with nimbus and krobylos—almost certainly Buddha,—meeting four others wearing turbans, differently dressed and perhaps bearing presents,—the first of whom Buddha converses with.

For comparison with the figures 67 and 68,—the latter in the Berlin Museum—we may here add a representation of a remarkable relief from Swāt (ill. 93). It presents Buddha addressing an ascetic Brāhmaṇa, sitting in his *pāṇsāla* or leaf hut, while behind the former stands Sakka as his protecting genius, in his usual scanty clothing and abundant hair, clasping his mace or *vajra* in his right hand. The meeting here might suggest that with Gayā Kāśyapa; but the absence of any indication of what neighbouring reliefs may have represented prevents any certain identification. Possibly this is from the same place as fig. 40.

In the Indian Museum at Calcutta is a fine relief from the Loriyan Tangai stūpa. The subject is the visit of Indra to Śākya Simha at

¹ *Jour. L. Art and Arch.*, vol. VIII, pp. 85, 76, and pl. 10, fig. 2.

² *Monum. de L'Inde*, vol. I, pp. 1192; and *Beal, Buddhist Legend*, pp. 84-85.

the Indrasaila hill (ill. 94). It is on a slab 3 feet 10 inches high by 2 feet 8 inches wide, and represents the scene in a much more developed form than as it appears elsewhere, in an archaic style,—on an



98 BUDDHA AND ASCETIC BRĀHMANA
Relief from Swāt; from a photograph

inscribed fragment from Barāhat, on the north gateway at Sāñchi, at Gayā, and in another sculpture, in the Calcutta Museum, from Mathurā.¹ A comparison of these versions is very instructive as helping us to trace the influence of the original Hindu conceptions on the Gāndhāra art, which took over the models and modified them according to a higher artistic standard. The story of Indra desiring to reverence Buddha at Indrasaila hill is well known,² and the Barāhat sculpture is labelled as "Indasālaguha." The Swāt sculpture represents the visit of Sakra and his retinue, with the Gandharva harper Pañchasikha, to the Buddha whilst he was living in the Indrasailaguhā—a cave near Buddha-Gayā. The entrance of the cave is surrounded by flames to represent the glory of the Teacher "replendent with a halo of many colours, proceeding to a fathom's length all round his person." Above and below,

¹ The Loryān Tanga sculpture has been noticed, along with the others, by Dr Th. Bloch in the *Proc. A. S. Benq* (1898), pp 186f. See also Cunningham, *Bharhut*, pl. xxviii, 4, and p. 88, *Mahābodhi*, pl viii, 6; Fergusson, *T. and Ser. Wor.* pl xxix, 1, and p. 138, *Ind. Mon.* pl 80, 1; and Anderson, *Arch. Coll. Ind. Mus.*, pt. i, p. 182; S. Hardy, *Mag. Buddh.* pp. 298f.

² Beal, *Si-yu-ki*, vol. II, p. 180; *Trav. of Fa-hsien*, p. 110; *Foe-kong-ki*, pp. 282-8; S. Hardy, *Man. Buddh.* pp. 298f., conf. Rlys Davids, *Buddh. Birth Stories*, p. 125.

the birds, beasts, and trees indicate the isolation of the place. Indra appears as a royal personage on the right, doing reverence to the ascetic, with his parasol-bearer close behind, and the Devas of his train beyond on both sides. His peculiar crown or headdress



91. BUDDHA VISITED BY SAKKA AT THE INDRAŚAILA CAVE.
A sculpture from Loryān Tangai in the Calcutta Museum.

is very similar to what we find also in the Mathurā sculpture. The figure of the Gandhārva musician, on the other side, has been much damaged by the fracture of the stone, but his harp is still visible. This sculpture may well be ascribed to the best period of Gandhāra art.

Among the Jātaka representations, perhaps the favourite is that of Sumedha or Megha, who lived in the age of Dīpankara Buddha,

the twenty-fourth predecessor of Gautama. The legend tells how Megha, the disciple of Ratna (*i.e.* of Maitreya Bodhisattva in a previous birth), obtains from Bhadrā, a water-girl, some stalks of the Utpala flower, or blue lotus, she has secured to present to Dīpaṅkara; these he throws into the air over the Buddha's head, and then places his deer-skin covering in a muddy place, unrolling his long hair for Dīpaṅkara to pass over, and so obtains his wish—that in a future age he shall be Sākya Muni, and in intermediate births Bhadrā shall be his wife. Megha then ascended into the air and did reverence to Buddha. In two sculptures, one in the British Museum (17 inches by 16) and the other at Lahor, we have most of the details. In the first, Megha



95. DĪPAṆKARA BUDDHA AND MEGHA.
From a wall relief in Cave XXXV at Kanheri.
Arch. Sur. West. Ind., vol. IV, p. 86.

or Sumedha is represented a second time, on a plaque in the air, worshipping the Buddha. Among the Mahāyāna sculptures in the Kanheri caves also, we find the same scene represented (ill. 95),—Bhadrā with her *lotā* and flowers; Sumedha throwing his flowers up, which remain in the air, over Dīpaṅkara; and then prostrating himself with his *jatā* unrolled at the feet of the Buddha.¹

One of the favourite subjects of Buddhist art was the first sermon in the Deer-park (*Mṛigadāva*) at Isipatana in the vicinity of Banāras.² "To listen to the first proclaiming of the law, evening—

¹ Conf. *Arch. Sur. W. Ind.* vol. IV, p. 86. For the story see *J. R. As. Soc.* vol. VI (1878), pp. 383ff. The southern version is given by Rhys Davids, *Bud. Birth Stories*, pp. 8-28, where the future Buddha is called Sumedha. For other examples, in the Calcutta and Lahor Museums, see *Ind. Monstr.* pl. 101, 114 (6), 140, and 147; *Jour. Ind. Art, &c.* vol. VIII, pl. 11, figs. 1, 2, and p. 86.

² The four sacred places to which pilgrimages were to be made by pious Buddhists were.—the scene of Buddha's birth or the Lumbini garden; the place of his enlightenment or the Vajrāsana at Buddha-Gayā; the place where he first preached his *Dharma*

like a lovely female—came, the various beings in the world all assembled, that they might receive the ambrosia and nectar of Nirvāṇa” Then “Buddha opened his mouth and preached the



96 THE FIRST SERMON AT BILVAPAS.
A relief from Swāt, in the Indian Museum, Calcutta

Dharmachakra Sūtra," and the "oldest of the five ascetics, Kaundinya, entered the first path, as did an *asaṅkhyā* of Devas &c." The illustration fig 96, is on a relief from Swāt, on a panel measuring 27 inches wide by 16 in height. In this large group at Isipatana, and the place, near Kusinagara, where he passed away "in that utter peace which leaves nothing whatever behind." Hence these four scenes are especially among the most frequent subjects of representation in the sculptures. Conf. *Radāsook Sūtra*, in *Sac. Bkr. of the East*, vol. XI, pp. 80, 155.

some faces are injured as well as the rich floral cornice, but the scene is, as a whole, animated and artistic. We have here the five ascetics seated listening to Buddha; the deer below his seat indicate the place, the pillar between them supports the *trisula* and wheel representative of the religious law (*dharma*), and behind appear the representatives of the Devas some throwing down flowers on the Teacher. On his left we cannot fail to recognise




97 WASHING THE MASTER'S FEET
A Gandhara relief in Lahore Museum

his constant attendant Sakra with a large carefully moulded head, distinguished by the beard and moustache.

The story relates that when Siddhârtha arrived at Isipatana the

five ascetics who resided there "were compelled to come before him and worship. They afterwards washed his feet, and enquired familiarly about his health, but Gautama informed them that they must not address him as an equal: he was now a supreme Buddha." The somewhat inferior relief, ill 97, apparently represents this part of the story, or some similar scene.

The next illustration (fig 98) may naturally be supposed to represent the sequel of the attainment of supreme knowledge (*bodhi*). The first food offered him after his temptation was by two merchants and consisted of honey and wheat. But Gautama reflecting



98. SUPPOSED PRESENTATION OF BUDDHA'S PĀTRA.
A Gaudhara sculpture in Lahor Museum.

that he must have an alms-bowl (*pātra*), the four Mahārājas each brought one of gold, which he refused; then they brought silver, emerald and ruby dishes, which were also refused; lastly, each brought an earthenware bowl, and Buddha "causing them to unite in one (lest there should be jealousy), accepted the one from all." The legend of the *pātra* is a long one: it is now said to be kept in Sāgara's palace at the bottom of the sea, but on the advent of Maitreya, it will divide into the original four, each of which is to be guarded by a Mahārāja, as it is the palladium of Buddhism.

One other sculpture may be referred to, as of quite remarkable character among these reliefs. It is on a small slab in the British Museum, about 16 inches long by 6½ high (see *Four. Indian Art*

and *Industry*, vol. VIII, pl. 17, fig 1). With a quasi-Corinthian pillar at the right end, it represents six men, carved with unusual life, bareheaded, with beards and moustaches, very muscular, and with boots or thick socks; but what serves as clothing reminds us of the Roman military tunica or kilt, growing down from their waists, as if parts of themselves. Each carries a spade or shovel over his left shoulder, except the left one who leans on his; and the second from the right carries some round object (a skull?) in his right hand. Nothing of Indian origin resembles this unique relief.—J.B.

A. Foucher has remarked (*Rev. de l'Hist. des Relig.* tome XXX, p. 359) that I have failed to point out in my account of the Gāndhāra sculptures, that the entire development of this period of art belongs to the Mahāyāna school. I had, however, taken in hand to treat the art forms independently of, and uninfluenced by the religious and theoretical development, whilst I favoured the opinion that the monuments must be examined, first of all without, and unconfined by, any fixed religious system. The forms of art, moreover, give so much of which the texts know nothing, and they can help us to nothing; while the texts themselves only become intelligible by access to the forms. The saying that art speaks her own language is just as true in Indian archæology as in western. But, it cannot be denied that just the consideration of the decisive word "Mahāyāna" would have had certain advantages. My chief object was to demonstrate that the Gāndhāra period was really the mother of all later Buddhist (as well as Brāhmanical) creations in art; that a definite history might actually be established on this basis, which would also rectify the history of international influences and the modifications of the interpretations that Buddhist monuments have undergone through other religions.

Now, in China, the four protectors of the world, along with the so-called "fat-bellied Buddha," or Ho-shang "with the sack," represent a pentad, which are so arranged in the entrance halls that the four protectors (Chaturmahārājas) hold the four corners of the hall while Pu-tai Ho-shang sits in the middle.


Ho-shang is the representative of the Mahāyāna system, thus it occurs that the peculiarities characterizing the old Mahāyāna art, i.e. the Gāndhāra school, have been applied to him. Further, it strikes one, that the figures of children, which surround Ho-shang, are the survivals of the diminutive attendants in the late antique model, and that his bare stomach, which has earned for him the European epithet of "fat-bellied," goes back to the peculiar arrangement of the robe, as shown in our accepted Gāndhāra Lokapālas. The peculiarity of his dress, which, according to eastern Asiatic ideas, borders on the indecent, tended to make the figure ridiculous and gave rise to those entertaining caricatures in which the Japanese especially excel, and among which the seven gods of fortune¹ and

¹ Ho-tei (the Chinese Pu-tai, "calico bag," Ho-shang, "priest" or "monk"), commonly known as Mi-lé P'usa, was a Chinese priest under the Liang dynasty, (A.D. 502-557), who is regarded as an incarnation of Maitreya; he is always represented as

even Ho-tei appear. The hemp sack of our fat monk is then perhaps the sack of our ancient "tribute-bearer."

These last remarks are to be regarded as purely hypothetical, and merely a suggestion which may possibly contain a grain of truth about things which are so entirely puzzling.

If we pause at the numerous little decorative figures from Gandhāra, an aspect of late antique art is there presented to us which perhaps accompanies the types above spoken of, the Pygmies,—the



99. PART OF A FRIEZE
From Loryan Tangai.

little cupids,—that appear with or without wings. They are represented on string courses, plinths or friezes, as boyish figures carrying garlands or playing between garlands, climbing, wrestling, or performing on (Indian?) musical instruments. In the intervening portions the old lotus-flowers, which remind one of palms, are again introduced, or the intervals are filled

in with symbols, animals, or birds. The ancient classic garland was, it appears, quite incomprehensible to the Indian: it resolved itself into roll-ornaments resembling snakes (ill. 99, 100). On the sculptures of the Amarāvati rails these garland-bearers belong to those elements which bear evidence to the influence of the Gandhāra



100. RELIEF WITH GARLAND-BEARING BOYS.
From Swāt. Original in Mus. I. Völkerkunde, Berlin

school. The boys at play have turned into men who, bearing huge snake-like bodies, advance in studied and graceful attitudes (ill. 101). The heads of the dragons (they are evidently intended to be placed one beside the other), which grasp the ends of the

garland, are the heads of the dragons. Edkins, *Chin. Buddh.* p. 148; *Cat. de Mus. Guizot*, p. 246; *Ann. Mus. Guizot*, (1898), p. 246. The seven gods of fortune (Vajrasana at Kabara), Dai-koku, Ho-tei, and the other gods, are an eclectic series.

bodies in a curious way, present the antique appearance of the dragons' heads on the chair-backs described above (conf. ill. 8)

Among the pairs of dallying figures in the borders of many Gāndhāra reliefs (*Four Ind. Art, &c.*, vol VIII, pl. 7, figs 2, 3) groups of gods and goddesses occur whose erotic excesses are a development of the ancient nude;—compare the copies in Burgess, *Cave Temples*, pl. xx, xlii, xlv, xlvii.

The bases and pedestals of statues are largely used for decorative sculptures. These are very varied,—worshippers before a lamp, the Nirvāṇa scene, figures of Buddhas and Bodhisattvas with attendants, &c.—and it is often hard to see what relation, if any, exists between the decorative scene and the principal image (see ill. 82).¹ The ill. 102 represents one of these bases in the Lahore Museum, the figure it supported is now unknown, but this pedestal is decorated with sculpture that we should hardly associate with a highly ethical religious cult. It represents some Bacchanalian orgy, and might recall the appearance of some

Roman sarcophagus, with its lion's head and claws; even the men on whose knees the women are seated look more like Romans than

¹ See *Jour. Ind. Art, &c.*, pl. 3, fig. 1; pl. 8, 2; pl. 9, 1; pl. 18, 4 and 5; pl. 28, 7; *Ind. Monte.* pl. 83, 86, 88, 112, 145.



101. RELIEF ON A RAIL COPING FROM AMARĀVATI. Men carrying a great snake roll. Ferguson, *Tree and Serp. Work.* pl. lv.

Oriental, while the women wear the usual heavy Hindû anklets.¹ Again, the fronts of the steps on the stairs leading up to stūpas or



102. PEDISTAL OF A GĀNDHARĀ SCULPTURE; AN ORGY. Original in Labor Museum.

shrines were elaborately decorated with sculptured reliefs. This at least was the case with fronts of the sixteen steps ascending to the stūpa at Jamālgarhī, considerable portions of which are now in the British Museum. They vary in height from about $4\frac{1}{2}$ to $5\frac{1}{2}$ inches, and the reliefs on them seem mostly to represent Jātaka scenes, among which General Cunningham identified certain episodes² of the *Sāma* and *Visvantara* or *Wessantara-Jātakas*. But others are of a more convivial character. The illustration 103 seems to picture "a vintage scene, in which," as Mr. Kipling remarks,³ "boys, leopards, a scene of dalliance, Bacchus on a leopard, and the wine-press of Europe (unknown in India, but common in Persia), are framed in a distinctly Byzantine arrangement of the grapevine." Both of these

examples are evidently strongly influenced by Western ideas.—J.B.

¹ J. L. Kipling in *Jour. R. I. Br. Arch.*, vol. I (1894), p. 188, from which illustrations 102 and 103 are borrowed.

² Cunningham, *Rep. Arch. Surv. Ind.*, vol. V, pp. 1897; *Eng. Mon.*, pl. 151; conf. Sp. Hardy, *Arch. Monuments*, p. 275; and *Mon. Surv.*, pp. 1187; Beal, *Fak-hian*, p. 104; *Jātakas*, No. 540; *J. R. As. Soc.*, vol. V (1870), p. 107; Burnouf, *Lotus*, p. 411; Upham, *Hist. Budd.*, vol. III, pt. 2, and Y. Fergusson, *Trees and Scap. Wor.*, p. 126.

³ *Jour. R. I. Br. Arch.*, vol. I, p. 188.

The wheel symbol, mentioned above pp. 68, 145, with or without the trident upon it, representing the doctrine of Buddha, belongs also to the decorative elements which the Gāndhāra sculptures have in common with other Indian ones. This wheel—which with two couchant gazelles beside it, has become, we may say, a hieroglyph for the first sermon in the deer-park at Bārānasi,—appears in compositions full of figures, in front of the preaching Buddha, as a presentation of the phrase: *dharmachakkam pavattesi*,—"he turned the wheel of the sacred doctrine." This representation is still continued in the northern school; in modern pictures it almost looks like a sort of monstrance or pyx. Indeed, the custom prevailing in the northern school of setting in motion a cylinder filled with printed or written prayers, instead of repeating them orally,—the so-called *Ch'oskor*: *dharmachakra*, "wheel of the law," can hardly be other than a materialized putting into practice of the old symbolical representation which was quite as current in the sculptures of Peshāwar, as in those of the Asoka period (conf. ill. 96).

The architectural elements which are employed in the decoration of the reliefs likewise still show in part the older Perso-Indian forms (conf. ill. 81, 82); above them rise the terraces with round dormer-windows disposed according to the old Indian pattern, as on the reliefs of Barāhat, Sāñchī, &c., but with more members. Little attention has been paid to the strength of these, often very slender, pillars: the crowded bell-capitals of the older art have become thin and light; new forms have even been given to the animal figures represented on the capital. In ill. 82 the zebu has become a kind of goat. The pillar itself, on which a double terrace rests, is placed on the backs of crouching figures with wings. It is exactly the same absurd combination as is found in Byzantine art, which placed pillars on bodies of animals or of winged creatures; and a like practice was long continued also in Dravidian architecture.

Along with these Perso-Indian elements which still appear, partly modified, in Gāndhāra, we have western forms of pillars and columns. Frequently pillars of the later Corinthian type are represented on

108 VITRAGE SCENE FROM A GANDHARA SCULPTURE. Original in Lahore Museum.



one and the same relief along with Perso-Indian zebu-pillars. This is seen in ill. 82; beside the Buddha-figure in the centre, stand the Perso-Indian, outside the Hellenic. Variations of this Corinthian order are employed, almost as on the façades of modern buildings, merely for decorative purposes. V. Smith is right when he points out that the circumstance that these forms,—so completely different from the Perso-Indian pillars, represented beside them,—forbid us speaking of a Romo-Corinthian order in a strictly technical architectural sense. The question of the nature of the architectural employment of the Indo-Corinthian pillars, however, is beyond the scope of this work.

A glance at the Gāndhāra panels represented in this book will show that for decorative purposes and the representation of buildings, pillars and other architectural forms of the Perso-Indian and Indian styles were employed side by side, sometimes on the same slab, with columns having Hellenic capitals and bases. Structurally the architecture of the same age may have shared in this hybrid character, but we have not much evidence to guide us to a determination; a stūpa such as the best preserved at Alī Masjid,¹ for example, can supply but little aid in recovering the features of temples and structures for occupation. What we see pictured in



104. CORINTHIAN CAPITAL FROM JAMĀLGARHĪ.
Fergusson, Ind. and Eastn. Archit. p. 173.

the sculptures, combined with the cave architecture of about the same age, must be our chief guide. But while the question cannot here be entered upon in detail, the singularly rich capitals found at Jamālgarhī and elsewhere in the Peshāwar valley can hardly be overlooked when speaking of the art of Gandhāra. Numerous examples exist in the Lahor, Calcutta, and British Museums.² The capital given in ill. 104, from Jamālgarhī, measures 35 inches across

¹ *Conf. Simpson, Trans. R. I. R. Arch. 1880, p. 55 and pl.; ibid., 1891, pp. 341, &c.; Fergusson, Ind. and Eastn. Arch. pp. 173f.*

² *Ind. Monr. pl. 73-74, and 108-111; Cunningham, Ar. Surv. Ind. Rep. vol. V, pl. xlvi-l.*

on the top, the lower section being 6 inches thick, and the upper 8 inches. It will be noted that the leafage is not of the classical acanthus, but more like one of the palms similarly treated: it is an imitation with divergencies,—not a strict copy. Then on one face, both of this and of the capital given on ill 105, as well as on others, there appears among the foliage a small figure of Buddha, standing or seated. These figures have been regarded as a possible indication of age. The first prominent example of this practice, in classical art, as Mr. Fergusson pointed out,¹ seems to be found in the Baths of Caracalla at Rome (cir 215 A.D.), but before such a feature was applied in an imperial work, it had doubtless been previously used elsewhere. And, in fact, we find a Nikê introduced



105. INDO-CORINTHIAN CAPITAL FROM LOMIYI IN TANAWAL.
Original in Ind. Mus., Calcutta.

among the acanthus leaves on the Corinthian capitals of the antæ of the temple of Augustus, built by Greek artists at Ancyra about A.D. 10; and another example is found on the capitals at Priene. These are of earlier date than the sculptures in Gandhâra, and its use would come to the east with the other models of the Hellenic artists who executed these reliefs.²

¹ *Ind. and East. Arch.* pp. 174-8.

² Texier and Pullan, *Prin. Ruins of Asia Minor*, pl. xxii and xxv, reproduced in Bosc, *Dick. gén. de l'Archéol.* fig. 88; Dilettanti Soc., *Antiq. of Ionia*, pl. I, ch. ii, pl. 14; pt. III, ch. ii, pl. 5, 7, J. Durm, *Die Bausteine*, Bd. I, S. 101.

The second capital (ill. 105) came from Loriyan Tangai, and is in the Calcutta Museum. The Jamālgarhī examples are usually in several pieces; this is in one block, but we have no scale from which to judge of its size. The figure of Buddha occurring on one side only of these capitals is indicative that they were used in a façade or the front of a projecting porch where the other sides were less exposed to view. All these capitals were apparently originally gilt, and some of them—as well as some of the best preserved sculptures—still show traces of gilding or of colour, so that, when entire, the effect of the whole must have been gorgeous in the extreme.¹



106. MINIATURE STÜPA FROM LORIYAN TANGAI.
Imperfect restoration. (Calcutta).

Small model stüpas were found in large abundance at Buddha-Gaya; and in the Swät valley several of a structural sort have been found, more or less disintegrated, but which might probably, with

¹ Cunningham, *Arch. Rep.* vol. V, pp. 40 and 106; Fergusson, *Ind. and East. Arch.* p. 124.

proper care, have been carefully pieced together on the spot, by some one who saw the position in which the different portions were found and knew how to combine them. As it is, in the Calcutta Museum, two restorations have been attempted with pieces, perhaps originally belonging to different examples, though all from beside the Loriyan Tangai stûpa.

One of these (fig. 106) is perhaps fairly correct, except that the piece on the top does not belong to it. The height to the top of the dome is 2 feet 6 inches, and the square base is in one piece, very carefully carved. On the side shewn are two compartments: that on the spectator's right is the return in state of the infant Gautama with his mother Mâyâdevî from the Lumbini garden.¹ That to the left may be a representation of the interview of the Rishi Asita Devala with Suddhodana respecting the future of the child. Another side of this base represents (1) Mâyâ on her couch and the descent of the white elephant, with four Devas looking down from two balconies, and (2) the Brâhmana interpreting the dream to Suddhodana, which may be compared with another similar sculpture (ill. 7). The third side represents (1) on the right end the great renunciation in a sculpture differing but little from the one given before (fig. 53); and (2) the giving back of Kanthaka to Chhanda, in which the horse is represented as on its knees in adoration of Gautama: Sakra, as usual, stands with his *vajra* just behind him, and other five or six Devas appear on the scene. Of the fourth side only fragments have been preserved: it represented the birth and the miraculous bathing of the child.


The tier forming the lowest one of the drum of the stûpa contains a series of seated Buddhas. Above this, the second and third tiers have perhaps been transposed in position: the one has a chequer pattern surmounted by a modillion cornice, and the other an alternation of trees and small Atlantes supporting a second cornice of the same pattern. Over all is the dome carved with large leaves as a covering, and crowned by a square box-shaped capital (*gala*), which was doubtless originally surmounted by an umbrella (*chhatra*).

The other stûpa (ill. 107) is much less satisfactorily put together from various pieces which could hardly have all belonged to the same structure. It is scarcely probable that, till very recent times, so small a *garbha* or dome would have been placed over so large a double pedestal; more likely the lower base belonged to another and larger chaitya, and the first tier above the dome is out of all proportion to the latter, while the one below it is as evidently out of place. The sculptured facets or shields attached to the dome, of which one is left, form a peculiarity not met with elsewhere, and seem to indicate the origin of the practice in Nepâl, of placing one of the Buddhas on each of the four faces of their great chaityas.²

¹ Compare this with the scene represented in Arnold's *Light of Asia*, ill. ed. p. 139. I owe the information respecting the other faces to Dr. Th. Bloch of the Calcutta Museum.

² *Notes on Ajanta Rock-Temples*, &c., p. 90; Wright's *Hist. of Nepâl*, pl. xi, p. 174.


The lions or *Simhas* at the corners and centre of each face, too, have not been remarked except in the Swāt stūpas. The excavated Loriyān Tangai stūpa itself was a hemispherical dome with scarcely any basement, but with figures projecting at regular intervals round the lower courses of the dome.—J.B.



107. MODEL STŪPA FROM LORIYĀN TANGAI.
Tentative restoration from various pieces. (Calcutta).

The influence of the Gāndhāra school is very perceptible in later Indian art. The types which were described in Chapter I are, however, less altered than the composition. This appears most clearly in the case of the reliefs of the "rail" at Amarāvati. A formal translation of compositions that have become typical certainly does not occur—though perhaps the birth-scene

is an exception—as has happened in the case of the modern art of the northern schools of Tibet, China, and Japan; but the construction of the relief itself differs from those of Barāhat and Sāñchī. This is occasioned primarily by the introduction into the composition of the figure of the founder of Buddhism. This figure—distinguished, however, by the *Rhāmandala*—naturally appeared in the centre of the compositions, the other figures being arranged according to their importance, starting from the centre. The old plan of crowding together several scenes on the same slab holds good, so far as I can see. The external form of the reliefs of the Amarāvati rail (conf. ill 8) is also noteworthy. After the Roman fashion, they are inserted almost entirely in rosettes (flat *nelumbia*, blue lotus), which adorn the pillars of the enclosure—for example, the middle parts of the rail-bars. The single figures are refined, mostly over-refined developments of the older Indian art: the affected and strained attitudes of the feebly treated bodies are particularly striking; the treatment of the garments, so far as the arrangement of the draperies is concerned, shows the influences of the Gāndhāra sculptures, although perhaps only by an indirect transition. The austere type of the faces in Barāhat—also noticeable here and there in Sāñchī—has likewise disappeared: in the full, effeminate, and very pleasing faces of the sculptures of Amarāvati the Greek influence is also very apparent. Notwithstanding, the Indian element decidedly preponderates: the foreign elements are overpowered by the Indian style, and serve only here and there as means to an end. What was said above about the character of the Indian lyric—especially as regards its strongly marked erotic features—may be repeated to a large extent about Amarāvati. The compositions are loaded with a crowd of voluptuous and grotesque figures: here and there appears a figure of great beauty, which, however, is smothered by the others. In spite of this, it may be said that the best reliefs of Amarāvati are also the best Indian sculptures.



108. CHADDANTA ELEPHANT.
From the Ajanta wall-paintings.
Beal, *Si-yu-ki*, vol. II, p. 49.



109 GĀNDHĀRA PEDISTAL WITH BUDDHA AND
BODHISATTVA

CHAPTER IV

REPRESENTATION OF BUDDHA AND BODHISATTVA.

The appearance of Alexander the Great in India, at the head of a powerful army gathered together from different nationalities, presented for the first time to the Indian Aryans the spectacle of a universal monarch. The idea of a universal empire, first conceived by the Achæmenides, led up to by Cyrus and organised by Darius, had become the inheritance of the Macedonian: no wonder that it found an echo in India, which, since the days of the Achæmenides, had always been intimately connected with Irân. As has been mentioned above, even in Buddha's time, the kingdom of Magadha had become the dominant power in India. This power further increased under the Maurya (Pāli, Mora) dynasty, which Chandragupta had founded. The third king of the Maurya line, Aśoka, afterward the patron of Buddhism, to whose influence the whole Indian peninsula was forced to submit, must have been the first who was regarded by his co-religionists as a Chakravartti.¹ This word, which originally meant the possessor or ruler of a Chakravartta (*Chakravāḍa*), i.e. a district, was at that time, owing to political conditions and the formation of a religious terminology, regarded as a title and had a particular signification. The word was incorrectly divided into *chakra* (wheel) and *vartagati* (to turn, to set in motion), and it was explained as meaning "The king, whose wheel (i.e. chariot)² rolls over all the world." In a previous chapter it was pointed out that, in Vedic times, the wheel played an important part as the symbol of occult power. The attributes and prerogatives of the Chakravartti, as well as his physical peculiarities, are systematically established—canonised, so

¹ Cf. Prof. Rhys Davids, *Buddhism*, pp. 318-20.

² The original meaning, however, was simply "Ruler of a district."

to speak. In the first place, he possesses the seven jewels (Skt. *sapta ratnāni*; Pāli, *satta ratanāni*), i.e. the best specimens of each kind that appear during the reign: the jewel of the wheel, of the elephant, of the war-horse, of woman, of the pearl, of the general, of the minister. The order of succession is, as Fergusson says, strange but characteristic. We cannot enter upon a detailed examination of this remarkable emblem here, but it is interesting to notice that the wheel of the Chakravarttī has become, we know not when, a mystic weapon, swung and thrown by the hand: the Hindū religion bestows it on Vishnu as his attribute, &c. Moreover, the iron "quoits" of the faqirs of the Sikh religion are well known.

The physical qualities of the Chakravarttī are those of the so-called "great Being" (Skt. *Mahāpuruṣa*, Pāli, *Mahāpurisa*). They consist of the thirty-two greater and eighty lesser physical characteristics or marks. But these beauty-marks the Chakravarttī has in common with Buddha. Indeed, in contradistinction to the emperor, who ruled over the whole world, whose attribute of majesty is theoretically developed by the church, there appears the figure of a ruler of a supernatural world. This is Buddha, who, according to the legends, was born of royal race, and would have become a Chakravarttī if he had not preferred to reveal to man the true doctrines. In the old Buddha legends (*Avidūreṇḍāna*) the contrast is most clearly expressed in the finely-sketched scene where Gautama leaves his home, and an angel opens to him the locked and guarded gate. Then Māra Vasavarttī, the god of passion, approaches and advises him not to leave his home and not to become a monk. "In seven days will the world with all its lands and their two thousand islands be thine." The wheel of the Chakravarttī is the symbol of Indian power: the wheel of Buddha is that of religion (Skt. *Dharmachakra*; Pāli, *Dhammachakka*).

These apotheoses of king and of Buddha attained actual completion in opposite ways; Buddha and his doctrine became, as we may say, recognised by the state,—an expression which is hardly appropriate, inasmuch as the intolerantly exclusive tendency of west Asiatic religions is not thereby indicated—and the grateful church gave the monarch a corresponding position in her system. That the whole theory was a gradual development is undoubted; the fact that representations of the so-called seven jewels appear first at Amarāvattī is a proof of this.¹ But, in any case, it was Asoka who gave rise to this view.

The specialising of the physical characteristics of the "great man" rested on the ancient art of explaining signs, and—as will appear from what follows—formed the basis of the artistic efforts.

¹ For example see the reliefs in Fergusson, *Tr. and Serp. Wor.* pl. xli, 3, xlv, 3; on the plinth of a Śiṅhanāda Lokeśvara, *J. E. As. Soc.* (1894), p. 54, and pl. i, etc.; Pozdneev, *Zap. geogr. Obšč.* XVI, pp. 87f.; conf. also K. Kusawara, *Dharmasaṅgraha in Anecd.* *Op. As. ser.* vol. I, pt. v, p. 60.

It has been mentioned that, even in the time of the Chinese pilgrims, there were attempts to establish authentic representations of Buddha. It may be said that the desire to have a picture of the conqueror made claims upon the Hindû artists, which were utterly at variance with their methods of conception. The rich ornament, which so often prevents us seeing that the body represented is wretchedly formed, disappeared in consequence of the legend. Instead of the figure of a king in rich turban, with garlands of flowers, rich ear, breast, and loin ornaments, the narrow upper garment distinct in all its parts, and the comfortably-fitting covering of the lower limbs,—the artist had to represent the figure of a monk unadorned, with shaven skull, in a cowl-like garment,—but so to idealise it that it should be worthy to rank as a sacred representation. The attitudes which had to be given to the figure likewise sprang from the legends: he had to be represented meditating, teaching, consoling, and entering Nirvāṇa, *i.e.* dying. At any rate, these were, and remained, the fundamental types, though the canon devised a particular pose for almost every scene in Buddha's life. Thus there originated a figure sitting—Indian fashion—with crossed legs, and hands laid flat on one another in the lap,—meditating; the right hand falling to the ground,—calling upon the earth as witness; the right hand raised and held palm forward, while the left hangs flat by the side, or holds the folds of the garment.

It is natural that an art, like the old Indian, which had not become independent—as it was not in a position to give the necessary dignity to such unornamented figures—should bestow a supernatural character upon them by means of all sorts of accessories of an extraordinary nature. To a perfected art, which had at its disposal all the types of systematically developed schools,—perhaps the Greek of the Roman period, or, in the domain of painting, the Spanish of the seventeenth century,—this subject, the creation of an ideal portrait of an ascetic or philosopher, might have afforded material for masterpieces. But the actual capacity was childishly weak, and the ritualistic interest was the chief thing considered. An idealising response to this conception now showed itself: the great Teacher, who had entered Nirvāṇa, became more and more god-like to his followers: the flowery epithets of the legends were interpreted literally; he thus became possessed of supernatural gifts. A further impulse to idealisation was given by the fact that the executive art restricted itself to youthful types. Even on the most ancient Buddhist monuments a series of popular signs have been canonised by Buddhism: we find the foot-marks with the sign of the wheel, or the well-known Svastika as symbol of Buddha (*conf. above, p. 72*). Now the physical perfections of the great being¹ form a series of exactly similar distinctive marks. They vary somewhat in their order: indeed, some of the "smaller beauty marks" are specified among the larger, and so on.

¹ *Conf. H. Kanizawa, i. 27, 171, 53ff.*

The customary order of the *mahāpurushu Lakshanas* or superior marks (*Lalitavistara*, *Mahāpadhānasutta*, *Dharmapradīpikā*) is: 1, the head shows a protuberance (*usknīsha*) on the skull; 2, the hair is glossy black (blue) like the tail of a peacock, or like pulverised eye-salve, it is arranged in short curls and each curl goes off from left to right; 3, the brow is broad and smooth, 4, between the eyebrows is a little ball (*ārṇā*, Pāli: *unna*—tuft of hair) shining like silver or snow; 5, the eyelashes are like those of a bull; 6, the eyes are brilliant black; 7, he has forty teeth of perfectly equal size; 8, they lie close to one another; 9, and are dazzling white; 10, his voice resembles Brahmā's; 11, he has an exquisite sense of taste (?); 12, the tongue is large and long; 13, the jaws are those of a lion; 14, the shoulders and arms are perfectly round; 15, the seven parts of the body are quite rounded and full (the palms of the hands, soles of the feet, etc.); 16, the space between the shoulders is filled out; 17, the skin has a tinge of gold colour; 18, the arms are so long that when he stands upright, the hands reach down to the knees; 19, the upper part of the body is that of a lion; 20, his figure is like that of the banian tree (*ficus religiosa*); 21, only one little hair grows from each pore; 22, these little hairs curl from above towards the right; 23, nature has concealed the marks of sex; 24, the thighs are well rounded, 25, the legs are like those of the gazelle; 26, the fingers and nails are long; 27, the heel is elongated; 28, the instep is high; 29, his feet and hands are delicate and slender; 30, his fingers and toes have a web between; 31, under the soles of the feet appear two shining wheels with a thousand spokes; 32, the feet are flat and stand firm.¹

The eighty smaller marks (*anuvyanjana-lakshana*) are: 1-3, his nails are round, copper-coloured, smooth; 4-6, the fingers round, beautiful (?), long; 7-8, neither veins nor bones are seen; 9, the sinews are firm; 10, the feet are alike; 11, the heel is large; 12, the lines of the hand are soft (?); 13-16, regular, deep, not twisted and elongated; 17, his lips are red like the fruit of the Bimba; 18, his voice is not rough; 19, he has a thin, long and copper-coloured tongue; 20, his agreeable and melodious voice resembles the sound made by an elephant or thunder; 21, he is of full strength; 22, he has long arms; 23, his limbs shine; 24-29, they are delicate and large, powerful, regular, well-knit and well-proportioned, 30, the knee-pan is broad, big and full; 31-33, his limbs are rounded, graceful and symmetrical; 34-35, the navel lies deep and is regular; 36-37, his behaviour is noble, causing joy everywhere; 38, he sheds abroad an unearthly light that dispels all darkness; 39, he walks slowly, like an elephant; 40-42, he strides like a lion, like an ox, like a *hansa*; 43, in walking he turns to the right; 44-46, his sides are muscular, shining, straight; 47, his belly is like a bow; 48, his

* ¹ The Sanskrit names of the Lakshanas are given in B. H. Hodgson's *Illustrations of the Lit. and Rel. of Buddh.* (1837), p. 129, or *Essays* (Lond. 1874), p. 90. (Conf. Burnouf, *Lotus*, pp. 616-17; Alabaster, *Wheel of the Law*, pp. 113ff. and 312f. Sp. Hardy, *Man. Buddh.* pp. 382f.; *Lalitavistara*, pp. 381f.—J.B.

body is free of all dark spots that could disfigure it; 49-51, the eye-teeth are round, pointed and regular; 52, the nose is prominent; 53-63, the eyes are brilliant, they are clear, with a friendly expression, long and large, they are like a flower—the leaf of the blue lotus (*nymphaea*), have beautiful even brows, which meet, are clearly marked and black; 64-67, the cheeks are full and smooth, without disfigurement, without trace of hate and anger; 68-69, his passions are perfectly bridled and have attained perfection; 70, his face and forehead express perfect harmony; 71, his head is perfectly beautiful; 72-79, the hair of the head is black, of the same length, well arranged, perfumed, not disordered, not dishevelled, neat, in coils; 80, the hair forms the figures *Śrīvatsa*, *Svastika*, *Nandīvavarta* and *Vardhamāna*.

Although many of these smaller beauty-marks are very difficult to describe and still more difficult to explain, it seemed necessary to specify them all, as they furnish a remarkable proof of the systematizing method of the Buddhists.¹ In the main—so much is clear—the basis is formed on a youthful figure with the peculiarities of the Hindūs, just as they are described even in Brāhmanical works: it is the type of the Indian hero. The long arms are specially strange. With the Hindūs as with the Persians, this is an old mark of noble birth. In old Persian names and cognomens, with which the Indian may be compared, this peculiarity is manifested; I need only recall 'Longimanus,' which corresponds to an O. Persian *Darghabāzu*, O. Indian *Dirghabahu*, and to the Persian name translated by the Greeks—*Megabazos* (O. Indian *Mahābāhu*), etc. With these appear characteristics of a supernatural, and—according to our ideas—uncouth nature, which militate against an ideal conception. Thus the tuft (*śrṇā*) between the brows must have had its origin in the superstition that men whose brows run into each other are specially gifted. The representations of Buddha give the *śrṇā* in the form of a small round protuberance over the root of the nose, which in older and more modern figures is frequently replaced by a pearl, and so on. The protuberance on the skull (*ushnīsha*) is likewise an abnormal physical peculiarity, which was thought to be extraordinary and supernatural.

The chief difference between ancient art and the art of the Gāndhāra period is that the figure of Buddha is evolved from foreign models. As has been pointed out, the hairsplitting philosophy of the Buddhist sects led to a highly developed detail of the characteristics of a Buddha. The person of Gautama takes the form of a belief, which is commented upon in all directions. The idea of Buddha is the chief matter. The introduction of the image of Buddha makes the ancient philosophy more of a religion.²

If we return to the sculptures, we see before us, among the

¹ The greater *śrṇā* are $25=4 \times (2 \times 2 \times 2)$; the lesser $80=(1+2+3+4) \times (2 \times 2 \times 2)$; and the smaller on each foot are $108=4 \times (3 \times 2 \times 2)$. Is this accidental?—J.B.

² See above p. 87, note 2.

Gāndhāra remains, the complete ideal Buddha, produced under Hellenic influence. And here we may give attention to the introduction of a retrograde movement and see how the type has become changed and deteriorated in different lands

The attitudes required by tradition,—the most important of the physical characteristics established by superstition,—though they



110. GAUTAMA BUDDHA FROM TAKHT-I BANI
Height 20 in. Original in Berlin Museum.

remain latent, are faithfully retained in the sculptures of Gandhāra. In true Greek style, the disfigurement of the bump of intelligence

(*ushnīṣa*) upon the skull, is concealed by a cluster of locks of hair, in many cases the closely-cut hair, which the figure should have, is replaced, incorrectly, and in contradiction to the tradition, by an abundance of locks. The Apollo type of the Alexandrine period, which was used as a basis for the Buddha-head, gives an idealization, which is in entire opposition to the possibility of the portrait of Gautama. Nowhere do we see the head shaved bare thus the idea



111. BUDDHA TORSO FROM TAHT-I-TARI.
Height 15½ in. Original in Berlin Museum.

strikes us, that the short curls turning from left to right are only an attempt of a stage of art no longer able to represent the free falling waved hair. In translating the Apollo-ideal, two things may have

influenced the Hellenists, or whoever effected this first translation. First of all, the character of the Greek god, not only as leader of the muses, but also as a nature god (Helios) in both phases he found his counterpart. In conformity with the old Indian nature-worship Buddha's epithets had become chiefly those of a light or sun-god, so much so, indeed, that in Europe it has been attempted to




112. GAITAMA ON THE PADMASANA.
From Lonyin Tangu.

deny his historic existence, and to make of him an old sun-god.¹ His appearance as teacher, physician of souls and healer, justified the other side. It must not be forgotten, either, that the district in which the translation took place, before the introduction of Buddhism, belonged to the fire-worship of Zarathushtra, which must

have become the state religion, and which united the Indian provinces with the Baktrian kingdom. It is known, and has already been mentioned, that wherever the Greeks came upon the light and sun-gods of the barbarians, Apollo types were there evoked.

The sculptures of the Gāndhāra convents have had a lengthy development, which cannot, indeed, as yet be exactly determined. But this is very apparent in the Buddha types, that along with an idealistic tendency which is certainly the older, as it preserves the Greek types, is found a realistic and clearly more modern one. But in both cases there are, if we may use the expression, Indian degeneracies. To the idealistic tendency belong Buddha-heads with youthful, Apollonic features, with gently smiling mouth, half-shut eyes with soft, full, fleshy parts, finely moulded nose, and sharply defined, luxuriant and elegantly arranged hair (conf. ill. 111). One, the finest, which the Berlin Museum possesses (ill. 110), even shows the coquettish locks before the ear, that were the fashion at Athens in the time of the Diadochs—successors of Alexander, and which; if I am not mistaken, are to be found on



113. BUDDHA HEAD FROM TAKHT-I-BÂHI.
Original in Berlin Museum.

114. BUDDHA HEAD FROM TAKHT-I-BÂHI.
Indian type. Original in Berlin Museum.

the Apollo Musagetes. With these examples we may also compare ill. 112,¹ a fine relief from Swāt. It represents the Buddha, with a youthful face; the eyes half closed, a slight smile about the mouth, the head unmarked, and the hair wavy and dressed in the style of the other Gāndhāra reliefs with the robe over both shoulders. The

¹ *Journal of the Asiatic Society of India*, vol. VII, p. 43.

sculpture represents the Jina upon the *padmāsana* or lotus-seat, supported, as usual, by two small worshipping figures.

Along with the idealistic type of purely Hellenic formation, are found heads of Indian race, executed in the way prescribed. On the one shown in ill. 114 the Indian element is distinct: the hair rough and treated in the orthodox way. A little later there follows the type of the Buddha-head shown in the relief represented in ill. 82. In the main it preserves the old idealistic forms, but they are preserved, as it were, artificially, and are deprived of all individuality and independence: a picture of still beauty absorbed in itself, which has an effeminate and unmanly effect.¹ The northern school has preserved this type well: it is shown in astonishing purity in the Buddha-heads of Bôrô Budur (conf. ill. 115). The hair



115. HEAD OF A BUDDHA FROM BÔRÔ BUDUR
Original in Berlin Museum.

is luxuriant as in ill. 82, and arranged in small locks as the canon requires. But the elongated ear-lobes are never missing, not even in the best heads. It appears that even this peculiarity, which shows so decidedly the laying aside of the royal ornaments, also arises from attempts made by Hindû artists in connection with the

¹ "The statue of Buddha should measure from the top of the *mekhika* to the sole 125 fingers," so also the length of the outstretched arms "measures 125 fingers." - A 1.

Buddha type, before the Gāndhāra sculptors idealized it. For comparison another example (fig. 116) may also be here introduced. It



116. BUDDHA STATUE

Original in Fitzwilliam Mus., Cambridge

one, with some beard on the chin. This certainly corresponds with examples of the Gāndhāra school, but how it comes about we do not know. A positive testimony is, however, at our command in Chinese sources. This is due to communications for which we have to thank Hirth,¹ relative to the artist Wei-chi-l-sōng of Khotan, who flourished at the Imperial court of Chang-an-fu (7th century),

¹ *Jour. Ind. Art, &c.*, vol. VIII, p. 85.

² *Über fremde Einflüsse die chine.* Kunst, Ss. 48f. "But as to how that character, foreign to Chinese, but, according to Genes, resembling Indian taste, came into ancient Chinese art, I can give no better explanation than that afforded by an allusion to the origin of the artist who served as an example to the Buddhist painters, the Central Asian Wei-chi-l-sōng. The Indian traits that we notice between the 7th and 12th

was found among some ancient remains on the west bank of the Indus, just outside the Hazārā district, and thus to the east of the other find-spots of such sculptures. Unfortunately it has been much injured by hewing off the arms and legs, and what remains is only about 2 feet in height. The hands are in an unusual position for a standing figure of the Buddha, but the face is particularly striking and of excellent workmanship.¹

On the sculptures of the southern school, monumental as well as miniature, the treatment of the hair and of the ears degenerates into the unnatural incoherence of its prolific reproduction, which was considered as a specially meritorious act.

The naturalistic tendency, likewise, working with purely antique materials, evidently did not appeal much to the Indian taste. It shows an austere, rather cold, Hindū face with coarse moustache (conf. ill. 117). In Indian sculpture no Buddha-head is seen with a moustache. But the old Chinese (and Japano-Korean) sculptures always give Buddha a moustache, although a very artificial-looking

and upon whose influence the Indo-Baktrian elements of the eastern Asiatic art must be based. One of the principles which are to be kept in mind in the further examination of Buddhist iconography is—that the common forms of the different countries must be tabulated with reference to the prototypes in Gandhāra. The moustache appears in Gandhāra at times in the idealistic type. The Buddha figure from Swāt district, represented in ill. 119, shows in the face powerful and full outlines, with fine features and smooth hair; the moustache is only indicated by some lightly-marked lines behind the corners of the mouth.

The treatment of drapery in the Buddha figures of the Gandhāra monasteries is almost entirely Grecian. The robe, in upright figures, is so laid round the body that it reaches to the ankles, covering both shoulders and the body. In the finer ancient pieces and good replicas (conf. ill. 117, 122) the robe is so disposed as to show the contour of the body, the folds following the lines of the limbs in a natural and unconstrained way. The robe is laid round the neck, and the folds marked by lines that are usually hollowed out (conf. ill. 122)



117 GANDHARA BUDDHA. Naturalistic type, with moustaches, from Swāt. Height 44 cm. Original in Berlin Museum.

centuries must have been introduced by way of India and Khotan, the home of I-sung, with its art-loving princely court, and from thence by Ch'ing-an-to, the imperial city of the 7th century, and Korea and Japan."

The arrangement of the drapery appears to be flatter in the later reliefs,—those which represent Buddha with moustaches. In the



118. GATTAMA BUDDHA.
Takht-i-Bâhi. Height 31 in.
Original in Berlin Museum.

northern school, and even in China and Japan, this way of arranging the drapery seems to have been preserved with wonderful tenacity. The ancient Chinese and Japanese Buddha-figures have preserved the 'draping' of the Gāndhāra figures in a peculiar way. Ill. 120 shows a small modern miniature of a Buddha from Japan, painted on silk. The statue of the sitting Buddha from Takht-i-Bâhi, in ill. 110, may be compared with this. The miniature makes no attempt at shading, but the arrangement of the folds is rendered clearly enough by the black outlines drawn in. The old drapery is still better preserved in the standing figures. Modern paintings also show it distinctly, as in ill. 124, from Japan—from a large picture which represents the Paradise (Sukhāvati) of Amitābha.¹ It has been mentioned above, that in the earlier Gāndhāra works the folds of the drapery are sharp and angular, sometimes even projecting at the edges. The Chinese wooden figure of a Buddha in ill. 125 shows a remarkable degeneracy from this thoroughly Greek idea. This wooden figure is, however, more interesting in respect that it is certainly a replica of a copy, which has been preserved in China and is

traced back, according to the Chinese tradition, to Udayana's sandalwood figure of the Master.² The first Indian kings who are

¹ Compare with this picture the beautiful legend in Schott's *Ueber den Buddhismus in China und Kuchuan*, Berl. Acad., 1846, Ss. 55ff. Also Yule, *The Book of Sir* *Roderic*, vol. I, pp. 406ff.

² Cf. N. Bar, *Travels of Fa-hien*, p. 210 (front of cover), and Hofmann, *Buddha-
thronen und Klenodien*, M 186, S. 220, and also illustration — *Führer des Kal*

mentioned as having possessed statues of Gautama were Prasena-jit of Kosala, who had seen the Master, and Udayana of Kausambi, at whose command the famous sandalwood figure was prepared by a master who had been sent to heaven,—which figure doubtless is



119 SANDALWOOD GAUTAMA BUDDHA WITH MOUSIACHES
From Suât, height 28½ inches. The great aureole that was behind the head is almost entirely broken off. (Original in Berlin Museum.)

connected with the Gāndhāra sculptures. We are indebted to Fāh-hian for the account of Prasena-jit to Hsuen Tshang for that of Udayana. Whether by the picture, which Prasena-jit is said to have possessed, another type of the Buddhist ideal is intended is naturally beyond our knowledge. On the Buddha figure, shown in ill. 125, which goes back to Udayana's type of Buddha, the edges of the folds stand out in imitation of the ancient forms: the raised lines do not merge into one another, and they are modelled into grotesque ornaments at the sides, while the edges of the drapery,

Museums f. Völkerkunde, 7 Aufl. (1898), S. 192. The reflection in the water. G. Huth, *Geschichte des Buddhismus in der Mongolei*, Bd. II (trans.) S. 400.

falling from the arms, have received a quite antique arrangement.

How strangely the Asiatics touched upon this representation is proved by the explanatory legends which a Tibetan historian quotes regarding the Buddha figure of Udayana. He relates how Buddha—



120. FIGURE OF A BUDDHA.

From a modern Japanese representation, prevalent in the Chinese religions. Painted on silk. Berlin Museum.

in order to lighten the work of the artists, who were blinded by his glory—was mirrored in the water. The artists reproduced this reflection and thus the waving lines of the robe are accounted for.

It is noted above that in these sculptures, the figure of the Buddha is draped in two ways,—with the right shoulder and arm bare, or with the robe drawn closely round the neck and over both shoulders. When he is represented as seated either on the *padmasana*—the lotus throne (as in ill. 121, and *Four Ind Art, &c*, vol. VIII, pl. 7, fig. 1, and pl. 8, figs. 1, 2),¹ or on the *vajrasana* in the *bhūmisparsamudra*, as in ill. 49, the first mode seems to be the more usual; this is also frequent in the case of standing figures (see ill. 95), and even in some representations of the *nirvāṇa* (ill. 75, 76). But it occurs in nearly all groups of Buddhist sculptures and paintings in other parts of India.² The vesture fitting closely round the neck, on the

¹ *Arch. Sur. S. Ind.—Amaraṇthi*, p. 12.

² See *Ind. Mon.*, pl. 98, and 102, fig. 1; *Amaraṇthi*, us., pl. xxvi, 1; xxxii, 4; xxxiv, 1; xxxv, 1; xxxvi, 3; xxxvii, 1, 2; xxxviii, 5; xxxix, 2; xli, 6; xliii, 5 and 8; li, 1 and 2; and iv, 5; *Cave Temples*, pl. xxxi; xxxv, 1; li, and lvi; *Arch. Sur. W. Ind.*, vol. III, pl. xli, vol. IV, pl. xxvii, xxx, and xli, 1; vol. V, pl. xviii, 4; Griffiths, *Ajanta Paintings*, pl. 15, 24, 38, 39, 43, 51, 54, 61, 68, 91 and 151, &c.

other hand, is distinctly the more prevalent among the Gāndhāra sculptures and is frequently copied elsewhere. Whether the rise of Buddhist iconography in the colder climate of Gandhāra and



121. BUDDHA AND BODHISATTVAS

15 inches broad From Loryān Tangai. Calcutta Museum.

under foreign influence favoured the more warmly draped forms, may deserve consideration; but the instances of both styles of dress are numerous.¹

The Buddha representations found in the stone enclosure of

¹ Dr. Th. Bloch, *J. As. S. Beng.* vol. LVII, pt. i, p. 288, states that, "wherever we find a Buddhist statue which has the right shoulder bare, this is to be taken as a sign that the statue represents, not a Buddha, but a Bodhisattva." In presence of the examples cited, and the remarks which follow, this conclusion cannot be supported.—J. B.

Amarāvati, are the principal Indian sculptures that follow the



122. GAUTAMA BUDDHA FROM TAKHT-I-BĀHI.
Height 38½ inches. Original in Berlin Museum.

Gāndhāra style (conf. ill. 123). Some Buddha statues found at Mathurā have also the robe laid over both shoulders, and the folds executed on the dress point to the Gāndhāra sculptures as models.

The Buddha image in the middle of the relief from Muhammad Nāri in ill. 82 is particularly remarkable, as in more than one respect presenting highly interesting features. As before mentioned, the head, especially in the treatment of the hair, is Indian; but in respect of the drapery the uncovered shoulder is striking. These two particulars belong exclusively to the Buddha-images of the southern school. The same character, however, is also found in the more recent Buddha figures from Bengal and Nepāl (Tāranāthā's Nepāl school) and in that of modern Tibet, which is dependent upon it. Evidently it is the old orthodox type¹ which becomes apparent here. The figures at Amarāvati (ill. 123) and Mathurā, which were influenced by the Gāndhāra sculptures, seem there-

fore to have been supplanted by a national Indian type which

¹ The European Buddha figures have also both shoulders covered. Conf. S. v. Oldenburg, *Turkistanische Denkmäler* pl. 12 (no number) 1, 2, 3; Sven Hedin, *Thurayya the Descent of Asia*, vol. II, p. 70; a very fine old Indian bronze of the same type, *J.A.S.B.* vol. LXIV (1893), pt. I, p. 159, and pl. viii.

was afterwards preserved in the southern church and also in Nepál and Tibet. Indeed, a Chinese source gives us the important information that the Buddha image depicted at Nálanda was represented with bared right shoulder.¹ Ill. 126 presents an ancient Nepál type; that shown by the great bronze dating from the 12th or 13th century, which is represented in ill. 127, is ancient Siamese; it is, however, extraordinarily like the ancient Burmese.

Stress must here be laid upon the fact that, with our present knowledge of the subject, it is quite impossible to give a detailed description of the individual tendencies. The different types, therefore, can only be sketched so far as they are at present known; placed in relation to ancient pieces; and, only in very special cases of contact can any connexion be established. Above all, there are blanks in the accessible material—both in respect of the history of the religion and the monuments preserved. It seems as if the different types, belonged to different schools. Thus it happens that in China, Lamaism, *i.e.* Tibetan Buddhism, preserves the Indian type of Buddha with the bare right shoulder, which it got from Nepál; while the ancient Chinese Buddhism, the so-called Foism, possesses the type, which in its draping, etc., points indirectly back to the Gāndhāra sculptures. That, notwithstanding, it appears in Lamaist sculptures also, is not denied.

* Besides we must take into consideration the fact that the southern school, at this time completely cut off from the northern one, by the revival of the Brahmanical cult, and, later still more radically, by Islām, was not by any means entirely separated in the Middle Ages. In fact, the northern school, more than once, exerted an influence in dogmatic, but still more in artistic departments in certain countries belonging to the southern school.² The Buddhist statues of old Kamboja, and further, partly of old Siam, old Burma, modern Shān, and Lāos—which always appear in royal attire and crown—have a peculiar—perhaps local character, which is only a variety of the old Indian. Some further points, that strike us in the Buddha type, which appears for the first time in Gāndhāra, are—the aureole, the sitting attitude, and the position of



123. GAUTAMA AND HIS SON
RAHULA,
With Buddha the vajra-bearer.
Amarāvati relief.³

¹ Conf. Hirth, *Ueber fremde Einflüsse auf die Chines. Kunst*, S. 51.

² From Fergusson, *Trees and Serp. Wor.* pl. lix, p. 189.

³ Conf. in this connection B. Laufer's pertinent remarks in *Globus*, Bd. LXXIII, 2, S. 81, fig. 6.

the hands All that is necessary has already been said on the aureole (p. 86)



124. BUDDHA FIGURES ATTENDED BY BODHISATTVAS
From a modern Japanese picture representing Amitābha's Paradise.
Original in Berlin Museum.


The change of position in the limbs gives to art the opportunity of characterising the action it desires to give to the figure. As to the feet, as the Buddha-figure is debarred every movement, there only remains the sitting posture in which, as has been pointed out, the

ascetics must give the standard; the upright position and a slight variation of it—the slowly stepping. In the reliefs—which we should imagine have been arranged in the workshop from model figures—the last type is the favourite one, and, as has been pointed out, with a leaning to the ancient idea of the sacrificing general.

The artist has more freedom in the question of the hands.¹ If we hold by the purely technical origin of our relief, let us watch how the sculptor changes his model figures, according to the legend which he is to represent. Thus gradually, certain hand-postures attached themselves to particular legends, and the position of the hands in the chief figure becomes an indication of the legend.

If we leave the theoretical side of the *mudrā*, we can gather so much for 'the practical art, that the whole life of Buddha, in its different incidents, required a series of modifications of hand postures, which were allotted for purposes of distinction to one and the same figure, and naturally we oftencst meet with those postures which illustrate favourite scenes.

What has been said is important on the following considerations: It has been above pointed out that, under the influence of art, the Buddha type broke free from the person; the idolatry, however, lay deeper and was older.



125 CHINESE BUDDHA FIGURE.
Carved in wood and gold lacquered.
Original in Berlin Museum.

¹ On the *mudrās*, see *Ar. Sur. W. Ind.* miscel publ. No 9, p. 99; *Ind. Ant.* vol. XXVI, p. 24; Waddell, *Lamason*, p. 335f; Grunwedel, *Mythol. d. Buddhismus in Tibet*, S. 200, n. 22; Schlagintweit, *Buddhism in Tibet*, pp. 56, 206; Foucher, *Étude sur l'Iconographie Bouddhique*, pp. 68f.—J.B.

Even while Buddha was still alive, the rudiments of a formal cult for him seem to have here and there appeared; various episodes, related in the *Jātakas* and the literature allied to them, indicate



126. OLD NEPAL STONE FIGURE OF GAUTAMA BUDDHA.
Seated on the lion throne with the formula: *Ye dharma hetuprabhavaḥ* ¹
Original in Berlin Museum.

this. We learn how Buddha again and again seeks to make his position clear even to his most devoted followers, and yet how it fared with him as with all religious teachers at all times: they themselves become the objects of worship—the gods of their sects. Even the latest Indian reformer, the Bengali Chandra-sēna, of the

¹ On the formula conf. *Arch. Sur. W. Ind.* vol. V, p. 18, note 3.

Brahmā-Samāj, in the present century, has had to defend himself against this. The apotheosis is still easier after death. It is characteristic of the biography of every reformer that it is idealized and remodelled, and so gradually becomes legendary.¹ The description of the life of Buddha, the sources of the individual versions of which



127. OLD SIAMESE BRONZE: GAUTAMA BUDDHA
(P'ra Kodom) from the ruins of Kampeng Pet, 12th-13th cent.
Size 12½ inches. Original in Berlin Museum.

(the *Avidurānidāna*, *Lalita Vistara*, etc.) have not been investigated, and between which no parallel has been made,—are imposing poems of considerable extent. The more the figure of the man, from whom a religious school has sprung, is deified, the more insistent becomes the question, whether he may ever come again. In India this development seemed a very natural one on account of the doctrine of the metempsychosis. The view of the Buddhist was not that Gautama, who had trodden the immortal path (*amataṃ padam*), might come again, but rather that there were other beings who become Buddhas. One word, which Gautama seemingly used

¹ Conf. e.g. the case of Nārāyaṇa Svāmi, Heber's *Narrative* (ed. 1820), vol. III, pp. 29f., 34-42; *Ind. Ant.* vol. I, pp. 331-36; Briggs, *Cities of Gujarāṣṭra*, pp. 235ff. and app. xiii-xxiv.—J.B.

for himself, and which is among the most difficult of his terms, is the word *Tathāgata*, "the one, who came thus." Originally, no doubt, it simply meant, "he who came like all other men." But



128. OLD INDIAN CLAY SEAL FROM BUDDHA GAYĀ.
Gautama Buddha surrounded by small stūpas, behind him the branches of
the Bodhi tree and—as it appears—the spire of the temple at Gayā.
Original in Berlin Museum.

soon an emphatic reference to the supernatural was seen in the term. So the circle of representation expanded till it was received as, "he who has come as his predecessors." In connexion with this is the idea that there have been, not one, but several Buddhas; and that each being, who wishes to become a Buddha, must in a former

existence have met a Buddha and expressed to him his wish to become the enlightener. These teachers of mankind appear upon the earth at long intervals and the doctrine (*Dharma*) which they all teach is the same. With each there is a period in which the doctrine flourishes, then a gradual decline, then it is overborne by the barbarians and completely overthrown,¹ till a new deliverer appears and once more establishes the lost truths in all their purity. Gautama Buddha's predecessors are: *Vipasyi* (Pāli, *Vipassī*); *Sikhī* (Pāli, *Sikhī*); *Visvabhū* (Pāli, *Vessabhū*); *Krakuchanda* (Pāli, *Kakusandha*); *Kanakamuni* (Pāli, *Konāgamaṇa*); and *Kāśyapa* (Pāli, *Kassapa*). Both the northern and southern schools recognise these direct predecessors of Gautama (a complete list would give more), the details related about them in both traditions and the names of the trees, under which they obtained enlightenment, agree and point to one source.² But the representations of them given in the southern and northern church no longer agree. Of this, more hereafter.

The last Buddha of this age of the world, after Gautama, will be *Maitreya* (Pāli, *Metteya*, Tib. *Jamba*, written *Byams-pa*), "the loving one." The northern school fully recognises him and puts revelations into his mouth; indeed, he is venerated everywhere, almost more than Gautama. In the southern canon, so far as I can see, he does not appear; though he is mentioned in the Singhalese chronicle, the *Mahāvamsa*. *Maitreya* is the *Bodhisattva* of the present age.

Mention has been made (p. 59) of the *Jātakas*, which describe the previous forms of existence of a Buddha, that is a *Bodhisattva*—a being whose characteristic (*satva*; Pāli, *satta*) is enlightenment (*bodhi*), who while doing a pious action, in the presence of a Buddha, expresses his desire, in a later incarnation, to become a Buddha. According to the theory, Gautama also expressed this wish before former Buddhas (Pāli, *paññadhīma-kar*). The sum total of his good actions (Pāli, *kamma*) allows him at each reincarnation to be born as a superior being in a constantly ascending scale of goodness, till, in the Tusita heaven, he resolves to accept another human existence, that he may show to bewildered man the way of salvation, and then to enter *Nirvāṇa* himself.

According to theory, the *Bodhisattvas* are innumerable; and it

¹ The "period of the first law" lasts 200 or some say 500 years from Śākya Muni's death. The second era is called *Saddharma pratirūpaka*—"the law of figures or images," and lasts 1000 years; and the third epoch, the "last law" or period of declining religion, should last 3000 years, after which *Maitreya* renews the process.—Des Guignes, *Mém. de l'Acad. des Inscrip.* tōm. xi. p. 201; Beal's *Romanic Legend*, p. 9.—J.B.

² Ante p. 74. The trees thus sacred to the seven Buddhas are respectively: *Pātali* (*Bignonia suarcelens*), *Pundarikā* (a kind of mango), *Sāla* (*Shorea robusta*), *Sirisa* (*Acacia vir.*), *Udumbara* (*Ficus glomerata*), *Nyagrodha* (*Ficus indica*), and *Pippala* (*Ficus religiosa*). A remarkable correspondence exists here between the twenty-four past Buddhas and the Jaina *Tirthamkaras*. See *Ind. Ant.* vol. Xlii, p. 270; *Jour. As. S. Beng.* vol. V, pp. 321f.; Sp. Hardy, *Men. Buddh.* p. 89.—J.B.

is the object of the religions of the Mahâyâna school,—which undoubtedly must be brought into connexion with our Gāndhâra sculptures,—to aspire to the transmigration as Bodhisattva—"the great career," as opposed to the Hīnayâna (the old school), the monks of which were only interested in their own salvation.

The Bodhisattva representation of later art is that of a royally attired young man, developed from the legend of the historic Buddha, who was, as we learn, a prince (ill. 129). Thus we may claim these youthful figures in rich attire, so frequent among Gāndhâra sculptures, as Bodhisattvas.

They wear crowns or richly ornamented turbans, or curly hair; they are decked with bracelets, necklets and breast-chains. In common with the unornamented representations of Buddha, they have the mark above the nose, called the *urna*, and the nimbus.

The Bodhisattvas, as has already been remarked, belong only to the northern or Mahâyâna schools. Except Maitreya, they are unknown in Ceylon, Siam, and Burma. In Ceylon and Siam the usual attendants or supporters of Buddha in the temple shrines are Śāriputra and Maudgalyāyana, —the "disciples of the right and left hand," with Ānanda, Kāśyapa, etc., standing by; in China, Ānanda and Kāśyapa frequently occupy the like positions, or with Śāriputra and Maudgalyāyana, Mañjuśrī and Samantabhadra, form a group of six beside the Buddha. And in many of the Indian cave sculptures we find the attendant figures, as it were, in a state of transition, holding *chauris* as servants, and also with some of the insignia of the later divinities.

As Buddhism spread, the converts naturally carried into their new religion much of their reverence for the old Hindū gods, and they found that the traditions offered them already embraced Indra, Brahmā, and others of their former divinities. Among the Hīnayâna sects in the south, little change was made: Vishṇu, Brahmā, Nārāyaṇa, etc., were simply accepted under their Hindū names.

But with the Mahâyâna schools, whilst these gods were received, they were made to fit into an elaborate system of nomenclature and myth by which each was assigned a place in the illimitable æons of their cosmogony: Indra or Sakra became Satamanyu and Vajrapāṇi, and his heaven of Swarga was named Trayastriṃsa-



129. BODHISATTVA. From Swāt. Calcutta Mus.

loka, Brahmā, so well known in Bauddha legend, had his chief attributes transferred to Mañjuśrī—the “lamp of wisdom” and of supernatural power; and still Sarasvatī continued to be one of his wives, the other being Lakshmi, Avalokitesvara or Padmapāni, again, has some analogy to the attributes of Vishnu or Padmanābha;¹ Virūpāksha, one of the “four kings,” bears one of Siva’s well-known names; the Sapta Tathāgatas take the place of the Brāhman Seven Rishis; and even Ganesa has been taken, over both as Vināyaka and as the demon Vinātaka (Jap. Binayakia).

Then Maudgalyāyana, the *arhat*, became Mahāsthāma or Mahāsthānaprāpta Bodhisattva, and still kept his place at Buddha Amitābha’s left hand in a popular triad analogous to the Saiva Trimurti. But in the easy-going way of such a religion, Ajita or Maitreya—the Buddha of the future—was also given the same place, and with Sākyamuni and Avalokitesvara forms an alternative Triratna or triad.

This, then, seems to be as rational a theory as we can form of the genesis of these rather superfluous creations of the northern schools of Buddhism. In the later developments of Nepalese and Tibetan sectaries their rôle is enlarged and varied.

¹ See *Arch. Sur. IV, Ind.* vol. V. pp. 14, 17.



180. YOUTHFUL BODHISATTVA.
Lahor Museum. From a photograph.

When first adopted by the Mahāyāna sects, the Bodhisattvas were probably best known by names denoting some easily recognised symbol or attribute, but in course of time, as the forms of the old gods faded out of the regards of the later religionists, these gave way to the hierarchical nomenclature. And the new members of the Pantheon were in no want of designations: one of them—Vikauṣuka Bodhisattva—has no less than 108 names: Mañjuśrī, for example, is variously styled Balavṛata, Mahāmāti, Jñānadarpana, Khadgin, Kumārarāja, Daṇḍin, Mañjubhadra, Sthirachakra, Vajradhara, Śikhādhara, Nilotpalin, Śārdūlavāhana, Simhakela, Vibhūṣhana, etc.

Different schools, too, introduced or specially favoured particular Bodhisattvas, e.g., the Yogācāryas exalt Samantabhadra, Vajrasattva, Mañjuśrī (under the designation of Vajrapāṇi), Ratnapāṇi, etc. The number of these creations has thus become legion: the following list of those more frequently mentioned by name in Buddhist literature might easily be augmented:—

Akshayamati	Pūrnachandra
Anantachāritra	Pūrnāmaitrāyaṇiputtra
Anantavikrāmin	Rāshṭrapāla
Anikshiptadhura	Ratnachandra
Avalokitesvara or Padmapāṇi	Ratnapāṇi
Bhadrapāla	Ratnaprabha
Bhaishajyasamudgata	Ruchiraketu
Buddhasṛjñāna	Sadāparibhūta
Dharaṇḍhara	Samantabhadra
Gadgadesvara	Sarvasattvapriyadarsana
Ghaṇṭāpāṇi	Sarvārthanāman
Kṣhitigarbha	Satatasamitābhīyukta
Mahāpratibhāna	Simha
Mahāsthānaprāpta	Srīgarbha
Mahāvīkrāmin	Supratishṭhitachāritra
Maitreya or Ajita	Trailokavikrāmin
Mañjuśrī or Mahāmāti	Triratnārya
Mārīchi	Vajragandha
Nakṣatrarāja	Vajrapāṇi or Vajradhara
Nityodyukta	Vajrasattva
Padmaśīla	Vikauṣuka
Padmaśrī	Viśiṣṭachāritra
Pradānarūpa	Viruddhachāritra
Prajñākūṭa	Viśvapāṇi or Ākāśagarbha
Pratibhāna	&c., &c.

The identification of the images of different Bodhisattvas is only possible in special instances: they mostly bear a very close resemblance to one another. But some of the more prominent of them have emblems by which they may be recognised: Avalokitesvara or Padmapāṇi has a white lotus in one hand, and on the front of his crown or *mukuta* is a small figure of a seated Buddha.

Vajrapāṇi has a *dāgaba* or *chaitya* as a cognizance (*chihna*) on his forehead and the *vajra* in his hand: but Mahāsthānaprāpta also appears with the same *chaitya* and with a diamond *vajra* supported on a flower. Mañjuśrī has a book, either in his hand or on a flower, and a sword; and Ākāśagarbha or Viśvapāṇi is recognised by the same weapon placed on a flower; and so on—J.B.

The fact that, in the scenes of the reliefs, which represent incidents before Gautama attained supreme knowledge, he is invariably depicted in the same way (conf. ill 50, 81),¹ proves clearly that the figures described can only represent Bodhisattvas.

Now later art, in a purely theoretic way, gives to individual Bodhisattvas the rank of Buddhas though not yet attained by them, and depicts them in the Buddha-type, though with strict adherence to a fixed posture of the hands; thus the Maitreya from Tibet (copied on page 134, fig. 85) is just a Buddha with the *Dharmachakra-mudrā*—a position which, in Lamaism, always denotes Maitreya, but may also be used for other Buddhas.

Now arises the difficult question whether these positions are established in the Gāndhāra sculptures, and whether, in the other attributes of the Bodhisattvas represented as princes, there may be a fixed and distinctive arrangement of the limbs.

Beginning with the last question, one attribute among the Gāndhāra figures strikes us: it is a small bottle with a pointed bottom.

¹ Conf. Bowring's *Siam*, vol. I (1857), pl. at p. 316 (middle figure); Alabaster, *Wheel of the Law*, pp. 164, 208.



131. TORSO OF A BODHISATTVĀ FROM TAKHT-I-BĀHI.
Original in Berlin Museum. 12 inches in height.

The modern representation of Maitreya (Tibetan, Jampa, written Byams-pa; Mongol, Maidari) in the pantheon of the northern school, as it has been developed in Tibet, shows the Bodhisattva in the ornaments and dress of a Hindû god or ancient Indian king,—generally of very youthful appearance. As a rule he is represented standing, but occasionally seated on a chair in European fashion. In the case of standing figures of Maitreya, the *dhoti* (under garment) is often caught up so high that the left leg remains bare to above the knee (conf. ill. 135). The modern attributes are the water flask or bottle (Tib. *bum-pa*; Skt. *maṅgalakalāsa*)—the most important requisite, and the rosary.¹ Frequently both attributes rest upon the conventionally executed lotus flowers, which the figure holds in its hand. This modern representation is important, since it seeks to combine the more ancient types above referred to with the new attributes.



183. SMALL BODHISATTVA STATUE (Maitreya?) on a small relief fragment, from the lower monastery at Natthu, near Sanghāo. From Cole, pl. 20.

182. HAND WITH GREEK OINTMENT FLASK. Swāt district. Orig. in Ber. Mus.

The old Indian bronze figure from Pekin, represented in ill. 134, now in the royal Ethnological Museum at Berlin, is clad in a short loin-cloth, the right hand without attribute, the left holding between the fingers something resembling the bud of a flower. On the lower side of the hand are traces of something having been broken off.

One of the oldest objects in the Berlin Museum is a bronze (of which, unfortunately, nothing is known for certain), which affords an interesting parallel. The figure represented in ill. 135 shows the same position of the hand as the Pekin Maitreya (ill. 134). It is executed, however, infinitely more carefully: the garments, the lips, are inlaid with copper; the crown ornaments, edges and pattern on the robe, and even the whites of the eyes are inlaid with silver. The style is that of Nepāl. The right hand holds the rosary; the left, in the same position as the

¹ Conf. *Versässl. aus dem Kgl. Mus. für Völkerk. Berl. XI, 2/3 (1890) Es. 47, 77. A Lamaist Maitreya standing with two lotus flowers (r. and l. hd.) conf. Uchtomskij, Beschreibung der Or. Reise, v. k. H. d. Groß.-Thronfolger (Russian ed., the German wants some of the plates) V, xxiv; also Grünwedel, Mythol. Buddh. in Tibet, p. 123). The Japanese Maitreya (Miroku) has his hands in his lap and a flask resting upon them, Hofmann, Buddhapanthéon von Nippon, S. 145, fig. 176 (pl. xx), and S. 541 (pl. xxvi).*

Pekin bronze, holds a small bottle with pointed bottom. It appears that this flask also existed in the case of that bronze, but is now broken away; the flower-like knob in the hand is the mouth of the bottle. On the latter, the representation of a stūpa appears on the crown, in the distinctive manner of the Nepāl style. This last attribute, with the rosary, suggests that though the type of the figure—as well as the symbol in the left hand—is identical in both, we are hardly justified in calling this latter figure also a Maitreya. If, meanwhile, we leave this figure out of account, the further data tend to the determination of the Maitreya-type.

There is in the Royal Berlin Museum also a Tibetan miniature on silk which depicts Maitreya (described on a label as Byams-pa) in exactly the same attitude as in the two bronzes, though without attributes and with rich curly hair. Instead of a crown, the figure wears a fillet.

The truthfulness of the Tibetan tradition is shown by a comparison of the illustrations Nos. 82 and 85. The latter picture (from the collection of the brothers Schlagintweit) represents Maitreya as Buddha, *i.e.* in the form in which Lamaism depicts him as a perfected Buddha. His characteristic feature is the hands in front of the breast with the fingers arranged in a mystic position (*mudrā*)—the so-called *dharmachakramudrā*, which Gautama also receives especially in the representations of the sermon at Banāras. This picture is named and has already been published by Schlagintweit (*Buddh. in Tibet*, p. 88). Beside



134. OLD INDIAN BRONZE OF JAMBA (Byams-pa): Maitreya from a monastery at Pekin. Height 8½ inches. Original in Berlin Museum.¹

¹ The title of "Byams-pa" the figure received in Pekin, and it is entered so in the MS. catalogue of the Pander collection. That catalogue was written in Tibetan letters in Pekin. If S. von Oldenburg (*Vostochn. Zam.* 363; *Globus*, 3 Feb. 1900, S. 73) says he is unwilling to speak about the figure as it is difficult to give a decision, I can only emphasize the accuracy of the title.

the chief figure, divinities rather smaller in size are represented as



135. IMAGE OF A BODHISATTVA.
Indian bronze inlaid with silver and copper.
Height 7½ inches. Original in Berlin Mus.

servants, and above are eight small Buddha pictures; the last of these is the same as the middle figure and must therefore be again Maitreya; the preceding one is undoubtedly Gautama. The other six must then be Gautama's predecessors: Vipasyi, Sikhi, Visvabhū, Krakuchchanda, Kanakamuni, Kāsyapa.¹ On the relief from Muhammad Nari, in ill. 82, eight Buddha statues are shown under the middle figure in splendidly composed types. The last of these, which, on the right of the sculpture, is turned towards the human worshippers (perhaps the donors of the relief?) does not wear the robe but has the customary lower garment, curled hair, and a small flask in the left hand: it is Maitreya. The preceding figure is the usual one of Gautama, the others are his six predecessors, as above. This shows that the royal figures of the Gandhâra monasteries with the flask may represent the Bodhisattva Maitreya, and that the Muhammad Nari relief actually does so.

But this sculpture (ill. 82) proves still more: comparison with the Tibet picture shows that the central figure is the same; we may call it Maitreya represented as the Buddha.² Conf. p. 194.

¹ We find the same eight figures painted over the door of Cave XVII and on the wall of the shrine in Cave XXII at Ajanta; in the latter, the names of the Buddhas are given below each, and of their respective Bodhi-trees above them; *Notes on Ajanta Paintings*, pp. 63 and 87; and *Inscriptions from Cave Temples* (Bombay, 1881), p. 88; also Griffiths, *Paintings from Ajanta*, vol. I, pl. lxi and xci, and pp. 36, 40.—J.B.

² Emphatically, we have to do with a Buddha figure with the *dharmaśāstramudra*.

Another result of this examination appears,—that even in the Gāndhāra school had arisen the scheme of distinguishing their saints by the different positions of the hand and fingers. Single types in the life of Buddha become, as it were, permanent attributes for certain figures; thus, the position of the hands before the breast in the so-called *dharmachakramudrā* is really that of the Buddha who 'turns the wheel of the law' (conf p 177). But even in the Gāndhāra school, we find Maitreya in this pose as the Buddha of the future who will yet turn the wheel of the doctrine.

The representation of Kāśyapa-Buddha,¹ the predecessor of Śākyamuni, is of interest. The attitude has not been noticed elsewhere, and was perhaps of no lengthened duration in the Buddhist sculpture of later times. The Berlin Museum possesses a small figure, somewhat chipped, which has doubtless formed part of a relief now destroyed, but which may be related to the figure shown on ill. 82. Kāśyapa's robe fits close to the body, and his right hand wrapped in it clasps it on his breast, while the left holds the falling garment. The other six Buddhas are thrown into the shade by this characteristic type, which in some ways reminds us of the statue of Sophocles in the Lateran.



130. A BODHIRATTVA FROM SWĀT: the head to be completed as in ill. 130. Original in Berlin Museum.

A systematic examination of all the types belonging to this group, along with the few representations to hand of the southern church, cannot be undertaken yet, from the want of available material. Suffice it to say, that even among the sculptures of the This is the most common form in the shrines at Ajantā. In Lamaism Maitreya has always this *mudrā* when he is placed in comparison with Śākyamuni. Conf. Schiefner, *Buddhistische Trilogie*, S. 1.

¹ Not to be confounded with the Brāhmana of the same name mentioned at pp. 62f. For the awakening of Kāśyapa, conf. Schiefner, *Mé. As. Ac. St. Pétersbourg*, tom. VII (1874), pp. 417f.; S. Beal, *Ind. Ant.* vol. XII, p. 328. What is said above only points out that Kāśyapa is found in the above pose, but not that every image so represented must be Kāśyapa; conf. fig. 140 (p 192), right side attendant.

Gāndhāra period, alongside Gautama, Maitreya and Kāśyapa in particular play a prominent part. It may be pointed out that, in the eschatology of northern Buddhism, a highly interesting connexion is established between the two last named. Kāśyapa lies uncorrupted in his stūpa: when Maitreya shall appear on earth, he will rise, work miracles, and disappear in flames,—a legend which strongly reminds us of a Persian (and a Muhammadan) tale.

But here, too, we are perhaps justified in pointing out the striking similarity of the representation of the coming Maitreya



187. BUDDHA FIGURE IN DHARMA-CHAKRAMUDRĀ. From Kadam-kuki Khel in Swāt. Original in Berlin Mus.

with Saoshyant (Sosiōsh), the deliverer in the Pārsī religion. Even though we do not know when the legend of Saoshyant received the development it now presents, still the dominant position of Maitreya in the northern school must have been influenced by it.

The worship of Maitreya must have been fully developed even in the fifth century, for the Chinese pilgrims know a set form of prayer to the Bodhisattva. The Gāndhāra sculptures, corresponding in this with the report of Fah-hian, show the worship at its height.

Tradition connects Maitreya directly with the origin of the Mahāyāna school in representing the Tantras as received from Maitreya by the monk Asaṅga, who is regarded as the founder of the whole later pantheon.¹ The Mahā-

yāna school—the so-called "greater vehicle," no longer seeks after the deliverance of the individual, but for rebirth as a Bodhisattva. These aspirations were developed by the learned character of the monks in the northern system, who regarded the followers of the

¹ On Asaṅga, see Rhys Davids, *Buddhism*, pp. 208f.; Beal, *Si-yu-ki*, vol. I, p. 226; Eitel, s.v.; Schiefner, *Lebensbesch. des Buddha Sakyamuni*, S. 80; Vassilief, *Le Bouddhisme*, pp. 237ff. How far Maitreya is connected with the Mahāyāna school, is witnessed by the following independent proof. Ho-shang, the follower of the Mahāyāna, passes as an incarnation of this Bodhisattva and is always associated with the Lokapālas, which agrees with our remarks, p. 130, &c. *Veröffentl. aus d. Kgl. Mus. für Völkerk.* Bd. I, 2/3, S. 59.

old doctrine with disdain as representatives of the "lesser vehicle" (Hīnayāna). Among the sculptures from the Gāndhāra monasteries, we find such a multitude of figures bearing the Bodhisattva character, that it would be impossible to regard them all as figures of Maitreya, even if we believed that at that period the cult of this Bodhisattva was at its height.

Besides the symbol of the flask (compare the relief, ill. 136, and the hand, ill. 132) we find represented as a favourite attribute in the hands of the Bodhisattva large single blossoms of the lotus flower¹



188. SMALL FIGURE OF A BUDDHA, broken from a relief which has been like that in ill. 82. From Kadam Kuku Khel in Swāt. Original in Berlin Museum.



189. FIGURE OF A BODHISATTVA, with a bunch of lotus flowers in his right, and a vessel in his left hand. Plaster cast in Königl. Mus. f. Völkerk. Berlin.

or whole bunches of such: an attribute that is readily explained by the religious custom (flower offerings). Among Indian sculptures Maitreya is distinguishable by the lotus flower in his hand; I need only refer to the Bauddha figures found at Supārā, which series closes with a Bodhisattva holding only a perfect lotus flower and no vessel. The two attributes—the flowers and flask—are well known from Sāñcht; in the Gāndhāra school, indeed, the antique flask with the pointed bottom takes the place of the round Indian

¹ The lotus flower as Maitreya's emblem is noticed above p. 186, note 1. This is also shown in older art: Bhagvānlāl Indrajī, *Supārā and Padana*, in *Jour. Bom. Br. E.A. Soc.* vol. XV, p. 298, and pl. v. where the whole series proves that Maitreya (and not Padmapāsi) is meant.

lōtā. As has been already noted, modern art in Tibet assigns to Maitreya both symbols, but for the vessel the long-beaked ritual jar (*maṅgalakalāsa*)

We may here notice a broken relief from Kāfikot in Swāt, now in the British Museum (ill 140). The style of art is less educated or cruder than usual. To the left is a Bodhisattva seated on an *āsana*, holding a flask in his left hand, and the right raised in the *abhaya-pāṇi mudrā* this we take to be Maitreya. His breast and



140. BUDDHA AND BODHISATTVA.

Buddha is attended by Sakra and Kāryapa (?); the Bodhisattva is probably Maitreya with an attendant. The fragment is 7½ in. high and about 13½ in. long. Brit. Mus.


right shoulder are bare, but he wears bracelets, necklace, ear-rings, &c., and is attended by a figure with a large bunch of flowers. The rest of the slab is occupied by Sākyamuni, attended on the left by a monk whose right shoulder and arm are covered by his robe, in the style ascribed above to Kāryapa. On his right is Sakra, in this case naked, except for a very scanty loin-cloth; and it is to be noted that, even now, in Nepāl, the Vajra-bearer wears no necklace or other ornaments.

Returning then to the bronze in ill. 135, we see that it represents the same type as the Maitreya in ill. 134. S. von Oldenburg claims ill. 135 for a Padmapāni, and he furnishes proof that it is so, and that, advancing from this, the name of Padmapāni might be applied to some of the Gāndhāra sculptures.¹ But the name Padmapāni is

¹ *Vortacharya Samśti*, pp. 362-3. Oldenburg's doubts about the stūpa in the crown are unfounded: he conjectures ill. 134 to bear an incorrectly copied figure of Amṛtābha; it undoubtedly represents a stūpa. This is an attribute of Padmapāni. *Notes on Ajanta Paintings*, &c., pl. xiv, 1, where the stūpa stands on the shorn head of Buddha. But Maitreya also has a stūpa in his hair; he is thus represented in the unpublished

unfortunately not a proper name, but an adjective in substantive form: "he with the lotus flower in the hand," a round-about name that may be associated with Vajrapāni. This Bodhisattva has always produced new representations, so that to-day it presents the most important figure in the pantheon of Tibet: he is incarnate in the Dalai-Lama.

Still, we must beware of generalizing too hastily; the flask in the hand of a Bodhisattva figure, as S. von Oldenburg has pointed out, does not necessarily indicate Maitreya. The proper *chihna* must decide as to the individual Bodhisattva; and the Amṛita flask appears in modern representations as an attribute of Avalokiteśvara or Padmapāni. We find this in the 11th century in Nepāl;¹ also at Bôrô Budûr,² where the existence of a small figure of a seated Buddha Amitābha on the forehead points distinctly to Avalokiteśvara; at Ajantā,³ we find Avalokiteśvara with a jug or flask in his left hand and a deer-skin over his left shoulder; and again holding the palm of his right hand forward (in the *vara mudrā*), and clasping a flask with oval body and narrow neck in the left. In the caves of Bâgh in Mālwa (ill. 141) also the representation of the same little figure in the head-dress precludes doubt that the representation is that of Avalokiteśvara.⁴ Almost as certainly the



141. AVALOKITEŚVARA.
From Bâgh Caves.



142. A BODHISATTVA.
From Aurangâbâd
Cave Temples.

Narthang print of the "five hundred gods," fol. 85, 1. A magnificent large gilded bronze Maitreya in the Berlin Museum, with the lotus flower, the wheel and a little jar upon it, and with the hands in the *gharmasakra mudrā*, has likewise a stûpa in the crown. But Mahāvastuśāstra has it also,—this Bodhisattva occurring very frequently in pictures representing Amitābha's paradise (Japan) as a companion to Padmapāni (with Amitābha on the crown)—as in the picture from which ill. 124 is taken. Individual Bodhisattva figures are seldom to be distinguished as to their names with absolute certainty. One must start from well-marked groups (triads, &c.) and so seek guidance. It appears as if tradition itself, by the arrangement of Bodhisattva figures in wrong succession, had become uncertain, and so named the individuals incorrectly. The same is the case in the representations of the Arhats—and here the Japanese tradition seems to be the best. Conf. on this J. Burgess, *Ar. Sur. W. Ind.* vol. V, pl. xx, 1, and xix, 6; *Jour. Ind. Art. &c.*, vol. VIII, pp. 85, 83.

¹ A. Foucher, in *Rev. de l'hist. des Religions*, tom. xxx, p. 358ff

² Bôrô-Budûr, Atlas, pl. cclxxxi,

³ Burgess, *Notes on the Buddhist Rock-temples of Ajanta*, pp. 35, 62,

⁴ Burgess, *Arch. Sur. W. Ind.*—Report on Elura Cave-Temples, &c., pl. xx, fig. 2.

Bodhisattva from the Aurangābād caves¹ represented in ill. 142, is the same.

If now we compare fig 135 above, with the Gāndhāra statue represented in ill. 143, Prof. von Oldenburg calls attention to the resemblance,—only the rosary in the left hand is wanting, in its place a lotus blossom appears in the palm: it has a nimbus, but is without a crown.² Ill. 121 is an example of Buddha on the *padmāsana* between two Bodhisattvas, and possibly that on his right held a flask now broken off. It would then appear that, though Maitreya has the flask or jug, it is also an attribute, at least occasionally, of Padmapāni.



143. A BODHISATTVA.—Padmapāni p
Cole, *Græco-Buddh. Sculp.* pl. 25.

We may here also consider the origin of the system at least from the sculptor's side, taking as a starting point a merely descriptive epithet—"he with the lotus flower in the hand." Here the personalities themselves vanish under the touch,—the vaguer the beginnings the more abundantly the attributes multiply in the sequel, and new epithets³ arise, from which again, under certain circumstances, new personages may evolve.

If we accept it as a fact that Padmapāni had become established in Gāndhāra sculpture, it may be asked whether his spiritual father, Amitābha, appears or not. Where later art represents him, he has either the garb and tonsure of a Buddha with the *dhyāna-mudrā* (the hands clasped in the lap), or the garb of a Bodhisattva with the same posture of the hands holding in them a vessel with *Amṛita*. Such Buddha figures actually appear in these sculptures (conf. ill. 82, the Buddha sitting in the frieze), and Bodhisattvas

¹ Burgess, *Arch. Surv. W. Ind. Exp.* vol. III, pl. iv, 1. The scale of drawing deprives us of perfect clearness as to the *śākhā*; but compare also woodcut 8, p. 80.

² *Globe*, 2 Feb. 1900, S. 73-75.

³ For the common epithets and names of Padmapāni or Avalokiteśvara, as Lokeshvara, Trailokeshvara, Padma, Abhayaśāhita, Āryapāla, Chintāchakra, Hāḥḥḥa, Mahākaraṇa, Śaṅkhaśāhita, &c., see *J. B. As. Soc.* (1894) pp. 76ff.; *Notes on Ajanta Paintings*, &c., p. 106f. and pl. xxiv-xxvii. Avalokiteśvara and Mahāsthānaprāpta are both mentioned in the *Sukhāśaṅkha*, §§ 81 and 84, which dates from as early as A.D. 100; conf. *J. B. As. Soc.* vol. XLIX, pt. 1, pp. xxii, 43, 52, and 176.—J.B.

also occur, with both hands in the lap, holding the same little bottle or flask mentioned above. Yet it cannot be asserted with certainty that Amitābha must be meant by these, though it is not improbable. Indeed, if we follow the Japanese tradition, even the middle figure in ill 82 might be Amitābha in Sukhāvati; the side figures would then be Padmapāni and Mahāsthānaprāpta!

We would then have before us here the beginning of the theory of the Dhyāni or meditative Buddhas, which forms the basis of the Mahāyāna doctrine.

Even the southern school recognises four stages of mystic contemplation (Skt. *dhyāna*; Pāli, *jhāna*), which the northern school subsequently increased to five. These five Dhyānas correspond, in the cosmogony, to the series of heavens in five terraces,—the so-called *Brahmalokas*, which rise above the inferior heavens of the gods, *Devalokas* (conf. pp. 60, 61). The theory then arose that each Buddha dwelling on the earth had his mystic counterpart (*Dhyāni-buddha*) in one of the Dhyāni-heavens, and that each of them again had his *Bodhisattva* or successor. Thus, with the five human Buddhas of the present period of the world's existence (*kalpa*), are associated five mystic antitypes in the corresponding Dhyāni degrees with their five successors (*Dhyāni-bodhisattvas*). We have thus the following correspondences:—

<i>Human Buddhas</i> (<i>Mānushi-buddhas</i>)	<i>Dhyāni Buddhas</i> . ¹	<i>Dhyāni Bodhisattvas</i> .
1. Krakucchanda	Vairocana	Samantabhadra
2. Kanakamuni	Akshobhya	Vajrapāni
3. Kāśyapa	Ratnasambhava	Ratnapāni
4. Gautama	Amitābha	Padmapāni
5. Maitreya	Amoghasiddha	Vivapāni

After the advent of Maitreya as Buddha the present world will be destroyed.


Prof. Rhys Davids has called attention to the fact that the whole theory, according to which every human Buddha emanates from his *spiritus rector* (Dhyāni-buddha), bears a resemblance to the æons and emanations of the Gnostics, and he regards it as not impossible that these beings owe their existence to Persian influence. Noteworthy in this connexion is the name "Immeasurable light" given to Amitābha—from whom Gautama is said to have emanated: it points distinctly to contact with the old Persian light worship.

The whole doctrine of the Dhyānibuddhas and Dhyānibodhisattvas appears to rest on the Zoroastrian theory of the *Fravashis* (Fervers). According to the Masdayasnian conception, every being, whether dead, living, or unborn, has his *Fravashi*, which joins itself to the body at birth, and after death intercedes for it. We have thus Iranian influence distinctly before us, which accords with the local surroundings of the Gāndhāra school. It was

¹ See *Notes on Ajanta Paintings*, p. 291., for the *mudrās*, *chakras*, colours and symbols of these *Mātāntara-paścha-Buddhamāyā*; there are also other arrangements in Nepal of six, seven and nine.—J. H.

necessary to touch upon these crude materials, since only in this way can we comprehend the never-ending repetition of Buddha figures in the buildings of later Buddhism.

The Buddhas and Bodhisattvas from the rock-temples at Elurâ, represented in ill. 144 and 145, are of this sort. In ill. 144 we have the Buddha type repeated five times, perhaps for the five Dhyâni-



144. BODHISATTVAS ON THE RIGHT SIDE OF THE SANCTUM IN TIN THÂL.
Burgess, *Rep. on Elurâ Cave Temp.*, *Ar. Sur. W. Ind.* vol. V, pl. xx, 1.

buddhas—all having here the *dhyânamudrâ* (the hands laid one upon another in the lap); though if they represent Dhyâ nibuddhas other *mudrâs* are usually assigned to each, except Amitâbha. Beneath we see five Bodhisattvas in the usual royal garb as in Gandhâra—only more markedly Hindu; they bear lotus flowers, some with special symbols over them, and one has a small flag. Further, the outmost is represented larger than the others and with a *vajra* over the flower he holds: whether he represents Vajrapâni or Mahâsthânaprâpta has perhaps yet to be decided. So in the case of ill. 145, in which eight Bodhisattvas are grouped seated round the Buddha,¹ we might naturally suppose that Padmapâni with the lotus flower, and the little Amitâbha figure in the hail, is the one

¹ *Ar. Sur. W. Ind.* vol. V, pp. 18f. Bunyiu Nanjio was of opinion that the eight here figured are the Hachi-dai-shaku-ehi or "eight great principal sons" [of Buddha], and reading from left to right he made the upper row Durgatiparisodhana, Akshagarbha, and Kshitigarbha; the lower three—Maitreya, Avalokitevara, and Mañjuvâri; with Semantabhadra on the left and Mahâsthânaprâpta to the right of the central figure. With these figures and others at Elurâ, compare those represented in Groneman, *Tijds. Paroch. en Miss. Java*, vol. xlix-lviii.—J.B.

on the left, and Vajrapāṇi is he with the lotus flower and thunderbolt over it.

This is the beginning of a purely formal distinction between figures which are always the same and all based on the same fundamental type—the seated figures gradually predominating very largely. With the varied arrangements of the fingers,—along with the colour of the body and of the garments changed by painting—other names always appear; and in this way an endless and altogether monotonous pantheon arises, with vague, merely allegorical names, and constant change of attributes. Now, as it was considered a salutary act of the best kind to represent as many Buddha figures as possible, all artistic activity naturally decayed, and after a time there were only reproductions of the established type that were more or less good, and more or less influenced by the native style. Rows of Buddha figures were employed in the decoration of temple façades, whole rocks were turned into terrace-reliefs filled with Buddhas, and caves filled with thousands of Buddha statues of all sizes.¹



145. WALL-SCULPTURE in the Tin Thāl (Elurā).
Burgess, *Report on the Elurā Cave Temples, Ar.*
Sur. W. Ind. vol. V, pl. xix, 6.

We now return to what was said in the first chapter. The Hīṇdu idea of the world recognises man, that is the individual, only as a link in a chain of incarnations. These incarnations are phases of metempsychosis (*Saṃsāra*). They are completed in world ages which originate, flourish, deteriorate, and vanish; upon which new ones arise to be annihilated in their turn. For every period there are Buddhas; they appear as emanations from countless Buddhas of the meditative spheres—Dhyānibuddhas. In contrast to this is the western-idea of constant progress, of constant improvement, which leaves the powers of the individual free to act, while the sum of the energy of the individualities forms an effective

We now return to what was said in the first chapter. The Hīṇdu idea of the world recognises man, that is the individual, only as a link in a chain of incarnations. These incarnations are phases of metempsychosis (*Saṃsāra*). They are completed in world ages which originate, flourish, deteriorate, and vanish; upon which new ones arise to be annihilated in their turn. For every period there are Buddhas; they appear as emanations from countless Buddhas of the meditative spheres—Dhyānibuddhas. In contrast to this is the western-idea of constant progress, of constant improvement, which leaves the powers of the individual free to act, while the sum of the energy of the individualities forms an effective

¹ I would refer to the Pegu Caves,—R. C. Temple's *Notes on Antiquities in Rama-ñādesa* (in *Ind. Ant.* vol. XXII, pp. 327ff.), pls. iv-vii. From these caves the Royal Museum, Berlin, possesses more than a hundred figures of Buddha. "In Wu-t'ai-shan, in the province of Shan-hsi in North China, the Yung-kung-szu temple contains 10,000 small tablets with representations of Maitreya. In Ch'an-fo-szu near Peking, I have seen 1,000 beautifully carved reliefs of Amitāyus the god of longevity."—Pander in *Zeitschr. f. Ethnologie*, Bd. XXI (1889), S. 46.

counterpoise to occasional retrogression and relapses into barbarism. It is quite in keeping with the character of the Indian idea of the world that the image, the picture of the founder of the religion is reduplicated to infinity and so loses its individuality. The Buddha-type, the sole subject of a somewhat statuary kind, which was tentatively developed and canonised, is treated decoratively in the façade ornamentation of magnificent temples. In relation to the splendour of these monuments, this figure of the one great man is again lost in repetitions to infinity.

As mentioned above, the religion had struggled through this phase in another form: the counterbalancing element was the return to a kind of monotheism in the shape of the doctrine of Ādibuddha—the primeval Buddha, from which all others emanated. This doctrine had appeared between the 12th and 13th centuries.

With the Gāndhāra sculptures the second period of Buddhist art closed in so far as no new ideas, no new principles of composition appear after that. Still there are some things we may point out, as they were certainly carried over by means of the Gāndhāra school from the antique into Buddhist art. It is well known that the late antique was in favour of the colossal; Buddhist art likewise has the colossal, and, indeed, such are the favourite figures: Buddhas in teaching, standing, recumbent form (passing into Nirvāṇa), and also the statue of Maitreya. It is only necessary to recall the colossal statues at Bāmiyān, made famous by Ritter, to indicate how this form of representation has been adopted in Buddhist art.¹

Another artistic feature, which appears even in the more modern Gāndhāra sculptures, must, at least, be briefly mentioned,—though it is difficult on the basis of the present materials to explain it fully. This is the lotus flower as a seat, or a kind of pedestal of two lotuses under the feet of the upright Buddha. This earlier form, which in the more ancient (Indian) art belonged only to the goddess Sīrī, seems to have been further developed in the Gāndhāra school on the basis of Indian influence. In the case of standing figures it was possibly an illustration of flowery poetical epithets, "lotus-footed," and such like; in the case of sitting figures, the representation perhaps had reference to the meditative attitude called

¹ Ritter, *Die Stupas oder die Architektonischen Denkmale an der Indo-Baktr. Königr.* u. *d. Colosse von Bamiyan*, pp. 24f. Hyde (1700) is perhaps the first European to call attention to these colossal, in *Hist. Relig. vet. Pers.* p. 182. Conf. Kaya in *Proc. R. Geog. Soc.* vol. I (1879) pp. 248ff., and my note in *Beal's Si-yu-ki*, vol. I, p. 51, n. 175. There is a large recumbent figure at Ajanta, Cave XXVI.—*Cave Temples*, p. 344. The Jains also erect colossal statues; conf. *Ind. Ant.* vol. II, pp. 129f., 358f., and vol. V, p. 36.—J.B.

Conf. also on Bāmiyān, M. G. Talbot in *J. R. As. Soc.* N.S., vol. XVIII, pp. 328ff.; other notes from the Chinese pilgrim by Kern, *Buddhismus*, Bd. II, pp. 212ff. The Maitreya colossus at Yung-ho-kang—*Veröffentl. Mus. Volk. Berlin*, Bd. I, 2/3, S. 77; in Lehn, *Waddell, Budd. of Tibet*, pp. 320f., 355, Graham Sandberg, *Handbk. of Colossal Tibetan* (Calo. 1894), p. 127; to these belong the Miryak (i.e. Maitreya) figures of Koyas, *J. R. As. Soc. N.S.* vol. XIX, pp. 555-7; the recumbent Buddha colossus, *Ind. Ant.* vol. XXII, pp. 127ff., pl. xvii, 2b.

"lotus-seat" (*padmāsana*). At any rate, the Buddha standing on lotus flowers appears even at Amarāvati (conf. p. 175) and in the ecclesiastical art of the present day it has become quite a common feature (conf. ill. 82, 85, 123, 124, 140, 141).

Two Bodhisattvas of the later pantheon have a distinctly individual character and thus have afforded material for some fine works which may be mentioned as showing, on the one hand, what was the chief ideal after which Buddhist art strove, and on the other, as clearly evidencing the extraordinary persistency of the Hellenic ideal of Buddha. They are the Bodhisattvas *Mañjuśrī* and *Padmapāni* already mentioned, and which at a later date were so extraordinarily richly developed.

Mañjuśrī, whose name means something like "having a lovely brilliance," may possibly have been a real personage, namely, the founder of civilization in Nepāl. In the system of the northern school he appears as the representative of that transcendental wisdom which is the aim of the Mahāyāna school.

His attributes are the sword "of knowledge," which he wields with his right hand to cleave the clouds of mental darkness (*andhakāra*), and in the left hand he has a book, which usually rests upon a lotus flower.

The relief in the Berlin Museum of a *Mañjuśrī* from Java, according to the inscription on it, was made by *Ādityavarmā* in the year 1265 Saka (i.e. A.D. 1343) and is a fine specimen of modern Buddhist sculpture (ill. 146).¹

The Bodhisattva is sitting on a great lotus flower and leaning against a broad cushion; his legs are drawn up and crossed in the Indian fashion; and he is in rich dress. He wears a highly ornamented crown; ear-rings with pendent chains (conf. the ear-ornaments of the Bodhisattva figure from Gandhāra in ill. 131); neck and breast chains, chain girdle, upper and lower bracelets, finger and toe rings. From behind the crown hang twisted locks of hair. The upper garment lies in a narrow band about the breast, from the left shoulder to the right side. The under garment clings close and smoothly to the legs, and is richly adorned with very interesting figures (conf. ill. 33), the body is well shaped, full, delicate; the breast and ribs are rounded and unmarked by bones or muscles. The feet unused to walking, the soles are soft-like and pressed down to an almost impossible degree. The body in the main is full of charming, almost womanly beauty, and has a look of unnatural development, which does not arise from the physical energy of the being represented. The raised arm only holds the sword aloft, but does not strike—it only serves to hold the attribute. The whole style of the face shows in great purity the Buddha-type mentioned before (p. 160ff.); in it the forms of the Gandhāra school are quite recognisable. The appearance of meditative re-

¹ For the curious history of this sculpture, see *Zeitsch. d. Deutsch. Morgenl. Bd. XVIII* (1884), pp. 494-505.

pose is secured by the nearly-closed eyes, the head pressed back on the nape of the neck, so that the very artificially formed, fleshy neck stands out prominently. The mouth is large but not broad, the under lip full, the upper puckered up at the corners almost to



146. OLD JAVANESE RELIEF OF MAÑJUŚRĪ BODHISATTVA.

Inscribed with the date 1265 Śaka: 1348 A.D. Original in Berlin Mus.

a smile : but the smile seems to be overcome and perfect rest to be attained.

The head is best characterised by the distinctive marks of the fourth and highest degree of meditation (*dhyāna*). According to the ideas of the southern church, the different Dhyānas are as follows :—

1. The first Dhyāna is a state of joy and happiness which have arisen from a life of solitude, yet full of contemplation and enquiry, after the ascetic is freed from all sensuality and fault.

2. The second Dhyāna-degree is a state of joy and happiness, which have arisen from deep peace of mind without contemplation and investigation, both of which are overcome: it is the bringing to rest of thought—the mastery of contemplation.

3. The third Dhyāna-degree is the state in which he becomes patient through joy and the uprooting of every passion,—glad and conscious of the joy which announces “the worthy one,” the arhat: patient, remembering, happy.

4. The fourth degree of Dhyāna is perfect equanimity and remembrance, without care and without joy, after the previous joy and care have ceased through the putting aside of that which gives joy, and after the putting aside of that which brings care.¹

The lotus flowers upon which (in modern Tibetan representations) the book usually rests are employed for the decoration of the background. The tasteful arrangement of the leaves and buds, which are represented artistically and with great understanding of Nature, indicates the ancient Indian manner (conf. p. 19f.). The book, in the usual form of palm-leaf manuscripts, tied round with a string, is held in the left hand. Four smaller figures of Mañjuśrī, very much resembling the principal one, surround it,—above and below, right and left. From analogy with Tibetan pictures, these appear to be intended for other forms of the Bodhisattva. In this way that sort of arrangement is obtained which we have already noted in the Gāndhāra reliefs (conf. pp. 130f.) and which is preserved in the paintings of the northern school. On a Tibetan picture the accessory figures would vary—in respect of the five sacred colours—with the character of the principal subject; and as Mañjuśrī is mostly represented as red, they remain white, yellow, green and blue.² With the modern Tibetan painters these colours must bear a certain proportion to each other on the pictures: above all, the blue (wrathful) forms of the deities must not predominate.

Mañjuśrī, as we have seen, may be regarded, to a certain extent, as the personification of meditation.

Padmapāṇi,—“the all-pitying one,”—is an emanation of Amitābha having appeared on earth from a lotus flower for the deliverance of mankind, he labours to do away with all suffering and all sorrow in all the domain of creation, so that hell is emptied.³ Then he returns to his throne, but soon again he sees misery and hell being filled once more. Out of grief his head bursts, &c.

Through the co-ordination of this personage with Kuan-yin, the Chinese goddess of pity, an interesting type has been formed. I do not refer to the purely Chinese (female) representations of this Bodhisattva, nor of the widespread eleven-headed ones, but of a

¹ But see also Childers, *Pāli Dictionary*, s.v. “jñānam”; Alabaster, *Wheel of the Law*, pp. 192-5; Sp. Hardy, *Legends and Theories*, pp. 178-180.—J. B.

² *Veröffentl. aus dem. Kgl. Mus. f. Völkerk. Berlin*. Bd. I, H. 2/3, S. 75, 146.

³ See the interesting parallel between the early chapters of the *Kāraṇḍa-Vyākhyāna* and the apocryphal *Gospel of Nicodemus*, by Prof. Cowell, *Jour. Philol.* vol. VI (1876), pp. 222-31, or *Ind. Ant.* vol. VIII, pp. 249-53.—J. B.

type which, though derived from Indian forms, is entirely strange to the canon. So represented, the Bodhisattva sits with the right foot drawn up; his right hand rests with the elbow on the right



147. BUDDHA ON THE LOTUS-THrone, WITH ATTENDANT BODHISATTVAS.
From Loriyan Tangai. In Calcutta Museum.

knee, and the head is sunk sorrowfully on the hand, the left hand rests carelessly on the left leg which hangs down. The ornaments and costume, type of the head, &c., continued Indian.¹

Among the Loriyan Tangai sculptures at Calcutta there is a relief that suggests comparison with such a figure. It is on a slab measuring 22 inches in length and 16 inches high (ill. 147). Buddha,


¹ *Cont. Grünwedel, Myth. d. Buddh. in Tibet, &c., S. 27, Abb. 22.*

with features of a somewhat uncommon type, is seated in the centre, on a *padmāsana* or lotus throne, in the attitude of teaching; a flowering plant overshadows him; and above is a canopy of three compartments, of which the two side ones have pointed arches; the joinings and ends of the three roofs are finished with tiger heads; and in each arch, over the head of its occupant, hangs a bunch of pearls or gems. The lotus on which Buddha sits is supported by two small figures rising out of the earth; in the one on the proper right we might be tempted to recognise Vajrapāṇi, but the turban, the covered breast, and roundish or conch-shaped object in his right hand is not in favour of this. A roundish object also lies on the seat in front of Buddha's left knee. The corresponding figure on the other side—with moustache, round object in one hand, and mace (?) in the other—is not identified. Behind the first a shaven-headed monk kneels in adoration; behind the other, the figure appears to be a female.

At each side of the central figure sits a Bodhisattva; that on the proper right probably Mañjuśrī (he "of glorious beauty") holding in his hand the book of Buddha's teaching; and the other attendant is Avalokiteśvara, or Padmapāṇi, with a flower in his left hand. Both these figures are very much in the pose of the Japanese figure just referred to.

The eleven-headed standing form of Avalokiteśvara is very frequent in Nepāl, Tibet, and Japan, and it occurs at an early date in the Kanheri Buddhist cave temples, as well as among the ruins of Nāgārjuna in Kambodia. In this form, as in others, he is represented with four or more arms,—with the upper right hand he holds up a rosary, and with the left a long-stemmed lotus flower (ill. 148). The uppermost head is regarded as that of Amitābha, who is represented as his spiritual origin; the others are arranged above one another, in threes, as in the Hindū Trimurti, and either the lowest head is single, or the tenth counting upwards.¹ In representations with only one head, the figure of Amitābha is placed as a crest on the *mukuta* or crown.

A favourite relief is what may be called the Litany of Avalokiteśvara or Padmapāṇi. It appears in the Bāudhdha caves at Elura, at Aurangābād, at Kanheri, and both in sculpture and painting at Ajantā. In these scenes the Bodhisattva is represented standing on a lotus and holding the rosary in his right hand and a lotus stem



148. AVALOKITEŚVARA.
A form of Padmapāṇi; from
a Nepalese drawing.

¹ *Cave Temples*, p. 857, and pl. iv; *Notes on Ajanta*, &c., p. 100 and pl. xxiv. 11; *Histoire de l'Art du Japon* (Paris, 1900), pls. xvii, xli, p. 911, &c.

in the left; at each side of the panel are representations of suppliants in danger from enraged elephants, from lions, snakes, fire and shipwreck, from murder, captivity, death, &c.,—from which Padmapâni delivers them. These scenes, taken in connexion with the late Mr. Beal's translation from Chinese of the "Confessional service of the great compassionate Kuan-yin," are of much interest, and show that at a date before the eighth century the character of this Bodhisattva must have been fully defined.¹ In other Kanheri sculptures he is attended by a female or Târâ at each side; whether this is connected with the worship of these goddesses as female counterparts of Avalokitesvara, has not been investigated.

The figures of Mañjuśrî and Padmapâni have been dwelt upon as showing how nearly northern Buddhist art approached mere personification. The purely spiritual element so entirely predominates that the human figure has become a mere form. But in the case of these two Bodhisattvas there remains at least a trace of personality, which in other representations—about which something must be said—is completely extinguished. The oldest personification of this kind is the goddess of transcendental knowledge—Prajñâ Pâramitâ (Tib. Sher-p'yin-ma), which, in style, as in worship, is not of much account.²

The final results of this multiplication of forms show a notable degeneration in two directions. On the one hand the limbs no longer suffice to bear all the attributes; several arms, several heads are given to the figure: it is reduplicated in itself. The literal representation of old epithets of strength and splendour probably gave rise to this: words like *Sahasrabâhu*, "the thousand-armed," i.e. "he who has the strength of thousands," and so on, received a purely external meaning. The ancient Indian method, borrowed from West Asia, of determining simple human forms by the appending of attributes,—in itself an altogether inartistic method,—degenerated into something repellant. Therewith real art comes to an end: the figure becomes a mere hieroglyph, the decking out with few or many attributes gives it the name of some religious idea. On the other hand, the chief figures are relieved of certain qualities which appear as particular Bodhisattvas—male and female. One of these goddesses of the latest Buddhism is "the victorious goddess of the skull-protuberance"—*Ushantshaviyayâ*³—"having the intelligence of the most splendid perfect one."

¹ See *Ar. Sur. W. Ind.* vol. III, pp. 75, 76, and pl. liii; vol. IV, p. 51, and pl. xxxiii, 3; *Cave Temples*, p. 357 and pl. lv. 1; *Notes on Ajanta*, &c., p. 42; and, for the "Confessional Service," *J. R. A. S. N.S.* vol. II (1866), pp. 408-25; Grünwedel, *Mythol. des Buddha in Tibet u. Mongol.* 3.65; Waddell, *Lamasism*, pp. 15, 357.—J. B.

² Other mere personifications of early date are Dharma (Buddha's teaching) and Saṅgha (the assembly of monks, the "church"), the goddess of the six syllables (*om mani padme hūm*), &c. Conf. also the beautiful figure of an old Javanese Prajñâ-pâramitâ in *Bijdragen tot de Taal-Land-en Volkenkunde van Nederl. Indië*. 6e Volgr. D. VIII (C. M. Pleyte, *Bijdr. tot de kennis van het Mahâyâna op Java*), fig. 1.

³ Tib. *gTang-lor-gnam-par-nyal-ma*. See above p. 162. Also Grünwedel, *Mythol. des Buddha in Tibet*, &c., 3. 135, 145, 151.

As we have seen, the deities, Bodhisattvas, and Buddhas were represented in Gandhâra in groups of threes, fives, eights,—and it seems as though this arrangement had some influence on their attributes: analogies of composition certainly exist.

The illustration No. 121 from Loryân Tangai, in the Calcutta Museum, is an example of a triad group. The relief is 15 inches broad and presents Buddha upon the *padmāsana* or lotus-seat with a standing Bodhisattva on each side. These can hardly, however, be directly related to the philosophical doctrine of the Ratnatraya as represented by Dharma, Buddha, and Saṃgha,—for these figures are not very prevalent in Nepāl, Tibet, &c. But they are closely connected with the popular worship of the three statues of “the past, present, and future Buddhas” represented by Śākyamuni with Avalokitesvara and Maitreya, and with the other triad of Amitābha or Amitāyus with Avalokitesvara on his left hand and Mahāsthāma on his right. This latter, at least, is an early Mahāyāna arrangement since it is represented in the *Amitāyur-dhyāna Sātra*.¹

The pantheon of the northern school of Buddhism in Tibet, China, and Japan, is the most gigantic in the world, but it is infinitely monotonous. Hardly a single figure shows real life. It is interesting to note how this endless system of models, originated in Tibet, China, and Japan, which, with slight variations of hand-postures, attributes, and colours, is always increasing. It arose from the representation of the monk in China and Japan; in Tibet from the portrait of the hierarch. In the former, the representations of monks, which doubtless began with an ideal portrait of the chief disciples (Sthaviras) and of the ancient magicians, degenerated into caricatures; but in Tibet the real portrait has been developed from the ideal. The Bodhisattvas are always incarnated in the hierarchs of Tibet: Padmapāni is reborn in the Dalai Lama, &c.; but the Bodhisattvas are eternally the same. The different stages of incarnation of the saints, however, present variations in their individuality. The portrait of the grand Lama presents an interesting reaction from the artificial rendering of the regions of the gods. The divine in earthly form, in many cases, breaks through in an exquisite way: the figure remains artificial and does not depart from the canon; but the heads of these hierarchs, on the bronzes and miniatures of the ecclesiastical art, are mostly of real artistic value.

Of the many good examples of this class which the Berlin Royal Museum possesses is the richly-gilt bronze of the spiritual Prince of Tra-shi-lhum-bo (*ḥKra-shis-lhun-po*) Pal-dān-ye-she (*ḍPal-dan-ye-shes*), who died in China in 1779 (conf. ill. 149). The portrait of this interesting man is remarkably fresh and faithful. In

¹ See *Sac. B. E.* vol. XLIX, pt. ii, pp. 176, 180ff. A quite similar relief is represented in *Amarāvati and Jaggayyapeta Stūpas*, p. 12. Mahāsthāma is, not improbably, a Mahāyāna deification or analogue of Maṇḍgalakṛāṇa, the right hand disciple of Gautama. Amitāyus is the *Sambhogakṛāṇa* or reflex spirituality of Amitābha, the corresponding *Manuṣhī Buddha* being Śākyamuni; his Bodhisattva is Padmapāni.—J.B.

the coarsely executed but beautifully arranged garment the last offshoots of the Gāndhāra school are noticeable. It is in keeping with the political power of the Tibetan hierarchy that the representations of the Grand Lamas should take the first place among the objects to



149 THE GRAND LAMA OF TRA-SHI-LHUM-BO PAL-DAN-YL-SHE (dPal-Idan-ye-she) 1737-1779). Gilt bronze from Tibet. The alms-bowl in the left hand is of lapis lazuli. Height 5½ inches. Original in Berlin Museum.

be venerated: the rudeness and persistent religiousness of the people has preserved this from the fate which befell it in China and Japan, forming a brilliant epoch—the caricatures of monks.

The individual element appearing in the portraits of the Lamas surpasses Indian art conditions: it points to the attainments in culture of the people of high Asia. And if we may correctly recognise the Issidones of Herodotus as the people of Tibet, then the modern

¹ *Konrad, Artists von Volkskennern*, in *Ab. d. k. k. Ak. der Wissensch. in Wien*, L. Phil. Cl., Bd. CVI (1888), pp. 715f., 718f.

Buddhist cult supplies a true chart of the progress of culture among these high Asian people, whose lot was connected in so remarkable a way with the Hindûs from the time when the Greeks obtained correct information about India. On the Lamaist altars, beside the relics of a barbarian stage—trumpets of human thigh bones, votive bowls of skulls, tambours of children's skulls—appear Buddha pictures in which traces of late antique artistic elements, still strongly inspiring, have a mystic existence; but beside these are the ideal portraits of the old Indian *pandits* and their successors the Lamas, with their intelligent—or, if we might rather say,—crafty faces. It we bear in mind, however, that they were the representatives of culture in those barbaric lands, that they were able to subdue and tame for ever the Mongols, the fiercest conquerors and warriors in the world, and that too without a religious war,—we can only rejoice that these valuable portraits, in modified antique forms, have been handed down.

The application and conversion of old sacred types to caricatures has appropriated even old compositions. Among these, as an instance, is the representation of the Nirvâna scene. The sketch



150. DEATH OF A WORLDLING.

From a Japanese coloured print, conf. Nos. 70-74.

Original in Berlin Museum

(ill. 150), from a Japanese picture, represents the death of a worldling in this manner. His numerous lady friends, and even a small lapdog, give free expression to their grief over the death of the "gentleman," who, larger than them all, lies before them.


It may be asked what is the use of all the æsthetic debate about "Japanese colour printing" so long as the chief facts are unknown to us, so long as we are not in a position to understand the wit—which here, fortunately, we do.

With reference to the formally conserved antique elements, outside India,—as was already noted in connexion with Indian ornaments,—a noteworthy phenomenon occurs: In India, foreign forms get merged in national ones; metamorphosed in all sorts of ways, they have held a long and highly varied existence, carried down into the Brahmanic art of the Middle Ages; while in lands outside India, the canon developed from the Gândhâra sculptures is more closely

conserved. We need only note the markedly antique elements still visible in the Javanese Buddha and Bodhisattva heads (ill. 115 and 146) compared with the Gāndhāra types (ill. 110, 111), or the Chino-Japanese arrangement of the garments (ill. 120, 125). The whole phenomenon is connected with language which, I believe, gave rise to the learned and hierarchical character of the northern monastic system. The southern school adhered to the Pāli language, because the current Prākṛita dialects of India proper were mutually intelligible enough, and the development of culture was common to all. Transitions between the Prākṛits existed just as certainly as between the modern idioms of Aryan origin in northern India. But the people of the Panjāb had not followed the Brahmanic development (conf. above p. 7), and even if in some lands under the Indo-Skythian rule, Aryan dialects were spoken, they undoubtedly became widely different. To them came the entirely allophylian tribes of the Indo-Skythian kingdom—Hellenes, Yueh-chis, the tribes of Dardistān, Kashmīr, Persians, Turks from the east, etc. For this reason, Sanskrīt, the language of the learned in the north, was chosen at Jālandhara for the language of the sacred texts. From that time onwards, even among the Lamas of Tibet and of remoter Mongolia, it has enjoyed an artistic life, which did not, however, continue free from error. In both cases the classical form veiled the greater decay of the original doctrine. The only individual elements which we meet with are the Lama portraits. But they are persons represented, not representers. The names of the artists are wanting. The forms are foreign: foreign people had executed the most important works; even at the present day mechanical occupations are in the hands of exclusive castes that originated in a mixing of races. The result was that art was not popular, that the Indian people in the mass continued indifferent to such matters. The peasant class, the core of Hinduism, continued in its primitive condition. Among primitive peoples, he who can carve a figure is by virtue of that fact a magician. What must have been the effect when the foreign artist covered buildings of quite a novel sort with decoration in a fixed style,—of hybrid creatures, etc., or found means to bring the image of the universally venerated Emancipator down from heaven! This explains why the Tibetan historian Tāranātha speaks of the ancient buildings as having been erected by Yakshas (fairies) and Nāgas (snake-demons). These names conceal those of the foreign artists. A similar state of things, founded on analogous facts, arose in the German middle ages. The builders of the first cathedrals were, for the most part, foreigners; the people regarded them as super-human—as in league with the Evil One. More than one architectural or plastic monument of the early middle ages has received a traditional explanation which, apart from the humorous element, reminds us of the Jātaka fable related above. The fact that Greek architectural anecdotes were also directly received, belongs to literary history.

An Indian element which soon appears is, as we have noted, the repetition of the same forms, it is parallel with the like phenomenon in the texts; the mystic magical power of the ritual text with its repetitions,—always regarded as of great importance in India,—led to the general disintegration in later Buddhist literature. The repetitions of the motifs brought about the dissolution also of Buddhist art.

Naturally, it was not possible to shake off fixed, influential attributes and to express the character of a mythological being by a corresponding representation of the body, such as Athens attained to when at the height of its glory. Still attempts at it are not wanting; India was not so distant from it in its warm appreciation of Nature. If we consider the representations of the Nāgas, and especially the Nāgas as the reliefs at Amarāvati (ill. 8) and the paintings of Ajantā (conf Griffith, *Ajantā* vol. I, pl 12) show them to us, we cannot fail to see in the excessively twisted bodies attempts to impart to them the characteristic of the body of the snake. In spite of this, the old attribute—a snake's hood on the neck—was naturally not to be omitted.




151 THE COFFIN OF GAUTAMA.

From a stūpa at Nālā near Sughān, excavated by Major Cole, 1888.

From a photograph.

In conclusion, we may append two or three further illustrations which differ somewhat from those already given.

Notice has already been directed (pp 113, 119, 122) to a figure which appears at the feet of the dying sage in most of the representations (ill 70-77). Since these pages were printed off, I have



152 MODEL SHRIK from Loryān Tangai, in Swāt district. Original in Calcutta Museum.

come upon a photograph of a relief (ill 151) from a stūpa at Nālā near Sanghāo.¹ It measures 13 inches in length by 11½ high, and is quite a unique representation. The trees behind and the figure on the right with the bed on which it rests, identify the box, with three monks beyond it, as the coffin of Buddha. And, the figure at the foot, being saluted by one of the monks, as if he had just arrived, seems to support the conjecture already made, that this may be Mahā-Kāśyapa, before whose arrival it was found impossible to remove the corpse for cremation.² This Kāśyapa was a Brāhmana of Magadha or Bihār, and the chief survivor of the eighty principal disciples or *Sthaviras*. On his arrival at Kusinārā, where Gautama died, having bared his right shoulder,—it is said the corpse put the feet out from the wrappings for Kāśyapa to worship; other versions say he changed the garments that enshrouded the body for others from his own store, and having replaced the cover of the coffin, the fire burst forth from the pile and consumed the

¹ "Sent to Tabor Museum, Dec. 1888,—No. 81-10 in Major Cole's Catalogue." This is all the information I have found respecting this sculpture.

² Cf. Const. S. Hardy, *Man. Budd.* p. 360f.

body.¹ After this, Kāśyapa convened the first Buddhist council for the settlement of the canon; and is reckoned as the first Patriarch. Sāriputra and Maudgalyāyana—the right and left hand *Sihaviras*,—had died before Gautama

In the museum at Bombay are two representations of the Nirvāṇa scene from Marjan stūpa near Miyan Khān. The best preserved is on a slab measuring 22 inches by 15, having a broad pilaster at each end. This personage there appears placing his hand against the foot of the figure of Gautama and inclining his head, as if reverencing the dead. This seems to support the probability that Kāśyapa is intended. Vajrapāṇi stands behind him, holding the *vajra* between his wrist and armpit, the seated figure and tripod appear in front of the bed; and those behind it are Devas with naked busts.

The sculpture represented in ill 152, came from Loriyan Tangai in the Swāt district, and is in the Calcutta Museum. It measures 2 feet 9 inches in height and 15 inches across. As will be noted, it is cut quite through the slab round the central figure. It is a remarkably fine piece of sculpture, and must have been regarded as a sort of altar. The central figure is, of course, the Buddha on the *padmasana*, in the teaching attitude; his right shoulder and arm are bare, and the robe is very carefully traced out. Over his head is a sort of canopy from which hangs a garland of flowers in a double loop, descending to touch the *ushnīsha*, resembling a *krobylos*, on his head. On each side, supporting the canopy, is a Persepolitan pillar with humped bullocks on their capitals; the base and shaft are only a slightly enriched copy of the pillars we find at Nāsik in the second century A.D. On the architrave above them are animal heads and the Buddhist rail or lattice pattern. Outside the pillars sit two Bodhisattvas—probably the same as in preceding examples. From above the architrave people (or Devas) look down, and over these is a cornice, supporting a small model of a temple at each end, in which sit two Buddhas. The central space is in two tiers,—the lower having two small figures of seated Buddhas and worshippers; the upper, an arched panel, contains a standing Buddha and two companions. Below the main figures is a cornice over a frieze ornamented by little figures carrying a great flower roll, such as is so common at Amarāvati, with a worshipping figure at each end. The stone fits into a socket in a base covered with a leaf-pattern.²

Lastly, from among the many detached pieces of sculpture from the Swāt districts, of some of which we have only photographs by Mr. Caddy, while the originals do not seem to have reached the Indian Museum, two more are represented (fig. 153). The measurements are, of course, unknown, but the head of Buddha appears to be of some size, and is a strikingly good piece of workmanship, showing the Gāndhāra style of art at about its best. The face is distinctly

¹ Rockhill, *Life of Buddha*, pp. 144, 145.

² *Jour. Ind. Art and Industry*, vol. VIII, p. 88.

less Indian than usual, but dignified and calm; the *ushnîsha* is again manipulated into a sort of Greek *krobylos*, and the ear-lobes, so



155. HEAD OF BUDDHA AND FRAGMENT OF SCULPTURE, from Swât.
From a photograph.

far as the photograph indicates, are not lengthened downwards in the usual way.¹ It may be compared with the illustrations Nos. 110-119, 121, 122, and 131.—J.B.

The foregoing sketch of the Gāndhāra school has been carried as far as is possible with the scanty materials to hand. it is a programme which demands long and continuous work. The last word has not yet been said, for the treatment in detail can only be carried out in India,—and especially in the museums of Lahor, Calcutta, and Peshāwar.

The results of the above investigations may be summed up somewhat as follows:—

1. Talent in sculptural art exists only in a limited degree among the Indian Aryans. The capacity for plastically developing perfect figures is wanting, as is also the feeling for well-proportioned composition. On the other hand a powerful poetic tendency is

¹ *Journal of the Asiatic Society of India*, Vol. VIII, p. 87.

evidenced, which, under the influences of tropical nature, readily borrows images from natural life, and, to the detriment of the composition, executes these broadly, idyllically, but with a fine emphasizing of the characteristic features. The gift of observation, sharpened by speculative training, leads to the humorous depicting of situations which very happily show the marked differences between the various classes of the people, and even ventures upon religious representations; but, notwithstanding this, the whole world of ideas remains subject to the religio-philosophic conception. The character of the people wavers between sensuality and pessimism.

2. The Greek influences shown by the art of the Asoka period follow in the track of older and very energetic Persian influences. This rôle of intermediary on the part of the Persian kingdom is, in a general way, characterized by Herodotos and Ktesias.

3. West Asian forms—the attribute of the thunderbolt, the so-called orientalizing of animals—afford types for Hindû gods and other mythological beings of the older school. The fabulous Indian animals mentioned by Herodotos, Ktesias, etc., belong to this category (conf. p. 42ff.) The wings of the hybrid animals sometimes appear in action (see pp. 48, 53); sometimes as flames.

4. The Gândhâra school represents a long development which begins with antique (heathen) forms and seems to end with Christian ones. The reliefs preserved are, indeed, for the most part, replicas of old models which are entirely based on Grecian composition laws, as, for example, the Bodhisattva at the gate (p. 98). In respect of style, the Gândhâra school is influenced by the more ancient one; as, for example, in the Nâch girl (p. 111), and Persian pillars (p. 151f.).

5. Hellenic deities in the character of the times of Alexander (*i. e.* local divinities) are traceable in Gandhâra: the god of the gate (p. 95), the earth goddess (p. 98), the gods that look down and which perhaps imply a date (p. 129f.). The following Greek divinities exist latent,—Zeus (p. 91), Gê (p. 100), Païnia (p. 148), Nikê (?) (p. 113). Athenê Promachos is directly represented as a Greek goddess. Apollo served as a pattern for Buddha (p. 164).

6. These Grecian representations have exercised a distinct influence on the texts of the northern school; for example, Vajrapâni (p. 91f.), and the Mahâpathavi (p. 100). Certain texts (such as the *Lalitâ Vistara*) are, so to speak, descriptions of reliefs or pictures.

7. The Buddha type, which, in China, passes as that of the king Udayana, reverts indirectly to the Gândhâra type (p. 170).

8. The types of the Gândhâra school (as well as the Grecian mode of composition) are still traceable in the Buddhist ecclesiastical art, as well as in the Buddhist schools of Tibet, China, and Japan.¹

¹ Palaeologue, *L'art Chinois*, is certainly right as to Chinese art and its so-called mythology, which offers merely schemes without a history and gives no new interpretation to Buddhist elements. The prince in gala costume, stiff and motionless, with the little tablet; the officer (wrestler); the two-sword juggler; and the long-bearded old man in dressing-gown,—represent nearly all the national Chinese types, which always recur.

The iconographical texts of the canonical literature of Tibet, as also the materials accumulated in illustrated Chinese encyclopædias, and certain portions of the Tantra (Sanskrit) literature, will require to be worked, by the aid of the monuments, into a history of types:—in the preceding, only a sketch has been attempted.

9. In many sculptures of the Gāndhāra school, the pictorial element is so strongly in evidence that one might imagine that an early school of painting had existed in Gandhāra, whose extreme offshoot is represented to some extent in the Tibetan ecclesiastical paintings; for example, the nimbus (p.86), and the reliefs of "the flight of the Bodhisattva," "the birth of Gautama" (pp 112f., 135). Conf. in this connexion, F. W. C. Müller, *Japanisches aus Java, Feestbundel aan Dr. P. J. Veth aangeboden*, S. 223, and Julien, *Houen Thsang*, tom. I, p. 110



BUDDHA TEACHING IN A VIRĀRA.
From a wall-painting in Cave XVI at Ajanta.
See *Cave-Temples*, p. 308.



WALL PAINTING FROM CAVE XVIII AT AJANTA.
Perhaps Apsarās flying through the air.
(*Cave Temples*, p. 810f., *Mrs. Spier's Life in Ant
India*, p. 370).

BIBLIOGRAPHY.

- Archæological Survey of India,—Gen. Cunningham's Reports.
Archæological Survey of Western India, vols. I—V. Burgess.
Archæol. Survey of Southern India: Burgess, Report on Amarāvati Stūpa, &c.
Archæologische Zeitung
Epigraphia Indica, vols. I and II.
Indian Antiquary.
Journal of the American Oriental Society.
Journal Asiatique.
Journal of the Asiatic Society of Bengal.
Journal of the Bombay Branch of the Royal Asiatic Society.
Journal of the Royal Asiatic Society of Great Britain and Ireland.
Journal of Indian Art and Industry,—vol. VIII (1899).
Journal of the Royal Institute of British Architects (1894).
Veröffentlichungen aus dem Kgl. Museum für Völkerkunde, Berlin.
Wiener Zeitschrift für die Kunde des Morgenlandes
Zapiski Vostochnago otdeleniia Imperatorskago Russkago arheologicheskogo
obschestva.
Zeitschrift der Deutschen Morgenländischen Gesellschaft.
J. Abbot, Note on a small Indo-Greek sculpture; *J. A. S. Ben.* vol. XXVII, p. 262
Indo-Grecian sculptures from the N.W. Frontier, *ib.* vol. XXIII, p. 391. On a
sculpture from the site of Bucephala, *ib.* vol. XVI, p. 604f.
John Anderson, Catalogue and Handbook of the Archæological Collections in the
India Museum; 2 parts; Calcutta, 1898.
Radan-Powell, Memorandum on the sculptures found in the Lahore Museum (not
seen).

- E. Clive Bayley: Notes on some sculptures found in the district of Peshāwar, *J. A. S. Ben.* vol. XXI, p. 603-621. Remarks on Babu Rājendra Lal Mitra's article on some Baktro-Buddhist relics from Bāwalpindi, *ib.* vol. XXXI, p. 184.
- S. Beal: Some remarks on the great tope at Śāhi, *J. E. As. Soc.* N.S. vol. V, pp. 164f. Legend of Dīpaṅkara Buddha, *ib.* vol. VI, pp. 377f.
- H. W. Bellew: General Report on the Yusufzai, Lahor, 1884, pp. 109-151.
- Bhagwan Lal Iddrajī, Ph.D.: Antiquarian Remains at Sopārā and Padana, *J. Rom. E. R. As. Soc.* 1882; and separately.
- J. Bird: Historical Researches on the Buddha and Jain Religions, 1847.
- Th. Bloch: Buddha worshipped by Indra, *Proc. A. S. Beng.* 1898, pp. 186-89. An inscribed Buddhist statue from Srāvastī, *J. As. S. Beng.* vol. LXXVII, pp. 174-205.
- G. Bühler: Ueber neue epigraphische Funde aus den N. W. Indien, *Anzeiger d. k. k. A. d. Wiss. zu Wien*, phil.-hist. Kl. Bd. XXXV (1898), S. 12-17. Ueber ein græco-buddh. Piedestal, *ib.*, Bd. XXXIII (1896), S. 64-67. Three Buddhist inscriptions from Swāt, *Epig. Ind.* vol. I, pp. 183-85. A new Karoshthī inscription from Swāt, *Wien. Zeitsch. f. d. Kunde d. Morgenlandes*, Bd. X, S. 51-58. The date of the Græco-buddhist pedestal of Hastnagar, *Ind. Ant.* vol. XX, p. 394; *conf.* vol. XXI, p. 186f.
- Jas. Burgess: Notes on Amarāvati Stūpa, *Ar. Sur. S. Ind.* No. 8, Madras, 1882. The Gāndhār Sculptures, *Jour. Ind. Art and Industry*, vol. VIII, Nos. 62, 63, and 69. Notes on the Buddha Rock-Temples of Ajantā, their paintings and sculptures, and on the paintings of the Bāgh caves, modern Buddha mythology, &c. (Bombay, 1879); *Arch. Sur. W. Ind.* No. 9. Report on the Buddhist Cave Temples and their inscriptions; Lond. 1883. Report on the Elura Cave-Temples, and the Brahmanical and Jaina Temples in Western India; Lond. 1883. Report on the Amarāvati and Jaggayyapeta Buddhist Stūpas; Lond. 1887. Report on the Antiquities of Bidar and Aurangabad districts; Lond. 1878. The Ancient Monuments, Temples and Sculptures of India, Part I, Lond. W. Griggs, (1897), plates 5-151. *Jour. R. Inst. Br. Arch.* 1894, pp. 112f., 144.
- Henry H. Cole: Memorandum on Ancient Monuments in Yusufzai; Simla, 1883; repr. in Second Report, pp. cxiv-cxxviii. Preservation of National Monuments, India: Græco-Buddhist Sculptures from Yusufzai, 1886; and Great Buddhist Tope at Śāhi, 1886.
- Alexander Cunningham: The Stūpa of Isharhut; Lond. 1879. The Bhilsa Topes; Lond. 1854. Mahābodhi, or the Great Buddhist Temple at Buddhagayā; Lond. 1892. Reports of the Archaeological Survey of India, especially vol. I (1871): *Gayā*, pp. 1-18 (*conf.* vol. III, pp. 79ff); vol. II, Peshāwar, &c.; vol. V, Yusufzai district; and vol. XIV (1882), Panjāb.
- Ernst Curtius: Die griechische Kunst in Indien, *Archaeol. Zeit.* N.F. Bd. VIII, S. 90ff. (1876), and in *Gesammelte Abhandl.* Bd. II, S. 235-243.
- Harold A. Deane: Note on Udayān and Gandhār, *J. E. As. Soc.* 1896, pp. 655-675, and 1898, p. 460.
- James Fergusson: History of Indian and Eastern Architecture, Lond. 1876. Tree and Serpent Worship, 2d ed. 1873, *conf.* *Ind. Ant.* vol. III, p. 69. Archaeology in India, Lond. 1884. Age of Indian Caves and Temples, *Ind. Ant.* vol. I, p. 257f. On the Rock-Temples of India, *J. E. As. Soc.* vol. VIII (1846), pp. 30-32. On the identification of the portrait of Khosroes among the paintings in the Ajanta Caves, *J. E. As. Soc.* vol. XI (1879), pp. 166-68; *conf.* *Ar. Sur. W. Ind.* No. 9. Description of the Amarāvati Tope at Giantur; *J. R. As. Soc.* vol. III (1868).
- James Fergusson and Jas. Burgess: The Cave-Temples of India, Lond. 1880.
- Alfred Foucher: L'art bouddhique dans l'Inde d'après un livre récent, *Rev. de l'hist. des religions*, t. XXX, pp. 318-371. Étude sur l'iconographie bouddhique de l'Inde, Paris, 1900. Catalogue des peintures néespal, et tibét. de la collection H.-H. Hodgson, Paris, 1897. Les scènes figurées de la légende du Bouddha, *J. As.* 9 sér. t. VII, 1898. Études de critique et d'histoire, Sér. II, pp. 101-118.

- R. Friedrich: Ueber zwei Inschriften auf einem Bilde des Mañjuśrī jetzt im Neuen Museum zu Berlin, *Zeitsch. d. Deut. Morgenl.* Bd. XVIII (1864).
- A. Fuhrer: Indoskithic Architecture and Sculpture of the Mathura School, *Jour. Ind. Art and Ind. vol. V*, p. 58. Monograph on Buddha Sakyanum's Birthplace, Allahabad, 1897.
- Percy Gardner: Greek and Skithic Kings of Baktria and India: Catalogue of Indian Coins in the British Museum, Lond. 1886.
- Goblet d'Alviella: Des influences classiques dans l'art de l'Inde; Bruxelles, 1897. Les Grecs dans l'Inde, *ib.* Ce que l'Inde doit à la Grèce; Paris, 1897.
- G. A. Grierson: On a stone image of the Buddha found at Rajāgrha, *J. As. Soc. Ben.* vol. LXIII, pt. 1, pp. 35-38.
- John Griffiths: The Paintings in the Buddhist Cave-Temples of Ajuntā, 2 vols., Lond. 1896.
On the Ajuntā frescoes, *conf. Ind. Ant.* vol. I (1872) p. 334, vol. II pp. 152-153; vol. III, pp. 25-28, 269ff., vol. IV, pp. 232, 339, *J. R. As. Soc.* vol. XI (1879), pp. 156-168; *Ar. Sur W. Ind.* No. 9; *J. A. S. Ben.* vol. V, pp. 557-611f.
- Lepel Griffin: Famous Monuments of Central India, London, 1886.
- F. S. Growse: Supposed Greek Sculpture at Mathurā, *J. As. S. Beng.* vol. XLIV, pp. 212f.; or Mathurā, a District Memoir, p. 156f.
- Albert Grünwedel: Mythologie des Buddhismus in Tibet und der Mongolei, Leipzig, 1900.
- F. Hirth: Ueber fremde Einflüsse in der chinesischen Kunst, München, 1896; or *Jahresber. d. geogr. Gesellsch.* 1896, S. 223-288.
- J. Lockwood Kipling: The classical influence in the architecture of the Indus region and Afghanistan, *J. R. Inst. Br. Arch.* vol. I (1894), pp. 134ff.
- G. Kizariokij: Chotansejja drevnosti iz sobranja N. F. Petrovskago, *Zap. IX*, 187ff.
- D. Klementz, W. Radloff: Nachrichten über die von der Kaiserl. Acad. der Wissensch. zu St. Petersburg in Jahre 1898 ausgesandte Expedition nach Turfan. Hft. L., St. Petersburg, 1899.
- Dr. Leitner: Græco-Buddhist Sculpture, *As. Quart. Rev.* 2d ed. vol. VII (1894), pp. 180-89. Alt- und Neu-indische Kunstgegenstände aus Prof. Leitner's jüngster Sammlung. K. K. österr. Mus. für Kunst und Industrie; Wien, 1893. Dr. Leitner's Græco-Buddhist Sculptures, *Ind. Ant.* vol. II, p. 242ff.
- Sylvain Lévi: Notes sur les Indo-Scythes, *Jour. As.* 9 sér. t. VIII (1896), pp. 144-84, and t. IX, pp. 5-12.
- Rev. W. Löwenthal: Account of some of the Sculptures in the Peshawar Museum, *J. As. S. Ben.* vol. XXXI (1862), p. 111.
- F. C. Mailey: Sanchi and its remains, Lond. 1892.
- I. P. Minayeff: Recherches sur le Bouddhisme (Ann. du Mus. Guimet), Paris, 1894.
- Sergius von Oldenburg: Zametki o buddijskom iskusstve, Vostochnyja Zametki; St. Petersburg, 1896. See *Jour. Amer. Or. Soc.* vol. XVIII, pp. 183-201. Scena iz legendy carja Asoki, *Zap. IX*.
- Tavernor Perry: The classical influence in Indian Architecture, *J. R. Inst. Br. Arch.* vol. I (1894), p. 147ff.
- Bābū Rajendralāla Mitra: Buddhagaya, the hermitage of Sākyamuni (Calc. 1878. The so-called Dhayuz at Sanchi, *Ind. Ant.* vol. I, pp. 36-40.
- Alex. Rea: South Indian Buddhist Antiquities: including the Stūpas of Bhāṭṭi-prōḥa, Gudiavāḍa and Ghantasāla, and other ancient sites in the Krishnā District; Madras 1894.
- Ritter: Die Stūpas (Topes) oder die architektonischen Denkmale an der indo-baktrischen Königstrasse und die Kolosse von Bamiyan, Berlin, 1898.

- Émile Senart: Notes d'Épigraphie Indienne, *Jo. As.*—especially 3, De quelques monuments indo-bactriennes, *J. As.* 8me sér. t. XV, pp. 113-163; and 7, Deux épigraphes du Svât, 9me sér. t. XIII, pp. 526-37, 555.
- R. Sewell: Report on the Amarâvati tope, 1877. See *Ind. Ant.* vol X, p 56. Early Buddhist symbolism, *J. R. As. Soc.* N.S. vol. XVIII, p. 364ff. Some Buddhist bronzes and relics, *J.R.A.S.* 1895, pp. 617-62.
- William Simpson: Buddhist Architecture—Jellalâbâd, *Tr. R. Inst. Br. Arch.*, 1879-80, pp. 37-64; Indian Architecture, *ib.* 1861-2, pp 165-178. Classical Influence in the Architecture of the Indus region and Afghanistan, *Jo. R. I. B. A.* (1894), pp. 93-112, 191ff. The Buddhist Caves of Afghanistan, *J. R. As. S. N. S.* vol. XIV, pp. 319-331. Some suggestions of origin in Indian architecture, *ib.* vol. XX, pp. 49-71. The Buddhist Praying-Wheel (Lond. 1896).
- Wm. F. Sinclair: Architecture in India, *J.R.A.S.* N.S. vol. XX, pp. 272-76.
- Vincent A. Smith: Græco-Roman influence on the civilization of ancient India, *J. As. S. Ben.* vol. LVIII, pt. i, pp. 107-198; vol. LXI, pp. 50-76; vol. LXII, pp. 84-87. The date of the Græco-Buddhist Pedestal from Hashtnagar, *Ind. Ant.* vol. XXI, p. 166f; conf. Bühler, *ib.* vol. XX, p. 394.
- V. A. Smith and W. Hoey: Ancient Buddhist statuettes, &c., *J. As. S. Ben.* vol. LXIV, pt. i, pp. 155-62.
- R. Phené Spiers: Classical influence in Indian architecture, *J. R. Inst. Br. Arch.* 1894, p. 150ff.
- M. Aurel Stein: Zoroastrian deities on Indo-Scythian coins, *Ind. Ant.* vol. XVII, pp. 89-97. Detailed Report of an Archaeological Tour with the Buner Field-Force, Lahor 1898; conf. *Ind. Ant.* vol. XXVIII.
- M. G. Talbot: The Rock-caves and Statues of Bâmban, *J. R. As. S. N. S.* vol. XVIII, pp. 323ff.
- N. W. Thomas: On a pictorial representation of the Wheel of Life from Japan,—*Mind*, Jan. 1901.
- Dr. L. A. Waddell: Græco-Buddhist Sculptures in Swât, *Imp. As. Quart. Rev.* Jan. 1896; conf. *Actes Or. Cong. Paris*, sec. 1, pp. 245-7. The Indian Buddhist cult of Avalokita and his consort Târâ, *J. R. A. S.* 1891, pp. 51ff. Buddha's Secret from a 6th century pictorial commentary and Tibetan tradition, *ib.* pp. 367ff. The Buddhism of Tibet, Lond. 1895.
- S. J. Warren: Two bas-reliefs of the Stûpa of Bharhut, Leiden 1890.
- H. H. Wilson. Ariana Antiqua, London 1841.



Bas-relief from KUOTAN,
in the collection of N. F. Patrovskiy,
(*Opisaniya*, 8 Feb. 1900).

INDEX.

A.

- Abdagases, King, 78.
 Abn, Mount, 29.
abhaya-pāni mudra, 192.
abhinishkramana, or flight of Gautama from home, 130; date 131.
acacia sirisa, 181n.
 Achæmenides, *see* Cyrus, Darius, Artaxerxes, 4, 7, 8, 9; first universal kingdom, 168; inscriptions of the A. 16; style of their buildings, 2, 17, 81.
 Adam's Peak or Sumanakūta, 72.
 Ādibuddha, 198.
 Adityavarmā, Javanese king, 199.
 Adrastoi, Skt. *Arāshtra*, 8.
 æons of the Gnostics, 195.
 Ahmadābād, 29.
 Ahryman of the Persians, 39.
 Ārāvāta, Indra's elephant, 38.
 Ajanta Cave-temples, 22f.; Paintings, 27, 97, 136, 139, 147, 188n.; Nāgas with twisted bodies, 43, 45, 209; Māra's attack on Buddha, 97; representation of the Nirvāṇa, 113, 120; 198n.; *Garuḍas* from A. 51; tribute-bearers, 186; *Avālokiteśvara*, 193.
 Ajātasattu, Pāli: *Ajātasattu*, king of Rājagṛha, 4, 15, 54.
 Ajita, Maitreya, 183, 184.
 Akāśgarbha bodhisattva, 184, 185, 196.
 Akṣobhya, Dhyaṇibuddha of Vajrapāni, 195.
 Alabaster, C., 161n., 185n.
 Alawakī Yaksha, 45.
 Alakappa town, 15.
 Alexander the Great, 4, 10, 15, 76, 78.
 Ali Masjid stūpa, 152.
 Āmrahvalī stūpa and railings, 22, 26, 27; Buddha appears, 174, 175, standing on a lotus, 199; the nimbus, 86; the *rajra*-bearer, 175; garland-bearers, 118f., 156; early Indian throneseats, 28, 29, 53; departure of the Bodhisattva at A. 103; Māyā, 112; Kāśyapa legend, 128; rosettes, 149; erotic figures, 157; the seven jewels, 159; attempt to express the deity in bodily form, 203.
amataṃ padmaṃ (Pāli), 179.
 Ambaśīlu Brahmana, 90.
 Ameshasponds, Persian archangels, 38.
 Amitābha, conf. *Sukhāvartī*, 186. Persian elements in the cult of A. 195f.; Dhyaṇibuddha of Padmapāni, 198, 199, 196, 201; A.'s paradise, 170, 176, 196; A. in the crown of Padmapāni, 193, 196.
 Amitāyus, 204n., 205.
 Amoghasiddha, Dhyaṇibuddha of Viśākhā, 52, 195.
 Āmṛta, 193, 194.
 Ananda, artist of a relief at Sāñicht, 25n.
 Ananda, favourite disciple of Buddha, 56, 114, 118, 122, 182.
 Ananta cave-temple, 41.
 Anāthapindada, 46.
 Anavāmā river, Pāli: *Anomā*, 14.
 Anoyra temple, 153.
andhakāra (Skt. Pāli), 199.
aṅgavastram (Skt.), 85.
aṅgiya (Hindi), 85.
 Aniruddha, 122.
aijali, 186n.
aijana (Skt. Pāli) "eye-salve," 161.
 Anomā, *see* Anavāmā.
 Antiochos Theos, 77.
 Anurādhapura, 74.
anurayaṇa-lakṣaṇas, marks of the Buddha, 161.
 Apālā Nāga, 43.
 Aphrodite, 40, 67.
 Apollo, 16, 137n, 164-166, 213.
 Apollonius of Tyana, 79n.
 Aquo Solis, Bath, 93.
 Arakhsia, Harahvati, Sarasvatī, 10, 105.
arasa (Tamil) 32n.
 Arāshtra, 8.
 Aravāta Nāga, 77.
 architectural elements, 129, 151f.
arhat (Skt.) 201.
 Aristæas, 34, 200n.
 Arischi Bordschi Ohsa, 63n.
 Arnold (Sir E.) 100n. 125n.
 Arsakes, Parthian king, 4.
 Artaxerxes Mnemon, 58.
 Ārya: the A. in the Penjāb, 6-8, 31; on the Ganges, 10; mythology of the A. 7; stone buildings, gold ornaments, 8; Indian Ā and Iranians, 6, 15; first idea of universal rule, 158.
āraṇa, seat, throne, 192.
 Asaṅga, a monk, 190.

- ascetics, 12, 13, 61, 95, 146; conf. Kāśyapa, Uruvilvā, Rāhmana.
Āśhādāha, Pāli: *Āśāha*, 131.
ashādāga (Skt.) 81.
Asita Rishi, 13, 139, 153.
Asoka, Pāli: *Asoka*, conf. *Piyāvasi*, Maurya, Mahinda; as prince at Vessanagara, 26; ('hakravartī, 158, 159; recognised Buddhism, 15f. 77, his buildings and their style (cf. Barāhat) 3, 4, 17, 22, 23, 20, 33, 37, 66, 81, 87, 105, 115, 123, 137, 151; no nimbus, 80, his inscriptions 16; intercourse with Greek princes, 77, Greek influences in the style of his buildings, conf. Hippocampus, Makara, Centaur, 17, 52-53, 57, railing at Gayā, 23, 52, 53, 57; chapel round the Bodhi tree, 69; intercourse with Tissa, king of Ceylon, 25, 26, 70)
 Assyrians, — barbarities of this people, 16; their art, 19; gods placed upon their attributes, 57; cherubim, 50.
Asuras, 43.
Athenē, 82, 85, 213.
Athens, 9, 186.
Atlantes, 135, 165.
ātman, 12.
Auraugābhād rock-temples, 194.
aureole, see nimbus, 176.
Avalokiteśvara bodhisattva, see Padmapāni, — 183, 184, 193, 194n. 205; eleven-headed A. 203.
Aviddronidāna, see Jātaka, 13, 87, 96, 100, 102n. 159, 179.
aviyāga, girdle, 41.
Azes, 73.
- B.**
- Bacchanalian representation, 149.
 Bāgh caves, 22, 27, 193.
 Bagistan, Behistun, 16.
bahāgī, 66, 73.
 Baktrians, see Indoskythians, Gandhāra, Yueh-chi, 4, 76, 106.
 Bali, 31.
balikammam kar (Pāli) 11.
 Ball, V. 51.
 Bāmiyān, colossi, 83, 198.
Bānāras, see Bārānāsī.
 Barāhat, Bharhut, stone rail and gates, 23, 23, 44, 67n.; no figure of Buddha at B. 68, 167; the so-called *Kinnarajātaka*, 47, 48; inscriptions, 23, 80n. 58, 69; Hindū type, 34; dormer windows, 161; sculptures, 23, 141; gods, 40, 41, 42, 187; the bodhi tree, 69.
Bārānāsī (Skt. and Pāli) mod. 'Benares,' Hind. Banāras, scene of the Jātakas, 54, 55; Buddha's sermon at B. 67n. 68, 69, 143-144, 167.
 Barstam, 186n.
 Bayley (Sir B. Oliver) 82, 86n. 215.
Beal (Rev. S.) 44a. 64n. 66n. 72n. 170n. 204, 214.
Beḍ-ā, 22.
 Behistun, see Bagistan.
 Benāvatā Yakkha, 45.
 Bengal, 174; see Brahmasamāj
 Ben-ten, 105, 148n.
 Benagar, 26.
 Bhadrā, 143.
Bhagarata Sakamuniya bodhi, 69.
 Bhagwānlāl Indraj, 191n. 216.
 Bhājā, 22, 41.
bhāmāudala, *piabhāmāudala*, aureole, 86, 157.
 Bharhut, see Barāhat.
bhikkhu, 14, 114.
 Bhulā, see Sāñchi, Vidyā, 22, 21.
 Bhupāl, 24.
 Bhūmidevi 87n.
bhūmispāsa mudrā, 172.
 Bhūteśar, 41n.
 bignonia suaveolens, 181n.
 Bihar, caves, 22.
bimba fruit, 161.
 Bimbisāra, 4, 68.
 Bindusāra, 4, 15.
 Bingara, 105.
 Bloch (Dr. Th.) 141n. 155n. 173n. 216.
 Blonay (G. de) 98n.
bodhi, 143, 181.
bodhidharma, bodhi-tree, 14, 23, 26, 35, 69, 70, 74, 92, 92, 97, 100, 180.
 Bodhisattva, Pāli: bodhisatta, 23, 35, 61, 70, 134, 158, 173, 176, 181-185, 205, 211; B. in Jātaka, 54f., leaves heaven, 61; his dwelling, 105, 125; explanation of his words. 180; representations of B. 3, 4, 182ff. especially, 191-199; Vajrapāni, 91, 93, 94; their Saktis, 105; see Maitreya, Mahāsthānaprāpta, Mañjuśrī, Vajrapāni, Padmapāni.
 Borazan Buddha figures, 174n. 218.
 Boro Budur, 124, 167, 193.
Bōrpus, 84n.
 Bowring (Sir J.) 185n.
 brahman, world-soul, 12.
 Brahmā, representations, 87, 95n. 103, 112, 125, 139; voice of B. 161.
 Brahmādatta, 54.
 Brahmaloka, 195.
 Brāhmana, the highest caste of Āryas, 10ff.; representation of B. at Sāñchi, see *ashādāga*, Kāśyapa, *jatā*, *Asita*, 61-66, 139; representation of B. in Gandhāra, 75, 115, 122, 127, 140, 141, 155; Brāhmana philosophy, 9n. 12, 14; converted by Buddha, 14; magicians, 54; B. type for Brahmā. 87.
 Brahmanic art, 1n. 42, 147.
 Brāhmanī kite, 49n.
 Brahmanism, revival of, 76, 80, 81, 175.
 Brahmasamāj, 179.
 Buddha, see Gautama, Siddhārtha, Mayā, Prajāpati, Nirvāṇa, &c., the 'Enlightened,' 1, 148; legends of his youth,

- flight, 13ff. 129f. 130; about contemporary with Sokrates, 9; converts the Kāśyapas, 81ff. 126f.; B. and the Chakravartī, 90, 159, 'the great being,' see Mahāpuruṣa 159ff., pre-existence—see Jātaka, Bodhi-vatṭa; B. and the Nāgas, 48ff. 49, 94, 106; see Ādibuddha, Mānushibuddha, Dhyanibuddha; no figure of B. at Bāṭāhar, Gayā, Sāñicht; B. representations, 3, 68, 86, 87, 89f. 92, 116, 130f. 152f. 157, 163, 167n. see Udayana, Prasenajit; stories from his previous existences, 37; Māra's army and B., 94, see Nirvāṇa, 114, 118ff. 182-181, 189, 190, 195-197, 199; B.'s coffin, 209, 210; figure used decoratively, 152-154; *lakṣhaṇa*, 160f.; B. Maitreya, 186ff., 'fat-bellied Buddha,' 147.
- Buddhagayā, see Gayā, 14, 52.
- Buddhaghosa, 5, 90n.
- buddhahaldhala*, 61.
- Buddhapāda, 71, 72, 74.
- Buddhapanthon van Nippon*, 8n.
- Buddhism, 87n.; first universal religion, 9; extension, 3, 23, southern and northern schools, see Aśoka, Rājagṛha, &c.
- Buhler (Dr. G.) 13n. 18n. 25n. 216.
- bum-pa* (Tib.) and *djam-ba*, 186.
- Bunyu Nanjio, 196n.
- Burgess (Jas.) 18n. 20n. 27, 36, 37n. 38, 45n. 46n. 47, 72n. 79n. 83n. 90n. 95n. 6n. 103n. 118n. 122n. 123, 131n. 133, 137, 139-146, 149-150, 152-156, 179n. 182-184, 192, 194, 196, 202-203, 205.
- Burma, Burmese, 20, 23, 71, 77, 129, 175.
- Burnouf (E.) 39n. 46n. 187n.
- Byān-pa (Tib.) see Maitreya, 184, 181, 181, 186, 187.
- Byzantine elements in Gāndhāra art, 152.
- C.
- Caracalla's baths, 153.
- centaur, see Tiryagyoni, 18n. 52.
- Ceylon, see Tīssa, Anurādhapura, Vēddās, 2, 26, 70, 72, 80.
- Chaddanta elephant, 157.
- Chaitya, 20, 21.
- chakra*, Pāli: *chakka*; *chakkaṃ vatteti*, 158.
- Chakravātka Nāga, 43.
- Chakravātka, 158.
- Chakravartī, 168, 169.
- Chāḍukya, 29.
- Chandā Yakkhini, 41, 45, 111.
- Chandra, the moon, 130.
- Chandragupta, 4, 15, 76, 158.
- Chandrasena, Bābā, 178.
- Chang-an-lu, 168, 169.
- Changcha-Hutuktu, 8n. 52, 56, 57.
- chārpāṭi*, 118.
- Chaturmahārājas or Chaturmahārāpki gods, 61, 136, 147.
- chauri*, 60.
- chelulāḥkapa*, 35.
- cherub, 50.
- Chetiyaṅgiri, 26.
- Chhanna or Chhanāka, 1-3, 14, 103, 128, 155.
- chhatra*, 155.
- Chhorten (Tib. *mch'od-rten*), 20n.
- Chhos-hkhor (Ch'os-k'or) 151.
- chikha*, or cognizance, 193, 194n.
- chimæra, 18.
- China, 3, 27, 57, 66, 79, 157, 164, 170, 175, 201, 204, 205 [see Han, Ming-ti, Thien-ku, Mahāyāna, Kuang-yun, P'an-lu, K'ien-lin]; Ch. pilgrims, 79, 160, 190, see Fah-hian, Hsuen-thsang, Sung-yun; Ch. mythology, 213n.
- Christian art, 42, 68, 135.
- chronology, 4-6.
- Chulakoka devata, 111.
- Chunda, 114.
- clay-seal, 180.
- coffin of Buddha, 209, 210.
- coin-types, 138.
- Cole (Maj. H. H.) 83n. 89n. 94, 109, 118, 125, 128, 130, 136, 216.
- Copleston (Bp.) 18n. 114n.
- Corean dog, 51.
- Corinthian pillars, 139, 151, 152.
- cuneiform inscriptions, 62.
- Cunningham (Sir A.) 18n. 25, 40n, 41n. 45n. 57n. 69, 78n. 83, 137, 216.
- Curtius, 41n. 216.
- cymbals (*ṭīṭas*) 129.
- Cyrus, 4, 7, 158.
- D.
- dāgala* (Sinhalese) 20, 21, 185.
- Dahala, 77.
- Dākinī, 102n.
- Dakṣiṇapatha, Dekhan, 6, 27.
- Dalai-lama, 183, 206.
- Dardistan, 208.
- Darghabāzu, 162.
- Darius, Old Pers. Darayavaush, 4, 9, 10, 10, 158.
- Daulatabād, 84.
- David's (T. H. Rhys) 13n. 78n. 91n. 92n.
- Denne (Major H. A.) 103, 216.
- Dehli, Hind. Dillī,—pillar at, 17, 22.
- Demetrios, 101, 138.
- demi-gods, 43.
- demons, dwarfs, 35; see Māra.
- Des Guignes, 181n.
- deus ex machina*, 90.
- Deva, 7, 39, 48, 60; devamanussa, 42.
- Devadatta, 54-56, 88, 89.
- Devadāsī, 113n.
- Devaloka, 60, 195; see Suddhāvāsa.
- devaputra, Pāli: devaputta, 39.
- devatā, 48, 120.

dent, 73.

dharmachakkam pavattesi, 151.

Dharmār, 22.

Dhanada, Dhanapati, —Kubera, 136.

Dharma, Pāli dharmma, the truth or ritual, Buddha's teaching, 181; personified, 204n. 205; Dh. symbol of the early period, 19, 20, 67n. 128; see Bārānasi, Mṛigadāva.

Dharmachakra, Pāli dharmachakka, 67n. 74, 151, 159; dharmachakramudrā, 185, 187, 188n. 189, 193n.; *Dharmachakra Sūtra*, 144.

Dharmachārīn, 130.

Dharmapradīpikā, 161.

dhātu, dhātuyartha, 20.

dhōti (Hind.) 35, 186.

Dhṛtarāshṭra, 30n. 47n. 136.

dhyaṇa, 193, 200, 201.

dhyaṇamudrā, 193n. 194, 196.

Dhyānibodhisattvas, 193.

Dhyānibuddhas, 52, 193, 197.

Diamond throne (*rajātāsana*) 14.

Diadocha, 166.

Dionysos, 78.

Dīpankara Buddha, 142, 143.

Dīrgabāhu, 162.

Dīgyāddana, 68.

do-rje (Tibetan), *vajra*, 91.

Drāvida style, 53, 151.

drākṣid, grapes, 3 ln.

Drona, 15.

Dulca, 46.

Duruy Herzberg, 101n, 186n, 137n.

dvare adhirātkādevatā, door god, 46, 95.

dvārapālas, 46.

E.

Ehrenreich, 9n.

Elapātra Nāga, 43, 94.

Elliot (Sir W.) 26.

Elūra, 22, 52, 95, 196, 197.

eunatian, 195.

Eros, 47, 88, 95, 213; erotic figures, 149.

Etruscan art, 85.

Euhemerism, 79.

Eukratides, 77.

Euthydemos, 138.

Evans (E. P.) 41n.

F.

Fah-hian, 5, 79, 81, 91, 171, 190.

Fausbøll (V.), 53n.

Fell (Capt. E.), 25.

Ferguson (Jas.), 17n. 20n. 21n. 23n. 25, 27n. 41n. 83, 112, 128, 149, 153, 159n.

ficus religiosa, 161, 181n.; *F. glomerata* and *F. indica*, 181n.

Foism, 175.

Foucaux (Ed.), 100n.

Foucher (A.), 98, 137n. 147, 177n. 193n.

Fravash, Perseus, 195.

G.

Gabet (M.), 81n.

Gaia or Gē, 100, 213; see *Mahāprithvi*.

Galloic divinities, 137n.

gandhakṛtī, 46.

Gandhāra (Old Pers.) in Herodotos, Gandaroi, subject to the Achæmenides, 10, 75, 82; under the Indo-skythians, 79; proper designation for the sculptures instead of Græco-Buddhist, &c. 82; G. monasteries, 22, 77, 108, 123.

Gāndhār school (Gāndhāra is the adj. from Gandhāra) 221. 27, 75, 84, 98, 163ff., influence on Indian art, 156; painting, 27, 147, 169.

Gandharva, 43, 17, 136.

Gangā, Vināyaka, 183.

Gangā, river goddess, 45.

Gangita Yaksṣa, 45.

Ganymede, 108, 110.

garbha, 20, 155.

garlands, 148.

Gardner (P.), 86n. 138, 217.

Garuda, 7, 43, 48-52, 67, 58, 93, 94, 108-110, 123, 135.

Garutmant, 49.

Gautama, Pāli: Gotamh, 9, 13, 14, 23, 37, 60, 62, 64, 66, 68, 125, 128-131, 162, 179, and see under Buddha.

Gayā, see Asoka, Burma; 14, 22, 23, 41, 43, 52, 53, 68, 69, 73, 74, 97, 178.

Gē, see Gaia.

German mythology, 7.

ghunghru (Hindi), 111.

giganto-machia, 134.

Girnār, 16n.

Gnostics, 195.

Goblet d'Alviella, 19n. 188n. 217

Gondopharas, 5, 78, 84.

Græco-Bactrian kingdom, 42, 76, 77.

Græco-Buddhist, 22, 75.

Græculi, 98.

grape vine, 34, 150.

Greek influence, 57, 213.

Griffin, Gryps, or Gryphus, 50.

Griffiths (Jo.), 27, 97, 189n. 209, 217.

Growse (F. S.), 84n. 217.

Gubernatis (A. de), 49n.

Gupta, 5, 80; coins, 138n.

Guru, 89.

H.

Hampel, 93n.

Han dynasty, 79.

harya, 161.

Hardy (Sp.), 43n. 54n. 62n. 161n. 210n.

Hariiegameś, 52.

Hārīt, 103-105.

Hazār, 168.

Heliokles, 77.

Hellas, 165.

Hellenes, 8, 9, 86, 165; see Greek.

Herakles, Heronules, 82, 99.

Hermaios, 78.

Hermes, 137n.

Herodotos, 10, 34, 75, 82, 206, 213.

Hesur, 93.

Hettner (H.), 101n.

hi-ki-la, 114.

Hindlaya, 6.

Hinayana, 182, 191.

Hindu, 10, 82.

Hindi, 32, 35.

Hindû, 33, 35, 36, 160, 162, 163, 182; H. type, 85, 86, 103; Hinduism, 80; H. artists, 100; mythology, 182.

Hindustân, 6, 8.

Hippocampi, 57, 81.

Hirth (F.) 34n. 163, 175n. 217.

Hinen Tshang, 68, 79n. 80, 81, 85, 91, 171, 214.

Hoffmann, 124, 170n. 186n.

Hokusai, 51.

Holf, 95n.

Ho-shang, 147, 190n., Ho-tei, 147n.

Hti (Burmese), 20.

Huc (M.), 81n.

Hultsch (E.), 60n. 69n.

Huth (G.), 171n.

I.

Indo-China, 8; *see* Burma, Siam.

Indo-Hellenic, 82.

Indo-corinthian, 152.

Indo-Skythians, 76, 79, 137, 138, 208; *see* Kanishka, Yueh-chi.

Indhyâdri, 27.

Indra, *see* Sakra, 7, 38, 87, 90, 91, 94, 95, 140-142.

Indra-silla, 140.

Indra, 10.

Iranians, *see* Achaemenides, Persians, 6, 8; Masdayasians, 81, 158, 190, 195.

Isipatana or Sarnâth, 22, 143-145.

Islâm, 175.

Isidore, 206.

I-tsing, 6.

J.

Jaina mythology, 1n. 29, 43n. 181n.; *colosi*, 198n.

Jalandhara, 5, 79, 80, 100, 208.

Jamâlgarh, 23, 82, 86, 133, 150, 152, 154.

Jam-ba, *see* Hyams-pa.

Jampâ (Skt. Yâmunâ), 45.

Japan, 3, 6, 9, 27, 80, 93n. 99, 137, 157, 163, 169n. 170, 208, 213; *see* Ten-gu, Hokusai, Amitâbha, Tori-i, Ten-nio, Onis, Kariobinga, Ho-shang, Ho-tei.

Jatâ, 61, 87.

Jâtuka, *see* *Aviddharenidâna*, 37, 38, 43, 53, 60, 100, 142, 181.

Java, 31, 80, 124, 199, 200, 208.

jâna, Pâli-*dhâna*, 198.

Ji-koku.—*Dharmashâstra*, 136n.

Jiuna, 102n.

Johnson (Capt.), 25.

Julg (B.), 58n.

Jupiter, 91.

K.

Kâbul, 6, 10, 79;—*grapes*, 34.

Kadâni-kuki Khel, 190, 191.

kadamba, 32.

kâdôlei (Tamil), 83n.

Kadphises, 77.

Kâfarkot, 120, 121.

kakubha, 32.

Kakusandâ, *see* Krakuchohhanda, 74, 181, 188, 195.

Kalpa, 195.

Kalpavriksha, 31.

Kâna or Smara, 57, 95.

Kâmadevalokas, 38, 39.

Kâmaloka, 94, 95.

kamajidatu, 189.

Kâinâvachara, 60, 61.

Kamboja, 80, 175.

kamma (Skt. *karma*), 181.

kammavâchâ (Pâli), 107.

Kampeng Pet, 179.

Kanakaummi, Pâli: *Konâgama*, 74, 181, 188, 195.

kañchukâni, 129.

Kanheri, 22, 108, 143.

Kanishka, 5, 78, 79.

Kanjur (Tibet.) *ba'ka-hgyar*, 3.

Kantâkâ, 95, 102, 103, 123, 155.

Kâuva, 77.

Kapilavastu, Pâli: *Kapillavatthu*, 13, 15.

karanphâl (Hind.), 111.

kari (Tamil), *curry*, 114.

Kariobinga, 49.

Kârié, 22.

Karyanda, 10.

Kasâvara, K. 159n.

Kâ-limir, 77, 79.

Kâsyapa, Pâli: *Kassapa*, *see* *Uruvilvâ*, n *Brahminasa*, 62, 68, 65-69, 114, 115, 119, 122, 123-128, 140, 182, 189n. 210.

Kâsyapa Buddha, Gautama's predecessor, 74, 181, 188-190, 192, 193.

Katak, 22.

Kausambi, 149.

kârya, 68.

keidappu (MalayAl.), 32.

keorâ (Mar.), Skt.: *ketaki*, Hind.: *ketki*, 32.

Kern (H.), 15n.

kesara, 32.

Khundesh, 27.

Khotan, 138n. 169n.

Khyung: K'yun,—*Guruda*, 52; K'yun-shag-ohan, 94n.

ki-lin, 19n.

Kia-kan, 92n.

Kimpurusha, 43n. 47n.

Kinnaras, Kinnaris. 13, 43, 47, 48, 50;

Kinnarajâtaka, 47.

Kipling (J. L.), 193n. 150, 217.

Kishimoin, Hariti, 105.

Kodya, Koŷya, 13.

- Kohistan, 75.
 Kōmoka (Jap.) Virūpākṣa, 136n.
 Kōmāgamaṇa, *see* Kāṇakamuni.
 Korea, 6, 80, 168; K. dog, 51.
 Kōsala, 10, 15, 68n. 69, 171.
 Krakuchchihanda, *see* Kakusandha, 181, 188, 195.
 Kṛm-shis-lhun-po, 205.
 Kriophoros, 135-136.
 Kṛishnā river, 26.
 Kṛishna=Māra, 80.
 krobyle, 86, 87, 115, 211, 212.
 Ktesias, 51, 58, 213.
 Kuin-yin, 201, 204.
 Kubera or Kuvera, 40n. 41, 45, 186, 127.
 Kubhā river, 75.
 Kuhu (E) 81.
 Keki-Ryūichi, 1n.
 Kumbhāṇḍar, 136.
 Kural, 40.
 Kurumbars, 53.
 Kūshan tribe, 77, 78.
 Kusinagara, Pāli: Kusinārā, 15, 115, 119, 122, 144n. 210, 211.
- L.
- Lahor, 83, 95, 96, 98, 105, 106, 145, 146, 212.
 lakṣhanas, 161, 162.
 Lakshmi, 37n. 39, 188.
 Lālitavajra, 56.
 Lalita-Pistara, 98, 101, 131n. 161, 179, 213.
 Lālitavayūha, 130.
 Lama, Tib. A-lā-ma, 'superior,' conf. Pal-dan-ye-she, Lālitavajra, 56, 117, 193, 203-207.
 Lamaisin, 35, 57, 68, 80, 105, 175, 185, 187.
 Laos, 175.
 Lassen (C.) 10n. 58n. 78n.
 Lat, 20, 22, 26.
 Lateran museum, *see* Kriophoros, Sophokles, 135, 189.
 Le Bon (A.) 23n.
 Leithner (Dr.) 83n. 217.
 Leuchters, 108, 109.
 Lha-so, 92n.
 Lokapāla-devatā, 40n. 137, 138, 147, 190n.
 Longimanus, 162.
 Loriyan-Tungai, 23, 102, 107, 119, 120, 131, 132, 140, 141n. 148, 153, 154, 156, 202, 203, 210, 211.
 lotā (Hind.) 59, 63, 127.
 lotus, 19. *see* Padma, Nelumbium.
 Lumbini, 111, 113, 125, 143n. 155.
- M.
- Macedonian empire, 9, 158.
 Mackenzie (Col. C.) 26.
 Madagask (Sir H.) 23.
 Mahāra, 46, 53.
 Magadha, 10, 14, 15, 68, 76, 158.
 Magadhi, *see* Pāli, 80.
 Maghavā=Sakra, 38.
 Maṇabāhu, 162.
 Mahābhiniṣkramana, 101, 103.
 Mahābodhi, 57n.
 Mahābrahmā, 38, 39; *see* Brahmā.
 Mahākṛtyāyana, 94n.
 Mahāmātī, Mañjuśrī, 184.
 Mahāpaddhāna sūtra, 161.
 Mahāparinirvāṇa, 117, 119; *see* Nirvāṇa.
 Mahāprithivī, Pāli. Mahāpāthivī; *see* Gaia, 100, 128, 213.
 Mahāpurusha, Pāli: Mahāpurisa, 159, 161.
 Mahārājā, *see* Chaturmahārājā, 43, 146.
 Mahāsthānuprāpta, Mahāsthāna, 183-185, 193n. 194n. 195, 196n. 205.
 Mahaut, Mahāvat, 60, 72, 73.
 Mahārasa, 26, 77, 181.
 Mahāyāna, 80, 147, 182, 190, 199, 205.
 Mahinda, Skt. Mahendra, 26, 70, 74.
 Mahorāga, 43.
 Maidari (Mong.), Maitrayu, 186.
 Maiser (Col. F. C.) 25, 217.
 Maitreya, Pāli: Metteyya, Tib. Byami-pa, 5, 61, 79, 81, 146, 147n. 181, 182, 186-193, 195, 196n. 197n. 198, 205; *see* Miroku, Miryek.
 Majjhantika, Skt. Madhyāntika, 77.
 Makara, dolphin, 41, 53, 57, 73, 81, 95.
 Malabar, 32, 36.
 Mālabhārī, 39.
 Mallā, 15, 122.
 Mandhava, 115, 120.
 māṅgalakālās, 186, 192.
 Mani, Manichaeism, 5, 81.
 Manikya, 23, 82.
 Mañjuśrī, Mañjughosha; *see* Sarasvatī, Mahāyāna, Adityavarmā, 57, 105, 182-185, 196n. 199-201, 203, 204.
 Manu, 40n.
 Mānushibuddha, 195.
 Māra, *see* Vāsavartī, Namuchi, Pāpīyān, Devadatta, Sakra, 14, 38, 39, 61, 82, 88-90, 92, 94-97, 100, 103, 159; Mārīkāyikas, 39.
 Marāṭhī, 82.
 Maravatti, 82.
 Marco Polo, 15, 71n.
 Mardonios, 10.
 Mars, 93.
 Masdayasnian, 195.
 Masson (C.) 8.
 Mātali, 88.
 Mathurā, 22, 23, 34, 41n. 82, 141-142, 174.
 Matsyānārī, 45, 81.
 Maṇḍalyāyana, 182, 183, 211.
 Maues, 78.
 Maurya, Pāli: Mora, *see* mayi-ra, 15, 70, 158.

Māyā, 13, 60, 100, 110-113, 117, 125 135, 130, 155.
mayura, Pali: *mora*, peacock, ensign of the Maurya-dynasty, 15, 70.
 Medes, 4, 10.
 Megabases, 162.
 Megasthenes, 4, 5, 34, 76, 82.
 Megha or Sumedha, 143.
 Menandros, *see* Miñḍa, 5, 77, 78.
 Mercury, 93.
 Meru, 43, 136.
 Mihirakula, 80.
 Miñḍa, *Miñḍa-panha*, 54n. 78.
milvusops elengi 32n.
 Minayeff (I. P.) 36n. 40n. 217.
 Minākshi, 40.
 Ming-ti, 79.
 Miroku, Maitreya, 186n.
 Miryek, Maitreya, 198n.
 miscellaneous sculptures, 139-147, 149-150, 152-156, 209-212.
 Mogas or Maues, 84n.
 Mongolia, 9, 31, 208; *see* ojir, Maidari.
 Mora, *see* Maurya, *mayura*, 158.
mrīḍat, *mrīḍikā*, 34n.
Mṛigadāva, *see* Sārṇāthā, 143.
 Muchilinda Nāga, 43; tree, 90.
mudrā, 172, 177, 187, 189, 192-194, 196.
 Muhammadans, 29.
 Muḥammad Nāri, 128, 130, 135, 174, 138.
muḥuta, 184, 203.
 Müller (F. W. C.) 52n. 214.
muṣṣu (Tamil) 24.
 Musagetes, *see* Apollo.
 Mya-ngan-das (Tibet.) *see* Nirvāṇa, 123.

N.

Nāch girls, 111, 112, 213.
 Nāga, Nāgī, Nāgakanyā, 29, 41-46, 50, 37, 63, 94, 106-108, 110, 120, 123, 131, 133n. 136, 208, 209; N. in the hand, 136n.
 Nāgabhoṣhana, Nāganītha=Śiva, 43.
Nāgananda, 49n. 108.
 Nāgarjuna, 5, 26.
 Nagy Szent Miklós, 93n.
 Nāgamēya, 52.
 Nāraṅgaṇa, 64.
nakula, Tibet. *neu-le*, 137.
 Nalā, 210.
 Nālāgiri, 54.
 Nālānda, 53, 175.
 Namuchi, 39.
 Nanduka Yakkha, 45.
nandydvarā, 162.
 Nāraka, 46.
 Nārāyaṇa Swāmī, 179n.
 Nar-thing, 8n. 198n.
 Nāsik, 5, 22, 45, 73, 211.
 Nattūn, 23, 89, 111, 118, 121, 122, 186.
navula kadamba, 32n.
 Nāyyarchohis, 32, 86.
netumbium, 19, 182; *see* *pāṇma*.

Nemæan lion, 82.
 Nepāl, 20n. 53 60, 155, 175, 176, 186-187, 199.
 Nga-ri-Khor-sum, 133, 134.
 Nicodemus, gospel of, -201n.
 Nikā, 112, 113, 153, 213.
nimbus, 80, 95.
 Nirmānarati, Skt. Nirmānarati, 61.
 Ni-ā, 95n.
 Nippon, 124.
 Nirvāṇa, 15, 39, 43, 68, 89, 113ff. 118n. 119-124, 144, 160, 172, 181, 193, 207.
 Northcote (Spencer) 135.
Nyagrodha, *see* Indica, 181n.

O.

ojir, 91n.
 Oldenberg (H.) 9n. 13n. 67n.
 Oldenburg (S. von) 174n. 187n. 192, 193, 194, 217.
 Oldfield (H. A.) 105n.
 Onis, 99.

P.

padah, 67.
pādapītha, 129.
padma, lotus, 19.
 Padmanābha, Viṣṇu, 183.
 Padmapāni, 184, 191n. 192-195, 199, 201, 208-209; *see* Avalokiteśvara.
 Padmasambhava, 92n.
padmāsana, 108, 165, 167, 172, 194, 203, 206, 211.
 'P'ag-skyes-po, Skt. Viṇūdhaka, 138.
 Paigña, 148-150, 213.
 p'ai-lu, or p'ai-fang, 21.
 Pal-dān-ye-she, dPal-/dan-ye-she, 205.
 Paleologue, 213n.
 Pālī or Māgadhi, 7, 10, 13-15, 20, 39, 62, 70, 79-80, 153 159, 181, 195, 208.
 Palimbothra, Pāṭaliputra, 76.
 Palmyra, 5.
 pandanus odoratissimus, 32n.
 Pāñchāśikha, 141, 142.
 Pāñchika, 104n.
 Pander, 187n.
panidim kar (Pālī) 181.
 Panjāb, 6, 7, 8, 11, 79, 208.
 Pannagas, Nāgas 47n.
pānsāla, 140.
 Pāpīyān, *see* Māra, 39.
 Parsclete, 61.
 Parānirmitavāsattī, Skt. Parānirmata-vaśīvartin, name of a heaven, 36, 61.
parinirvāṇa, *see* Nirvāṇa, 4.
parna, 43.
 Pāst, 190.
 Pārivaṇṣītha, 52.
pātali,—bignonia suaveolens, 181n.
 Pāṭaliputra, Gr. Palimbothra, modern Patna, 76, 77, 82; *see* Megasthenes, Afoka.
 patera, 126, 128.
 Pātā, 76, 82.

- paṭra*, alms-bowl, 126, 128, 133n. 134, 146.
Pāva, 15.
Pequ caves, 197n.
Pekin, 57, 186, 187.
pentaptera arjuna, 32n.
Pergamon, 184, 185.
Persepolis, 17.
Persians, 9, 10, 21-22, 151, 190, 195, 218;
Persian style, 16-17, *see* *Achæmenian*,
Zoroastrian, 93n.
Peshāwar. *Purnshapura*, 83, 151, 212; *see*
Jamālgarh, *Takht-i-Bāhi*.
Pfungst (A.) 133n.
pigmies, 35, 58.
Pippala—*ficus religiosa*, 181n.
Pisuna=*Māra*, 39.
Pitāmaha=*Brahmā*, 39.
Piyadasi (Pāli), *Skt. Priyadarśi*; *see*
Asoka, 15, 16.
Platæa, 10.
Plato, 9.
Plutarch, 78.
Pozdnev, 97n.
Prabhānandala, *see* *bhānandala*, 86.
pradakṣiṇa, 21.
Prajapati, 13, 111, 125, 135.
Prajñāka, 104.
Prajñāparamitā, 204.
Pra K'odom, 179.
Prākṛit, old Indian popular dialect, 208.
Prasenajit, *Pāli*: *Pasenadi*, 68n, 69, 171.
Prasoi (Gr.) *Prāchyā*, "the easterns," 15,
 78.
Price, 153.
Prithivī, *Pāli*: *Pathavi*, *see* *Mahāprithivī*,
 98, 101.
Proikonnēsos, 34, 206n.
Ptolemy Philadelphos, 77.
piṭṭa, 10, 11.
Pulumayi, 26.
pundarika, 181n.
Purāika Yakkha, 45.
Purnshapura, *Peshāwar*, 76n. 83.
Pushya, 131.
P'ya Tāk, 102, 103.
Pythagoras, 9.
- R.
- Rāhula*, 13, 14, 95; *Rāhulānāṭa*, 13.
Rājagṛha, *Skt. Rājagṛha*, 14, 15, 104.
Rājā Pāsenadi Kosalā, 69.
Rājendralāla Mitra, 18n. 52, 69n. 97, 217.
Rāmagrāma, 15.
Rāmañāṇḍava, 197n.
Rānt-ka nār cave, *Orissa*, 23.
Ratnapāri Bodhisattva, 184, 195.
Ratnasambhava, 184, 193.
rat. 34n.
Rigveda, 7, 8, 34.
Ritayamātra, 32.
Rōkūhū (W. J.), 16n, 36n. 44, 46n. 122n.
Rōkūhū
Rōkūhū *matamara* 61.
- Rohini river*, 13.
Rome, 84, 100, 147, *Romo-Cornithian*,
 152.
Rouse (W. H. D.) 53n.
Rudra=*Siva*, 94.
Rūpāvacchara, 39.
- S.
- Sabbaddātha-jātaka*, 53f.
sacred places, 143n.
Sāchi, 38.
Sāddhanumāla, 4.
Sāgara, 146.
Sahampati=*Brahmā*, 39.
sahasrabāhu, 204.
Sahasraneto=*Sakra*, 38.
Sākala, 77.
Sakka or Sakra, *Indra*, 7, 8, 38, 47, 61,
 87, 90, 91n. 94, 112, 125, 133n. 140, 145,
 155, 182, 192.
Sakti, 105; *see* *Sarasvatī*, 183.
Sākya Muni, *see* *Buddha*, *Gautama*, 9, 143.
Sāla (Pāli), *Skt. Śāla*, 111, 119, 121, 161n.
Samantabhadra, 182, 184, 195.
Sam-ye, 92n.
Sānchi, 5, 17, 18, 19, 21-26, 29, 33-39, 41,
 42, 47-50, 58, 59, 62-71, 72-74, 87, 111,
 115, 126, 157, 191; *measurements*, 72n.
Sangala, *Sānkala*, 77.
Saṅgha, 205.
Saṅghamittā, 26.
Saṅghāo, 23, 86, 94, 109, 118, 188.
Saṅkhaśāla, 49n.
Sankisa, 22.
sansāra, 12, 197.
Sanskrit, 80.
Sasabyant, 190.
sapta-padda, 139.
sapta ratnāni, *Pāli*: *satta ratanāni*, 169.
Sapta Tathāgata, 183.
Sarasvatī, 105, 106, *Jap. Den-ten*, 148n.
 183.
Sāriputta, *Skt. Śāriputra*, 182, 211.
Sarnāth, 22, 148; *see* *Isipatana*.
Sarvāstivādin school, 80.
Sātāgata Yakkha, 45.
Sātākarni, 25n.
Satakratu, *see* *Sakka*, 139.
Satamanya, *see* *Sakka*, 90.
Sātāpāni, *Skt. Sātāparṇa*, 15.
saṭṭa, *Pāli*: *satta*, 181.
Sāvatti, *Skt. Śrāvastī*, 10.
Scherman (L.) 9.
Schiefner, 94n. 95n.
Schlagintweit (E.) 187.
Selenkos Nikator, 4, 76.
Senari (E.) 16n. 79n. 84, 103, 218.
Se-ra, 92n.
Shāhderi, 23.
Shahr-i-Bahlol, 83.
Shā-kya-thub-pa,—*Sākya-Buddha*, 123.
Shān people, 175.
Shen-fai 107n.

- Sher-p'yin-ma, 201.
 shores robusta, 181n.
 Siam, Siamese, 31, 80, 103, 175.
 Siddhas, 47n.
 Siddhārtha, Pāli: Siddhatta, Gautama, 4, 9, 13, 113, 145.
 Sihalaḍḍipa, Skt. Simhaladvipa, Ceylon, 70.
 Sikh, 159.
 Sikhī Buddha, Pāli: Sikhī, 74, 181, 188.
 Sikri, 103, 140.
 Silenos, 34, 82, 86, 139n, 213.
 Simha, 5, 80, Bodhisattva, 184.
 Simhanāda, 169n.
 simhas, 165.
 simhāsana, 136n.
 simhastambha, 20.
 Simpson (W.) 18n, 152, 218.
 sumurg, 48.
 Sindhu river, 10.
 Singalese, 20, 26, 114n, 181.
 sirens, 47.
 Sīrī (Pāli), Skt. Śrī, see Lakṣmī, Tirumagal, 37, 39, 40, 74, 105, 198; Sīrīmā devatā, 40, 41.
 śrīśa, ficus religiosa, 181n.
 Śiva, 43, 72n, 94, 138n.
 Skylax, 10.
 Smara, — Kāma, 95.
 Smith (Vincent A.) 82-84, 125, 131-135, 138n, 152, 218.
 Soan-to river, 83.
 Socrates, 9.
 Sophocles, 180.
 Soṇa-h, Soṇalyant, 190.
 Śrīvasta, Pāli: Śāvatthi, 10.
 Śrīvatsa figure, 102.
 Stambha, 20.
 Stem (M. A.), 79n, 218.
 śhanvira, 46, 205, 210.
 Sthūvara, Prithivī, 101.
 stotra, 93.
 Strabo, 91.
 stūpa, 15, 19-26, 29, 34, 36, 58, 59, 67, 71, 180, 187, miniature Stūpas 154-156.
 Subhadra, Pāli: Subhadda, 115, 122.
 Subhāvastu, Swāt river, 43.
 Subuloma Yakkha, 45.
 śūdra, 21, 41.
 Suddhavaśa, Pāli: Suddhavaśa, 60n.
 Suddhodana, 14, 139, 155, see Buddha.
 Sujātā, 73.
 Sukhāvati, see Amitābha, 170, 195; Sukhāvatī-i-gāha, 194n.
 Sulis, 93.
 Sumnakkāśa, 72.
 Sumedha or Megha, 142, 143.
 Sunga dynasty, 77.
 Sung-yun, 5, 81.
 Supārā, 191.
 Suyama, — Garuḍa, 48, 49.
 Suparva Yakkha, 45.
 Sūrya, 41, 130.
 Susu, 17.
 Sūtras, buddhist, see Jātaka, 7, 37, 38, 41, 49.
 Suvāstu, Swāt river, 83.
 Sven Hedm, 174n.
 svastika, 162.
 Swāt, Subhāvastu, 23, 43, 83, 115, 125, 138, 140, 141, 144, 169, 171, 182, 186, 189, 190, 211.
 Syrian kingdom, 76.
 T.
 tābīj, tā'wiz, 116.
 takka, takkei, 32.
 Takht-i-Bāhi, 23, 85, 117, 163, 164, 167, 170, 174, 185.
 tāla, 129.
 Tamil, 32, 35, 40n; see Kural, Tiruvalluvar, Tirumaga, aram, maudu, takkei, sokkī.
 Tanjor, 113n.
 Tanjur, Tib. b-Tan-gyur, 3.
 Tantra, 190, 213.
 Tārā, 93n.
 Tārānātha, 81n, 174, 203.
 Tathāgata, 46, 180.
 Taurus, Skt. Jāvuri, 130, 131.
 Tāvatisa, Skt. Trayastriṃśat, 38, 61, 90, 182.
 Taylor (Col.), 25.
 Temple (R. C.) 197n.
 Ten-gu, Garuḍa, 51.
 Tennant (Sir E.) 72n.
 Ten-nin, 49.
 thambha, Skt. Stambha, 20.
 Theodoros inscription, 84.
 Thien-kon, Garuḍa, 51, 52.
 Thomas (St.) 78.
 thrones, 28, 29, 53, 56, 57.
 thupa, Skt. stūpa, 20.
 Thurston (E.) 33n.
 Tibet, Tibetan, 3, 6, 9, 27, 31, 68, 80, 105, 110, 136, 175, 185-187, 192, 201, 206; Tibetan dog, 51.
 Tin-thil at Elurā, 196, 197.
 Tirhut, 22.
 tirtha, 62.
 Tirthakas, 122.
 Tirthamkars, 48n, 181n.
 Tiruvaga, Skt. or Bhāmidevi, 37, 40.
 Tiruvallavar, 40n.
 Tiryagyoni, 18n, 52, 58.
 Tissa, 26.
 Tomaschek, 200n.
 torana, 21, 28; tori-i (Jap.) 21.
 Trailokya, 89.
 Tra-shi-lhum-po, 205, 206.
 trees of the Buddhas, 181n.
 Trikha, 43.
 Tripitaka, 5.
 tridulān or triad, 183.
 tridula, 92, 145.
 Turukkas, Turks, 79.
 Tushita, Pāli: Tusita, 61, 132.

Tyche or Fortune, 40.

U.

Udayagiri, in Orissa, 22, 23; in Malwa, 40, 41.

Udayana, 68, 170-172, 213.

Udyāna, Pāli: Ujjāna, Gr. Suastēni, 13, 76, 80.

Udumbara, flos glomerata, 181n.

Ujjayini, 26.

Ujjeniya, son of Asoka, 28.

U-K'ong, 80.

Upāvana, 122.

Uraeus, 44.

Urud, Pāli: *uruma*, 161, 162, 166, 182.

Urūvilā, Pāli: Urūvelā, 14, 62, 64, 65, 78, 126-128.

uskutaka, 161, 162, 164, 211, 212.

Ushalekhaviya, Tib. *gTsug-tor-rnam-par-rnyal-ma*, 204.

Utpala flower, 143.

Uttarāshukha, 181.

V.

vdhana, 40n. 41n. 87.

Vaiśālika school, 80.

Vairocana Buddha, 195.

Vaiśākha unkhatura, 130, 131.

Vaiśāli, Pāli: Vesālī, 15.

Vairāmanā, Vairāvana, 136, 148n.; see Kubera.

vajra, 38, 90, 92n. 93, 139, 140, 155, 192.

Vajrapāni, Sakra, 38, 90, 91, 93-95, 103, 108, 118n. 120, 121, 125, 184, 185, 195, 197, 203.

vajrasana, 14, 100, 143n. 172.

Vajrayudha, 38.

Vallée Poussin (L. de la) 113n.

vardhamāna figure, 162.

Vāsavo, —Sakra, 38.

Vāsavartī, Pāli: Vāsavattī, 39, 97.

Vāsishtha, 26n.

Vassilief (V.) 95n. 190n.

Veda, vedic, 7, 8, 38, 49, 54, 105, 158.

Veddās, 72.

Vejayana, 38.

Vessabhū (Pāli), Skt. Viśvabhū, 74, 181, 188.

Vessānagara, mod. Resnagar, 28.

Vesādhpa, 15.

Vidā, Bhīṣa, 24.

Vidyadhara, 47n.

viśāra, 15, 20, 21.

Vikantaka Bodhisattva, 184.

Vikramāditya, 53, 74.

vīnd, 105.

Vipāsyī, Pāli: Vipassī, 74, 181, 188.

Virūdhaka, 40n. 15, 136, 138.

Virūpāksha, 13, 138, 183.

Vishnu, Vamshavā mythology, 1n. 37n. 72, 159.

Viśvabhū, see Vessabhū.

Viśvakarma, 95.

Visvanāra Jātaka, 150.

Visvaptu, 184, 185.

vijānga, girdle, 41.

W.

Waddell (Dr. L. A.) 105n. 177n. 194n. 218.

Wei-chi-f-song of Khotan, 108.

wheel symbol, 145, 161, 158-159.

woman in sculpture, 36.

wood-carving, 29-30.

Wu-t'ai-shan, 197n.

X.

Xerxes, 4, 10.

Y.

Yaksha, Pāli: Yakkha, 36, 40n. 11, 13n. 43, 46, 73, 95, 102n. 103, 104, 111n. 136, 137, 208.

Yakshini, Pāli: Yakkhini, 11, 43n. 104, 111.

Yāna, 114.

Yamunā, mod. Jamunā, 45.

Yavana, Greeks, 77; Yavānā, 116, 128, 130.

Yasodharā, 13.

Yazdigard, 81n.

ye dharmā ketuprabhādh, 178.

Yeld (Dr.) 25.

Ye-tha or Sakas, 78.

Yogachārya school, 184.

Yoginis, sorceresses, 111.

Yonaka, Yavana, 77.

Yueh-chi, 76, 77, 79, 80, 208.

Yule (Col. H.) 71n. 170n.

Yūsufai, 23, 82, 110.

Z.

Zarathushtra, Zoroaster, 165.

zebu, on pillars, 151, 152.

Zeus, 91, 93, 213.

Zōchō-tanno (Jap.) Virūdhaka, 136n.

Zoroastrians, see Ferver, Masdayasniari, Sosiosh, Mani, 81, 195.

CORRIGENDA.

Page 15, line 11 from bottom, read *Prāchyā* for *Prachya*.

„ 20, note 2, read *mChhod-rten* for *mChod-rten*, and *gDun-rten* for *mDun-rten*.

„ 21, l. 21, „ *p'ai-lus* or *p'ai-fangs* for *pai-lus*.

„ 25, l. 17,—see p. 72, note 2.

„ 32, l. 6 from bot. read 25 for 22.

„ 100, under illust. read—Barberini; and in note 2, read *Materialien*.

„ 101, note, read *Merten* for *Murten*; S. 587 for S. 58; and *römischen* for *römisches*.

„ 102, note, read *Dākinis* for *Dākinis*.

„ 103, l. 17, for “the Vedas . . . vessel” read—“and with two silver vases which contain ‘the three robes’ and the almsbowl for the newly ordained monk, exactly in the modern Siamese fashion” (A. Grünwedel).

„ 103, note 3, read a sketch by for the sketch of.

„ 105, l. 13 from bot. read *Siri* for *Siri*.

„ 109, l. 4 „ „ *Nāgānanda* for *Nāgānanda*.

„ 112, ll. 4 and 6, read *Māyā* and *Māyādevi*.